Shasta County Bridge Preventative Maintenance Project List

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft^2)	Total Particip. Cost	Unit Cost ($\$/ft^2$)	Federal Share	Running Fed Summary	Local Share	Running Local Share
1		Shasta County	Develop next year's BPMP								1.00	15,000	15,000	13,280	13,280	1,721	1,721
2		Shasta County	6C-52	7G23-B	Lakeshore Drive	Doney Creek	0.8 mi SW Antlr UC on I-5	51.5		Bridge Deck Seal	12,598	124,000	9.84	109,777	123,057	14,223	15,943
3		Shasta County	6C-54	7G23-A	Lakeshore Drive	Charlie Creek	1.8 mi SW Antlr UC on I-5	66.0		Bridge Deck Seal	10,103	101,000	10.00	89,415	212,472	11,585	27,528
4		Shasta County	6C-18	2J5-A	Dersch Road	Cow Creek	0.7 mi E Deschutes Road	96.8		Embankment Erosion Control	6,480	50,000	7.72	44,265	256,737	5,735	33,263
5		Shasta County	6C-101	3J14-A	Old 44 Drive	South Cow Creek	0.5 mi N of S.R. 44	93.5	SD	Methacrylate Treat. / Joint Seal	7,731	45,000	5.82	39,839	296,576	5,162	38,425
6		Shasta County	6C-258	4H34-B	Old Alturas Road	Stillwater Creek	0.1 mi E Old Oregon Trail	86.2		Methacrylate Treatment	3,793	25,000	6.59	22,133	318,708	2,868	41,292
7		Shasta County	6C-346	3N11-A	Mountain Meadow R	Battle Creek	0.1 mi E Thatcher Mill Rd	66.9	SD	Methacrylate Treatment	936	20,000	21.37	17,706	336,414	2,294	43,586
8		Shasta County	6C-41	2J7-A	Deschutes Road	Sacramento River	1.0 mi S Dersch Road	98.3		Methacrylate Treatment	27,556	100,000	3.63	88,530	424,944	11,470	55,056

RECEIVED BY
JUL 22 2009
DISTRIC
LOCAL ASSIS