BID OPENING DATE 04/24/13 IN KERN COUNTY NEAR EDISON AT 04/25/13
CONTRACT NUMBER 06-0N4014 NEUMARKLE ROAD UC CONTRACT CODE 'B '
LOCATION 06-KER-58-67.8 25 CONTRACT ITEMS

CONSTRUCT ROCK SLOPE PROTECTION FEDERAL AID NH-17D5-(004)E

DB GOALS: DISADVANTAGED BUSINESS ENTERPRISE - 6.0%
PROPOSALS ISSUED 9 FUND TOTAL HA23 0 TOTAL NUMBER OF WORKING DAYS 35

NUMBER OF BIDDERS 4 ENGINEERS EST 438,790.00 AMOUNT UNDER 51,007.00 PERCENT UNDER EST 11.62

BID RANK	BID TOTAL	BIDDER ID	BIDDER INFORMATION (NAME/ADDRESS/LOCATION)	
1	387,783.00	1	GRIFFITH COMPANY 1128 CARRIER PARKWAY AVE BAKERSFIELD CA 93308	661 392-6640 00000088 FAX 661 393-9525
2	401,348.00	2	SUMMER CONSTRUCTION INC P O BOX 30 SANTA PAULA CA 93061	805 933-9364 00597494 FAX 805 525-3000
3	447,467.00	3	GRANITE CONSTRUCTION COMPANY P O BOX 5127 BAKERSFIELD CA 93388	661 399-3361 00000089 FAX 661 399-3598
4	476,890.00	4	CIMARRON INC 929 OBYRNES FERRY ROAD COPPEROPOLIS CA 95228	209 522-1655 00827599 FAX 209 522-1652

S U M M A R Y O F R E M A I N I N G B I D D E R S

L I S T O F S U B C O N T R A C T O R S

BIDDER ID	NAME AND ADDRESS	DESCRIPTION OF PORTION OF WORK SUBCONTRACTED
01	BLUE IRON INC NEWPORT BEACH CA 92660	SHEET PILING
	J & M LAND RESTORATION BAKERSFIELD CA 93308	EROSION CONTROL & COMPOST & FIBER ROLL

S U M M A R Y O F R E M A I N I N G B I D D E R S

L I S T O F S U B C O N T R A C T O R S

BIDDER ID	NAME AND ADDRESS	DESCRIPTION OF PORTION OF WORK SUBCONTRACTED
02	AUSTIN ENTERPRISE BAKERSFIELD CA	ITEMS 2, 4
	BLUE IRON NEWPORT BEACH, CA	ITEM 17
	GENI OAKLAND CA	ITEMS 1, 5, 6
	J&M LAND RESTORATION BAKERSFIELD CA	ITEMS 8, 15, 16
	MENDEZ CONCRETE INC SANTA PAULA CA	ITEM 18
	SOUTH VALLEY TRANSPORT INC BAKERSFIELD CA	ITEMS 21, 22, 23, 24

BIDDER ID	NAME AND ADDRESS	DESCRIPTION OF PORTION OF WORK SUBCONTRACTED
03	AUSTIN ENTERPRISE BAKERSFIELD CA	CONSTRUCTION AREA SIGNS, TRAFFIC CONTROL
	BLUE IRON INC WEST SACRAMENTO CA	STEEL SHEET PILING, INSTALL ONLY
	J&M LAND RESTORATION BAKERSFIELD CA	EROSION CONTROL, TEMP FIBER ROLL

S U M M A R Y O F R E M A I N I N G B I D D E R S

L I S T O F S U B C O N T R A C T O R S

BIDDER ID	NAME AND ADDRESS	DESCRIPTION OF PORTION OF WORK SUBCONTRACTED
04	ACACIA EROSION CONTROL INC SANTA BARBARA CA	ITEMS 15, 16
	BLUE IRON INC WEST SACRAMENTO CA	ITEM 17
	NLS TRUCKING INC	ITEMS 21 THRU 24

ITEM NO.	ITEM CODE	ITEM DESCRIPTION	UNIT OF MEASURE	ESTIMATED QUANTITY	BID	AMOUNT
1	070030	LEAD COMPLIANCE PLAN	LS	LUMP SUM	1,365.00	1,365.00
2	120090	CONSTRUCTION AREA SIGNS	LS	LUMP SUM	1,250.00	1,250.00
3	120100	TRAFFIC CONTROL SYSTEM	LS	LUMP SUM	14,438.00	14,438.00
4	128652	PORTABLE CHANGEABLE MESSAGE SIGN (LS)	LS	LUMP SUM	440.00	440.00
5	130100	JOB SITE MANAGEMENT	LS	LUMP SUM	125.00	125.00
6	130200	PREPARE WATER POLLUTION CONTROL PROGRAM	LS	LUMP SUM	900.00	900.00
7	130620	TEMPORARY DRAINAGE INLET PROTECTION	EA	1	1.00	1.00
8	130640	TEMPORARY FIBER ROLL	LF	400	3.84	1,536.00
9	130710	TEMPORARY CONSTRUCTION ENTRANCE	EA	1	1.00	1.00
10	130900	TEMPORARY CONCRETE WASHOUT	LS	LUMP SUM	320.00	320.00
11	150812	REMOVE PIPE (LF)	LF	24	14.75	354.00
12	160102	CLEARING AND GRUBBING (LS)	LS	LUMP SUM	2,250.00	2,250.00
13	190101	ROADWAY EXCAVATION	CY	50	137.86	6,893.00
14	198010	IMPORTED BORROW (CY)	CY	130	51.50	6,695.00
15	210210	EROSION CONTROL (DRY SEED) (SQFT)	SQFT	26,500	.08	2,120.00
16	210600	COMPOST	SQFT	26,500	.27	7,155.00
17	490801	STEEL SHEET PILING	SQFT	4,450	28.60	127,270.00
18 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	13	585.00	7,605.00
19	665024	24" CORRUGATED STEEL PIPE (.109" THICK)	LF	24	103.00	2,472.00
20	705015	24" STEEL FLARED END SECTION	EA	1	154.00	154.00
21	720118	ROCK SLOPE PROTECTION (2T, METHOD A)	CY	680	90.75	61,710.00
22	721019	ROCK SLOPE PROTECTION (NO. 3, METHOD B) (CY)	CY	35	89.00	3,115.00
23	721022	ROCK SLOPE PROTECTION (1T, METHOD B)	CY	1,680	79.25	133,140.00
24	721026	ROCK SLOPE PROTECTION (NO. 1, METHOD B) (CY)	CY	6	127.00	762.00
25	729011	ROCK SLOPE PROTECTION FABRIC (CLASS 8)	SQYD	2,380	2.40	5,712.00
					TOTAL	387,783.00

S U M M A R Y O F R E M A I N I N G B I D D E R S

ITEM	SECOND BID	SECOND AMOUNT	THIRD BID	THIRD AMOUNT	FOURTH BID	FOURTH AMOUNT
1	2,019.00	2019.00	800.00	800.00	1,000.00	1000.00
2	1,760.00	1760.00	3,000.00	3000.00	2,000.00	2000.00
3	12,663.00	12663.00	28,000.00	28000.00	6,000.00	6000.00
4	1,375.00	1375.00	2,500.00	2500.00	1,000.00	1000.00
5	2,148.00	2148.00	1,000.00	1000.00	10,000.00	10000.00
6	1,466.00	1466.00	250.00	250.00	2,000.00	2000.00
7	801.00	801.00	400.00	400.00	100.00	100.00
8	4.00	1600.00	5.00	2000.00	10.00	4000.00
9	2,117.00	2117.00	3,000.00	3000.00	1,900.00	1900.00
10	1,012.00	1012.00	1,000.00	1000.00	1,000.00	1000.00
11	40.00	960.00	50.00	1200.00	50.00	1200.00
12	6,843.00	6843.00	12,000.00	12000.00	9,800.00	9800.00
13	67.00	3350.00	200.00	10000.00	60.00	3000.00
14	44.00	5720.00	32.00	4160.00	90.00	11700.00
15	.08	2120.00	.08	2120.00	.06	1590.00
16	.27	7155.00	.23	6095.00	.37	9805.00
17	33.00	146850.00	29.00	129050.00	26.50	117925.00
18	963.00	12519.00	1,500.00	19500.00	1,400.00	18200.00
19	111.00	2664.00	140.00	3360.00	200.00	4800.00
20	766.00	766.00	250.00	250.00	1,000.00	1000.00
21	70.00	47600.00	90.00	61200.00	110.00	74800.00
22	100.00	3500.00	92.00	3220.00	110.00	3850.00
23	75.00	126000.00	86.00	144480.00	110.00	184800.00
24	200.00	1200.00	92.00	552.00	110.00	660.00
25	3.00	7140.00	3.50	8330.00	2.00	4760.00
TOT		401,348.00		447,467.00		476,890.00