

Third Bidder

10-24-14A11:28 RCVD

This information may be submitted with your bid proposal. If it is not, and you are the apparent low bidder or the second or third low bidder, it must be submitted and received as specified in section 2 of the specifications. Failure to submit the required DBE information will be grounds for finding the bid nonresponsive.

CONTRACT NO: 06-0P9704

BID AMOUNT: \$ 1,781,442.00

BID OPENING DATE: 10/22/14

BIDDER'S NAME: Coral Construction Company

DBE GOAL FROM CONTRACT, %: 13%

DBE PRIME CONTRACTOR CERTIFICATION¹:

BID ITEM NO.	ITEM OF WORK AND DESCRIPTION OF SERVICES TO BE SUBCONTRACTED OR MATERIALS TO BE PROVIDED ²	FOR CALTRANS USE ONLY	NAME OF DBEs (Must be certified on the date bids are opened - include Caltrans certification #, DBE address and phone number) (Indicate 2nd and lower tier subcontractors)	DOLLAR AMOUNT DBE ³
<u>12, 22, 23, 24, 29, 30, 32, 33, 72</u>	<u>Temp Con. Entrance, Clear* Grab, Road Ex, Ditch Ex, Agg Base, HMA, HMA (Misc Area), Tack,</u>		<u>Mass X Inc. DBE Cert #39715 55 Shaw Avenue #105 Clovis, CA 93612 (559) 472-3274</u>	<u>\$679,750.00</u>
	<u>Mobilization (Partial)</u>			

IMPORTANT: Identify all DBE firms being claimed for credit, regardless of tier. Names of the First Tier DBE Subcontractors and their respective items(s) of work listed above must be consistent, where applicable, with the names and items of work in the "Subcontractor List" submitted with your bid. Copies of the DBE quotes are required.

Total Claimed Participation

\$ 679,750.00

38.15 %

1. DBE prime contractors must enter their certification number and indicate all work to be performed by DBEs including work performed by its own forces.
2. If 100% of item is not to be performed or furnished by DBE, describe exact portion of item to be performed or furnished.
3. See section 2-1.12 of the specifications to determine the credit allowed for DBE firms.

Signature of Bidder

10/22/14 (503) 682-2262
 Date (Area Code) Tel. No.

John Weizner
 Person to Contact (Please Type or Print)

Submit to:

MSC 43
 OFFICE ENGINEER
 DEPARTMENT OF TRANSPORTATION
 1727 30TH STREET
 SACRAMENTO, CA 95816-7005

Proposal - Caltrans 06-0P9704

MASS X INC

55 Shaw Ave #105

Clovis, Ca. 93612

Contact: Jim Leppo

Phone / Fax: (559) 472-3274 / (559) 472-3275

License # 902334 - SBE/DBE/WBE/Union Contractor

Quote To: Coral Construction
Attn: Kris Karpstein
Phone: (503) 682-2252
Fax: (503) 682-0110
Proposal Date: 10-22-14

Addendums 1

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
12	Temp Construction Entrance	2.00	EA	3,000.00	6,000.00
22	Clear & Grub	1.00	LS	30,000.00	30,000.00
23	Roadway Excavation	5,420.00	CY	19.00	102,980.00
24	Ditch Excavation	3,900.00	CY	16.00	62,400.00
29	Class 2 Aggregate Base	1,890.00	CY	50.00	94,500.00
30	Hot Mix Asphalt	3,690.00	TON	90.00	332,100.00
32	Place Hot Mix Asphalt (Misc)	51.00	SY	270.00	13,770.00
33	Tack Coat	2.00	TON	1,500.00	3,000.00
72	Mobilization	1.00	LS	35,000.00	35,000.00
GRAND TOTAL					\$679,750.00

NOTES:

CONDITIONS:

- A mutually agreeable schedule will be drafted and agreed upon prior to performing the work.
- All terms and conditions of this proposal must be a part of any subcontract between Coral Construction and Mass X.
- All payments to Mass X will be in compliance with job specifications and amount paid to Mass X will be what is paid by owner.
- All items must be awarded to Mass X unless agreed by Mass X prior to bid time.
- All listed items include water for our work.
- Mass X, Inc. is a SBE/DBE/WBE/Union Contractor.
- Price is based on all of our work being completed prior to the installation of the high tension cable barrier posts.

BID ITEMS - INCLUSIONS/EXCLUSIONS

#12 - Temp Construction Entrance:

- Includes install/removal of entrances.
- Includes 1 move-in for install and 1 move-in for removal.

#22 - Clear & Grub:

- Includes all work per plans & specs.
- Includes 1 move-in for all work.
- Excludes the handling of hazardous material & debris.

- Excludes removal of guard railing, crash cushions & related; underground & related; existing signs & related.
- 3 days for work listed.

#23 & #24 - Roadway Excavation/Ditch Excavation:

- Includes all work per plans & specs.
- Includes off-haul of spoils generated from our work.
- Includes 1 move-in for all work.
- Excludes handling/off-haul of underground spoils & spoils from HTC/B posts/footings.
- Excludes grading under vegetation control mat, unless mat is in listed roadway excavation areas.
- Roadway Ex & Related - 8 days.
- Ditch Excavation - 4 days.

#29 - Class 2 Aggregate Base:

- Includes furnish & install baserock per plans & specs.
- Includes 1 move-in for all baserock operations.
- Excludes sawcutting @ pipe crossings.
- Class 2 @ inside shoulder & median work - 5 days.
- Class 2 @ pipe crossings - 2 days.

#30 - Hot Mix Asphalt:

- Includes furnish & install asphalt per plans & specs.
- Includes 1 move-in for all paving.
- Excludes patch paving at high tension cable barrier posts.
- 5 days for listed work.

#32 - Place HMA (Misc):

- Includes removal & offhaul cold mix (installed by others) for installation of HMA @ 2 pipe crossings.
- Includes minor grading @ misc paving area shown on sheet C-1.
- Includes 1 move-in for all work.
- Excludes sawcutting @ pipe crossings.
- Excludes replacement of striping/markers.
- If pipe crossings are larger than dimensions shown on drawings, we will expect to be compensated for this work, whether recognized by Caltrans or not.
- Misc AC @ guard railing - 1 day.
- Misc AC @ pipe crossings - 2 days.


#33 - Tack Coat:

- Includes all work per plans and specs.

EXCLUSIONS:

- Permits, fees & bonding. Bonding available at 2% if required.
- Night work.
- Sanitation.
- Traffic control, signage, flagging, message boards.
- Staking, surveying, testing & any inspection fees.
- Concrete, underground, and electrical (including but not limited to backfill and compaction). Spoils generated from these operations will be handled by others at no cost to Mass X and must be completed prior to Mass X grading operations unless agreed by Mass X.
- Dewatering.
- Storm water pollution prevention plan and its implementation, including but not limited to the installation, maintenance & removal of bmp's.
- Water pollution control and its implementation.
- Dust control plan and implementation (Mass X Inc will provide dust control for our operations).
- Street sweeping.

Sincerely,


Jim Leppo
Estimator