

**DEPARTMENT OF TRANSPORTATION**

DIVISION OF ENGINEERING SERVICES

OFFICE ENGINEER

1727 30<sup>th</sup> Street MS-43

P.O. BOX 168041

SACRAMENTO, CA 95816-8041

FAX (916) 227-6214

[www.dot.ca.gov/hq/esc/oe](http://www.dot.ca.gov/hq/esc/oe)

*Serious Drought.  
Help save water!*

October 13, 2014

12-Ora-5-3.0/3.7

12-0F96A4

Project ID 1200020277

IMD-ACNHPI-005-2(972)75E

STPLN-6212(016)E

Addendum No.1

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN ORANGE COUNTY IN SAN CLEMENTE FROM 0.4 MILE SOUTH TO 0.3 MILE NORTH OF AVENIDA PICO UNDERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on Thursday, October 23, 2014.

This addendum is being issued to revise the project plans, the *Notice to Bidders and Special Provisions*, the *Bid* book, and the Federal Minimum Wages with Modification Number 18 dated 08/22/2014.

Project plan sheets 2, 3, 4, 5, 6, 16, 17, 18, 19, 52, 307, 308, 309, 536, 540 and 549 are replaced and attached for substitution for the like-numbered sheets.

Duplicate project plan sheet 194 is deleted.

Project plan sheet 193 was omitted and is attached for addition to the project plans.

In the Special Provisions, Section 39, "HOT MIX ASPHALT," is replaced as follows:

**"Add to section 39-4.02C of the RSS for section 39:**

For HMA-O, the grade of asphalt binder must be PG 64-10.

For RHMA-O, the grade of asphalt binder must be PG 64-16".

Addendum No. 1  
Page 2  
October 13, 2014

12-Ora-5-3.0/3.7  
12-0F96A4  
Project ID 1200020277  
IMD-ACNHPI-005-2(972)75E  
STPLN-6212(016)E

In the *Bid* book, in the "Bid Item List," Items 128, 143, and 159 are replaced.

In the *Bid* book, in the "Bid Item List," Items 281 and 282 are added.

In the *Bid* book, in the "Bid Item List," Item 280 is deleted.

To *Bid* book holders:

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the *Notice to Bidders* section of the *Notice to Bidders and Special Provisions*.

Submit the *Bid* book as described in the *Electronic Bidding Guide* at the Bidders' Exchange website.

**[http://www.dot.ca.gov/hq/esc/oe/electronic\\_bidding/electronic\\_bidding.html](http://www.dot.ca.gov/hq/esc/oe/electronic_bidding/electronic_bidding.html)**

Inform subcontractors and suppliers as necessary.

This addendum, EBS addendum file, attachments and the modified wage rates are available for the Contractors' download on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/project\\_ads\\_addenda/12/12-0F96A4](http://www.dot.ca.gov/hq/esc/oe/project_ads_addenda/12/12-0F96A4)**

If you are not a *Bid* book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,



MOHSEN SULTAN  
Chief, Office of Plans, Specifications & Estimates  
Office Engineer  
Division of Engineering Services

Attachments

**BID ITEM LIST  
12-0F96A4**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
121	220101	FINISHING ROADWAY	LS	LUMP SUM	LUMP SUM	
122	260203	CLASS 2 AGGREGATE BASE (CY)	CY	5,480		
123	280000	LEAN CONCRETE BASE	CY	6,190		
124	280015	LEAN CONCRETE BASE RAPID SETTING	CY	300		
125	360200	BASE BOND BREAKER	SQYD	52,900		
126	390011	PREPAVING INERTIAL PROFILER	LS	LUMP SUM	LUMP SUM	
127	390132	HOT MIX ASPHALT (TYPE A)	TON	35,000		
128	390134	HOT MIX ASPHALT (OPEN GRADED)	TON	3,330		
129	390137	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	TON	9,780		
130	394073	PLACE HOT MIX ASPHALT DIKE (TYPE A)	LF	100		
131	027214	PLACE HOT MIX ASPHALT DIKE (TYPE C MODIFIED)	LF	200		
132	027215	PLACE HOT MIX ASPHALT DIKE (TYPE E MODIFIED)	LF	2,590		
133	027216	PLACE HOT MIX ASPHALT DIKE (TYPE F MODIFIED)	LF	920		
134	397005	TACK COAT	TON	140		
135	401050	JOINTED PLAIN CONCRETE PAVEMENT	CY	16,800		
136	027217	JOINTED PLAIN CONCRETE PAVEMENT (RAMP TERMINI WITH RAPID STRENGTH CONCRETE)	CY	750		
137	414240	ISOLATION JOINT SEAL (ASPHALT RUBBER)	LF	4,930		
138	460210	GROUND ANCHOR (SUBHORIZONTAL)	EA	632		
139 (F)	477021	MECHANICALLY STABILIZED EMBANKMENT, LOCATION A	SQFT	15,575		
140 (F)	477022	MECHANICALLY STABILIZED EMBANKMENT, LOCATION B	SQFT	11,600		

CONTRACT NO. 12-0F96A4

REPLACED PER ADDENDUM NO. 1 DATED OCTOBER 13, 2014

**BID ITEM LIST  
12-0F96A4**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
141 (F)	477023	MECHANICALLY STABILIZED EMBANKMENT, LOCATION C	SQFT	25,770		
142	480300	TEMPORARY SUPPORT	LS	LUMP SUM	LUMP SUM	
143	490508	FURNISH STEEL PILING (HP 10 X 57)	LF	3,127		
144	490509	DRIVE STEEL PILE (HP 10 X 57)	EA	72		
145	490538	FURNISH STEEL PILING (HP 14 X 117)	LF	20,355		
146	490539	DRIVE STEEL PILE (HP 14 X 117)	EA	344		
147	498044	36" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	52		
148	498052	60" CAST-IN-DRILLED-HOLE CONCRETE PILE (SIGN FOUNDATION)	LF	200		
149	500001	PRESTRESSING CAST-IN-PLACE CONCRETE	LS	LUMP SUM	LUMP SUM	
150 (F)	510051	STRUCTURAL CONCRETE, BRIDGE FOOTING	CY	1,120		
151 (F)	510053	STRUCTURAL CONCRETE, BRIDGE	CY	4,387		
152 (F)	510060	STRUCTURAL CONCRETE, RETAINING WALL	CY	940		
153 (F)	510072	STRUCTURAL CONCRETE, BARRIER SLAB	CY	1,190		
154 (F)	510086	STRUCTURAL CONCRETE, APPROACH SLAB (TYPE N)	CY	367		
155 (F)	510502	MINOR CONCRETE (MINOR STRUCTURE)	CY	388		
156	510526	MINOR CONCRETE (BACKFILL)	CY	.3		
157 (F)	511035	ARCHITECTURAL TREATMENT	SQFT	19,700		
158	519100	JOINT SEAL (MR 2")	LF	360		
159 (F)	520102	BAR REINFORCING STEEL (BRIDGE)	LB	1,188,690		
160 (F)	520103	BAR REINFORCING STEEL (RETAINING WALL)	LB	275,440		

CONTRACT NO. 12-0F96A4  
REPLACED PER ADDENDUM NO. 1 DATED OCTOBER 13, 2014

**BID ITEM LIST  
12-0F96A4**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
261	027242	TEMPORARY COMMUNICATION SYSTEM	LS	LUMP SUM	LUMP SUM	
262	027243	MODIFY COMMUNICATION SYSTEM	LS	LUMP SUM	LUMP SUM	
263	860797	ELECTRIC SERVICE (IRRIGATION)	LS	LUMP SUM	LUMP SUM	
264	860990	CLOSED CIRCUIT TELEVISION SYSTEM	LS	LUMP SUM	LUMP SUM	
265	027244	CLOSED CIRCUIT TELEVISION SYSTEM (STAGE CONSTRUCTION)	LS	LUMP SUM	LUMP SUM	
266	027245	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 1) (STAGE 1A)	LS	LUMP SUM	LUMP SUM	
267	027246	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 1) (STAGE 1B)	LS	LUMP SUM	LUMP SUM	
268	027247	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 1) (STAGE 1C)	LS	LUMP SUM	LUMP SUM	
269	027248	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 1) (STAGE 1D)	LS	LUMP SUM	LUMP SUM	
270	027249	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 1) (STAGE 2A)	LS	LUMP SUM	LUMP SUM	
271	027250	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 1) (FINAL STAGE)	LS	LUMP SUM	LUMP SUM	
272	027251	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 2) (STAGE 1A)	LS	LUMP SUM	LUMP SUM	
273	027252	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 2) (STAGE 1B)	LS	LUMP SUM	LUMP SUM	
274	027253	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 2) (STAGE 1C)	LS	LUMP SUM	LUMP SUM	
275	027254	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 2) (STAGE 1D)	LS	LUMP SUM	LUMP SUM	
276	027255	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 2) (STAGE 2A)	LS	LUMP SUM	LUMP SUM	
277	027256	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATION 2) (STAGE 2B)	LS	LUMP SUM	LUMP SUM	
278	027257	RAMP METERING SYSTEM (STAGE CONSTRUCTION) (LOCATON 2) (FINAL STAGE)	LS	LUMP SUM	LUMP SUM	
279	869075	SYSTEM TESTING AND DOCUMENTATION	LS	LUMP SUM	LUMP SUM	
280	BLANK					

CONTRACT NO. 12-0F96A4  
REPLACED PER ADDENDUM NO. 1 DATED OCTOBER 13, 2014

**BID ITEM LIST  
12-0F96A4**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
281	390138	RUBBERIZED HOTMIX ASPHALT (OPEN GRADED)	TON	3,780		
282	999990	MOBILIZATION	LS	LUMP SUM	LUMP SUM	

**TOTAL BID:**

**\$**  
\_\_\_\_\_