

Standards Update (SNs, Std Plans Lists, SSPs)

April 20, 2026

Use with 2025 Standard Plans:

SSPNo	Effective Date	Description	Update
Special Notices			
SN-305	A04-20-26		SN-305. Revised instructions to use the SN through October 2027.
Standard Plans			
StdPlan	A04-20-26	Standard Plans List	Revised the Standard Plans List and Canceled Standard Plans List to coincide with the Revised Standard Plans for the 2025 Standard Plans Erratum No. 1.
Canceled_StdPln	A04-20-26	Canceled Standard Plans List	Revised the Standard Plans List and Canceled Standard Plans List to coincide with the Revised Standard Plans for the 2025 Standard Plans Erratum No. 1.
SSPs			
2-1.06B	A04-20-26		Section 2-1.06B. Revised instructions for telephone number to schedule a viewing date.
5-1.14	A04-20-26	SAFETY QUALITY CONTROL MANAGER	Section 5-1.14. Revised the SSP instructions to update requirements for using a safety quality control manager in a project. Revised the content of the SSP to update general requirements, certifications, and qualifications of the safety quality control manager.
6-1.04	C04-20-26	Buy America	Section 6-1.04. SSP 6-1.04 is canceled. New NSSP is created to replace the SSP.
8-1.04C	A04-20-26	Delayed Start	Section 8-1.04C. Revised to add Society for Protective Coatings Quality Professional Certifications and Safety Quality Control Manager (SQCM) Resume and Certification to submittal requirements list in the 3rd paragraph. Minor revision to the instructions.
11-1.07	A04-20-26		Section 11-1.07. New SSP to prohibit digital radiography testing. Digital radiography was incorporated into the 2020 editions of AWS D1.1 and AWS D1.5. Currently, the Department does not have the ability to perform QA of digital radiography.
13-4	A04-20-26		Section 13-4. Removed reference to specific permit number.
13-12	A04-20-26		Section 13-12. Added additional instructions and references for dewatering activities.
21-2.04	A04-20-26		Section 21-2.04. Revised the webpage reference within the instructions from OCCS to the Landscape Architecture Program's webpage.
49-3.02B(7)	C04-20-26		Section 49-3.02B(7). This SSP is canceled. The foundation report will no longer allow the use of slurry cement backfill in the annular space between the soil and the casing for Type II CIDH piling.
52-2.01	C04-20-26		Section 52-2.01. This SSP is canceled. Pilot

Standards Update (SNs, Std Plans Lists, SSPs)

April 20, 2026

Use with 2025 Standard Plans:

SSPNo	Effective Date	Description	Update
			program to use ASTM A1055 as an alternative to ASTM A775 or A934 has ended.
52-2.02A(1)	C04-20-26		Section 52-2.02A(1). This SSP is canceled. Specification redundancy. List of additional locations requiring ASTM A775 would be generated from locations shown on the plans.
52-2.02A(3)(c)	C04-20-26		Section 52-2.02A(3)(c). This SSP is canceled. Pilot program to use ASTM A1035 as an alternative to ASTM A775 has ended.
52-2.02(B)	C04-20-26		Section 52-2.02B. This SSP is canceled. Pilot program to use ASTM A1035 as an alternative to ASTM A775 has ended.
52-2.03A(1)	C04-20-26		Section 52-2.03A(1). SSP is canceled. The SSP provided redundant information already required to be shown in plans or specified in SSP 83-3.02C.
55-1.02E(7)(b)	C04-20-26	Backing for Welds	Section 55-1.02E(7)(b). This SSP is canceled. Necessary provisions for weld backing are already addressed in AWS D1.5.
58-2.01A	A04-20-26	Alternative Sound Wall Location	Section 58-2.01A. Revised the instructions to remove the requirement to include SSP 58-4.01A.
60-3.05E	A04-20-26	Galvanic Anodes	Section 60-3.05E. Minor revision to change "rebar" to "reinforcement" in the 4th paragraph.
71-6.03	A04-20-26	CULVERTS AND PIPELINES	Section 71-6.03. Revised paragraphs 7 and 8 instructions to clarify when to delete alternate paragraphs .
81-3.02C	A04-20-26		Section 81-3.02C. New SSP to revise testing method for retroreflective pavement markers.
83-2.01B	A04-20-26		Section 83-2.01B. Revised SSP to remove redundant language and clarify earthwork and compaction requirements.
83-2.01C	A04-20-26	Vegetation Control Mat	Section 83-2.01C. Revised SSP to remove redundant language and clarify earthwork and compaction requirements.
84-6	A04-20-26	Traffic Stripe Tape Warranty	Section 84-6. Revised SSP to update retroreflectivity testing method and frequency and clarify warranty requirements for traffic stripe tape.