


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	Pla	65	R11.9/R24.1		

REGISTERED CIVIL ENGINEER DATE _____

PLANS APPROVAL DATE _____

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



FENCE AND GATE SUMMARY

SHEET No.	STATION	CHAIN LINK FENCE (TYPE CL-6)	CHAIN LINK FENCE (TYPE CL-4)	WROUGHT IRON FENCE	10' CHAIN LINK GATE (TYPE CL-6)	14' CHAIN LINK GATE (TYPE CL-6)	20' CHAIN LINK GATE (TYPE CL-6)	FENCE WM, (TYPE WM, METAL POST)	REMOVE FENCE	TEMPORARY FENCE
		LF	LF	LF	EA	EA	EA	LF	LF	LF
L-1 TO L-4	"D13" 646+14.83 TO 678+43.60	5,399						16	4,652	3,117
L-2, L-3, & L-67	"INDR1" 661+65.70 TO 679+23.10	1,063							1,183	
L-3, L-65 TO L-69	"IND1" 32+33.66 TO 83+51.55	2,561						27	1,958	2,789
L-4 TO L-6	"D13" 678+43.60 TO 690+10.44	2,298			4				1,053	1,476
L-6 TO L-9	"D13" 690+10.44 TO 723+58.70	701								984
L-6 TO L-8	"F1" 690+45.45 TO 706+85.34	1,655								
L-8 TO L-9	"F2" 705+59.73 TO 721+01.87			1,635	1					
L-6 TO L-7	"F4" 690+71.08 TO 706+08.38	1,644			1					
L-7 TO L-9	"F5" 706+03.04 TO 720+67.31	1,302								
L-9 TO L-10	"D13" 723+58.70 TO 730+60.46	1,833			2			74	1,896	656
L-13 TO L-18	"D13" 760+57.87 TO 807+08.41	2,345			4			746	1,885	984
L-18 TO L-19	"D13" 808+69.21 TO 818+83.90	9,492						234	3,676	8,202
L-72 TO L-73	"NEL1" 32+80.83 TO 65+61.66	3,496						150	5,210	4,950
L-19 TO L-21	"NB9" 823+33.51 TO 849+79.26	5,289						9	152	5,906
L-21 TO L-24	"D13" 849+79.26 TO 883+03.95	6,963								2,625
L-25 TO L-28	"D13" 885+07.88 TO 918+63.24	7,417			2					4,593
L-74 TO L-77	"NIC1" 23+62.19 TO 72+17.82	6,518						2,422	9,027	8,761
L-28 TO L-29	"D13" 921+91.32 TO 933+85.86	2,858								328
L-29 TO L-33	"D13" 933+85.86 TO 985+32.90	10,690			2					3,609
L-33 TO L-35	"D13" 985+32.90 TO 1001+89.98	3,273								1,640
L-35 TO L-37	"NB10" 1001+89.98 TO 1025+15.61	4,952						10	470	2,789
L-78 TO L-80	"WIS1" 16+40.41 TO 72+18.20	4,592						1,073	4,907	6,234
L-38 TO L-40	"NB10" 1030+85.64 TO 1049+63.3	3,799			1			134	6,286	2,133
L-40	"D13" 1049+63.30 TO 1050+34.39	298								2,664
L-40 TO L-45	"D13" 1053+48.55 TO 1102+35.88	9,998			2					294
L-45 TO L-47	"D13" 1102+35.88 TO 1118+10.68	3,347			1					1,312
L-47 TO L-51	"D13" 1118+10.68 TO 1163+38.23	9,558			4			76	2,208	3,937
L-51 TO L-52	"D13" 1163+38.23 TO 1175+19.33	2,985	1,314			2		76	2,313	984
L-81 TO L-83	"DOWD1" 32+80.83 TO 85+29.32							755	4,883	481
L-52 TO L-55	"D13" 1175+19.33 TO 1199+02.28	4,852	2,417		2					2,461
L-55 TO L-57	"NB11" 1199+02.28 TO 1222+42.63	5,567	2,822							4,757
L-86 TO L-91	"EB11" 62+80.83 TO 84+39.59	1,013	1,662					47	5,088	363
L-57 TO L-59	"NB11" 1225+30.38 TO 1247+19.10	6,189								3,129
L-59	"D13" 1247+19.10 TO 1249+34.00	420						11	7,348	98
L-59 TO L-64	"D16" 1249+34.00 TO 1319+54.98	5,657						22	3,937	2,789
TOTAL		140,024	8,215	1,635	26	2	1	5,882	74,219	86,997

THIS EXAMPLE IS ONE OF MANY EXAMPLES OF THE VARIOUS TYPES OF PROJECT PLAN SHEETS FROM THE SAME CONSTRUCTION PROJECT, "ROUTE 65 BYPASS PROJECT."

SUMMARY OF QUANTITY SHEET, EXAMPLE "65 Q-14"

SUMMARY OF QUANTITIES Q-14

