


Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
03	Pla	65	R11.9/R24.1		

REGISTERED CIVIL ENGINEER DATE \_\_\_\_\_

PLANS APPROVAL DATE \_\_\_\_\_

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.



### PAVEMENT STRUCTURE QUANTITIES SUMMARY

LOCATION	RUBBERIZED HOT MIX ASPHALT (GAP GRADED)	HOT MIX ASPHALT (TYPE A)	CLASS 2 AGGREGATE BASE	CLASS 2 AGGREGATE SUBBASE	TACK COAT	SLURRY SEAL	COLD PLANE ASPHALT CONCRETE PAVEMENT
	TON	TON	CY	CY	TON	TON	SQYD
"D13"	36,058.1	84,719.2	116,293.3	139,769.9	224.14		
"NB9/SB9"	5,037.1	11,334.7	16,005.5	19,847.0	32.27		
"NB10/SB10"	5,040.0	11,340.7	16,565.1	20,463.6	31.40		
"NB11/SB11"	5,399.7	12,160.8	17,186.6	21,305.5	30.60		
"D16"	916.5	3,609.0	8,359.3	9,747.0	9.08		
"IND1"		11,782.4	22,069.7		28.43		
"FR"		3,054.7	4,126.7			125.6	
"NEL1"		6,775.5	12,435.3		13.93		
"NIC1"		3,307.7	5,723.7		4.67		
"NOF1"		1,007.3	1,707.5		1.63		
"NOF2"		163.6	277.3		0.26		
"WIS1"		4,311.0	7,296.7		6.09		
"WISF1"		971.1	1,633.0		2.20		
"DOWF1"		5,224.7	8,856.3		8.44		
"WB11/EB11"		8,395.6	15,357.8		9.52		
"IN4"	1,339.1	2,297.7	3,710.1	4,415.9	3.90		
"IN3"	635.0	1,097.7	1,884.4	2,163.2	1.69		
"F1"	1,087.5	2,186.6	2,656.5	3,642.3	5.96		
"F2"	784.0	1,579.7	1,930.8	2,625.7	4.29		
"F4"			2,470.0	3,458.1			
"F5"	685.4	1,382.2	1,693.8	2,295.6	3.75		
"F6"	537.3	1,095.1	1,382.9	1,799.5	2.94		
"ROD1"		215.7	394.6		0.49		
"DR11"		23.2	60.6		0.04		
"DRI2"		94.4	266.8		0.15		
"MOR1"		1,269.5	2,510.5		2.78		
"DOW1"		324.8	1,284.7		0.74		
"CULR1"		286.1	485.0		0.46		
"EX65N2"		799.3	1,676.5		1.64		
INDUSTRIAL PARK AND RIDE		1,053.7	3,159.6				
RETENTION BASIN		330.1	646.1				
HMA (TEXTURED PAVING)		413.6	695.3				
MINOR CONCRETE (SIDEWALK)			595.1				
MINOR CONCRETE (STAMPED CONCRETE)			120.0				
HMA DIKE		68.8					
Misc DRAINAGE QUANTITIES		23.8	146.0				
STAGE CONSTRUCTION QUANTITIES	493.0	9,009.6	15,249.2			125.7	16,898
<b>TOTAL</b>	<b>58,012.7</b>	<b>191,709.6</b>	<b>296,912.3</b>	<b>231,533.3</b>	<b>431.49</b>	<b>251.3</b>	<b>16,898</b>

THIS EXAMPLE IS ONE OF MANY EXAMPLES OF THE VARIOUS TYPES OF PROJECT PLAN SHEETS FROM THE SAME CONSTRUCTION PROJECT, "ROUTE 65 BYPASS PROJECT."

### SUMMARY OF QUANTITIES SHEET, EXAMPLE "65 Q-5"

### SUMMARY OF QUANTITIES Q-5

STATE OF CALIFORNIA - DEPARTMENT OF TRANSPORTATION  
**Caltrans**  
 REVISION: DATE PLOTTED => 29-DEC-2011  
 00-00-00 TIME PLOTTED => 11:20

SUMMARY OF QUANTITIES SHEET, EXAMPLE "65 Q-5" RELEASED 1/6/2012