

Attachment C—Partial List of Items Inappropriate as Supplemental Work

Type of Work	Reason for Not Including as Supplemental Work
Additional Drainage Work	Too general. Supplemental work must not be used to take the place of complete design work and quantity calculations.
Additional Electrical Work	Too general. Supplemental work must not be used to take the place of complete design work and quantity calculations.
Additional Roadwork Additional Excavation Additional Subexcavation Additional Work Additional Bid Quantities	Too general. Supplemental work must not be used to take the place of complete design work and quantity calculations. Address quantity uncertainty by increasing quantity estimate. Also, this work is not to be covered by contingency.
Clean out Existing Culvert Repair Existing	Improper to perform maintenance work if funded from other than State maintenance funds. The item of work does not fall within the statutory definition of construction project. See Sections 28 and 29 of the Streets and Highways Code.
Environmental Mitigation	Too general. Either include the mitigation work as contract item work if it is required by a permit, license, agreement, or certification (PLAC), or do the mitigation as a separate project.
Haul Material	Include in contract item work.
Hazardous Substances and Asbestos	Include contract item for this work. Hazardous substances can only be managed by the prime contractor if the work is specified in the original contract documents.
Hot Mix Asphalt (Leveling)	Include in contract item work.
Improvement for Safety	Too broad. Supplemental work must not be used to take the place of complete design work and quantity calculations. Show or specify the work so that the appropriate contractor or subcontractor or both could bid it.
Locate Existing Underground Facilities	Utility location should be done during project design and incorporated in the contract documents in accordance with the high and low risk policy.
Modify Irrigation System	Include in contract item work if the needed modifications are know, otherwise if the modifications are unknown and unforeseen work than the work should be paid from contingency funds.
Mowing Maintain Landscape	Improper to perform maintenance work if funded from other than State maintenance funds. The item of work does not fall within the statutory definition of construction project. See Sections 28 and 29 of the Streets and Highways Code.
Prune Existing Plants	Improper to perform maintenance work if funded from other than State maintenance funds. The item of does not fall within the statutory definition of construction project. See Sections 28 and 29 of the Streets and Highways Code. Include pruning in contract item work that is necessary to construct the work when the extent of pruning is known. If the extent of pruning is unknown then the pruning work should be paid form contingency funds.

Type of Work	Reason for Not Including as Supplemental Work
Remove Slide	Include in contract item work for existing slides. Removal of unanticipated slides and slipouts during the work will be paid from contingency funds.
Remove Unsuitable Material	Include in contract item work when unsuitable material is identified during project design. Removal of unsuitable material found during the work will be paid from contingency funds..
Subsurface Drainage	Include in contract item work if problem is identified during project design. For wet subsurface conditions encountered during the work subsurface drainage will be paid from contingency funds.