

## **Bridge Design Details 7.10 August 2025**

## **Bent Cap Stirrup Reinforcement (Vertical Exterior Girders)**




Figure 7.10.1 Stirrup Reinforcement at Skewed Bent Caps (Greater than 20° Skew)

## Notes:

- 1. On sharply skewed structures, a PART PLAN is provided as shown here, to assure adequate reinforcement is provided at bent cap and hinge ends.
- 2. For skews 0° to 20°, place bent cap and diaphragm stirrups parallel to girders; for skews over 20°, place bent cap and diaphragm stirrups normal to £ Bent but may be placed parallel to girders if required for utility openings. Careful consideration should be given to the size and placement of utility openings on sharply skewed structures.