



CALIFORNIA BRIDGE ENGINEERS SEMINAR

ADVANCING BRIDGE ENGINEERING THROUGH INNOVATION



CABES 2026

Presentation 9 - From Blueprint to Bedrock



From Blueprint to Bedrock: A Case Study on the Design and Execution of CIDH Foundations in Bridge Projects

Yashwanth Sai Kistamsetty, M. Tech (Structures)

Structure Construction – Caltrans

02/25/2026

Contents

- Project overview
- CIDH – An introduction
- Design CIDH – Blueprint
- Proposed change
- CIDH Installation methodology – Bedrock
- Comparison
- Results & significance
- Conclusion


Project Overview

- Dr. Fine bridge replacement on state highway 101 in Del Norte county.
- 4 span, single frame structure.
- Length 1031ft long.
- Width 51ft, 2 travel lanes.
- Superstructure- PS CIP box girder.
- Schedule driven – 7 workday calendar.



CIDH – An Introduction

- Cast-in Drilled Hole piles (CIDH) are deep foundational elements.
- It is a replacement pile.
- A typical bridge foundation for cohesive soils, granular soils.
- Load transfer mechanism – End bearing and Skin friction.
- Designed for ultimate and serviceability limit states.
- Vital role in importance in bridge performance.



Blueprint





California Bridge Engineers Seminar 2026



Design CIDH (Permanent Casing)

- 96" Ø CIDH with 108" x ½" permanent steel casing.
- Pile cut off elevation at +23.00 ft.
- Specified tip elevation at -115.00 ft.
- Steel casing specified tip elevation at -80.00 ft.
- Total steel casing length = 103 ft.
- Log of test boring.



55.4' Rt Sta 298+78.4
 E Rte 101

RC-09-002

FOR PLAN VIEW, SEE
 "LOG OF TEST BORINGS 1 OF 20"



Proposed Change

- The 1/2" wall likely to buckle during installation.
- Significant schedule delays.
- Use of a thicker and more robust temporary steel casing.
- Contractor's preferred means and methods.
- Incompliance with specifications.
- Eliminate the Permanent steel casing bid item from the contract.
- A no cost change order.

Bedrock




CIDH Installation Methodology (Temporary Casing)

- Oscillator with temporary casing (120") to hold the hole open from caving.
- Advanced to the anticipated rock
- Drilled open hole (96") drill rig.



Drilling Equipment's:

- Buma 300 Grab operated by Liebherr HS 895HD crane.
- Soilmec SR 125 rotary drilling rig.



Casing Installation

- 123" O.D casing installed to the rock layer.
- Leffer VRM 3800 casing oscillator.
- Casing sections connected by jointed segments.
- Each casing segment was about 10' in length.
- HD bolted connections.



Drilling Sequence:




Figure 3-8 Construction Using Casing Advanced Ahead of Excavation: (a) drive casing into bearing stratum; (b) drill through casing; (c) complete and clean hole, set reinforcing; (d) place concrete to head greater than external water pressure; (e) pull casing while adding concrete

Points to be taken care of:


- Soil plug on oscillator casing
- Fluid head relative to ground water elevation
- Oscillator pressure
- Slurry test parameters

Maintaining Soil Plug

- ASR and Contractor should be measuring a logging to maintain the soil plug.

Oscillated CIDH Pile Profile Form. *NEW*

- Top of Soil Plug
- Top of Slurry
- Exposed casing
- Soil Plug Thickness
- Piezometric Head / GWS



Excavation log:

- Full time inspection
- Drilling tools used
- Drilled depth
- Elevation tip
- Soil description and notes
- Time in/out
- Casing tip established

CALIFORNIA DEPARTMENT OF TRANSPORTATION
Drilled Shaft Excavation Log
SC-3803 (Rev 11/23/2022)

JOB STAMP
01-426404
01-DN-101-35.8/36.5
0108000193

Br. Name: D1 Fine Bridge Br. No.: 01-0041 Abut./Bent No.: P2 FT
Pile No.: P3 LT Pile Length: 123' Pile Diameter: 10.35'
Drilling Contractor: MACM Rock Socket Diameter: 3'
Date Drilling Started: 4/18/24 Drilling Equipment: Lubber 45.845 + Laffer 3.8M
Date Drilling Completed: 5/16/24 Bottom Cleaning Equipment: Art. 11 GW Elev.: 197.45
Drilling Slurry: SHOWN 1706 Drilling Additives: N/A Slurry Elev.: 30
Date Poured: N/A Recorded By: SG

Drilled Depth* (ft)	Elevation** (ft)		Time	Drilling Tool	Soil/Rock Description & Notes
	From	To			
15/02.5	36.5	37.5	13:03	12.05 Comp	Beginning to see dissection of soil block. Good sand + large cobbles. Recovery
15/05	37.5	38.5	13:33	13.40	Rocky sand + large cobbles. Small Recovery
16/05	38.5	39.5	13:41	13.48	"
14/53	39.5	40.5	13:49	13.52	"
14/53	40.5	41.5	13:58	14:03	"
13/54	41.5	42.5	14:05	14:10	"
13/54	42.5	43.5	14:15	14:23	"
12/54	43.5	44.5	14:24	14:35	"
12/54	44.5	45.5	14:37	14:42	"
12/54	45.5	46.5	14:43	14:58	"
12/54	46.5	47.5	15:05	15:05	"
10/52.5	47.5	48.5	16:02	16:09	Sand plug
10/52.5	48.5	49.5	16:10	16:19	Very sand + large Med cobbles. Small Recovery
10/53	49.5	50.5	16:20	16:32	"
9/510	50.5	51.5	16:33	16:39	"
9/510	51.5	52.5	16:40	16:49	"
9/514	52.5	53.5	16:55	17:10	"
29/74	53.5	54.5	17:45	18:00	Casing added
29/74.5	54.5	55.5	18:10	18:10	"
29/74.5	55.5	56.5	18:21	18:21	"
18/73	56.5	57.5	18:23	18:34	"
18/73	57.5	58.5	18:35	18:45	"
18/73	58.5	59.5	18:46	18:58	"

* Depth Reference: Bottom Plate 9 Oscillator
** Elevation BM: 37.95

Top 2 = 11
Top 3 = 11.5
Top 4 = 11.5

CALIFORNIA DEPARTMENT OF TRANSPORTATION
Drilled Shaft Bottom Inspection
SC-3805 (Rev 11/23/2022)

JOB STAMP
01-426404
01-DN-101-35.8/36.5
0108000193

Br. Name: D1 Fine Bridge Br. No.: 01-0041 Abut./Bent No.: P3
Pile No.: P3 LT Pile Length: 123' Pile Diameter: 10.35'
Drilling Contractor: MACM Rock Socket Diameter: 3'
Date Drilling Started: 11/01/24 Drilling Equipment: Soil Mtr CR125 + Laffer Oscillator
Date Drilling Completed: 11/08/24 Bottom Cleaning Equipment: Art. 11
Recorded By: SG Date: 11/10/24 Time: 0930 Hrs
Job North At: 12:00

Inspection Type: ☒ Visual ☒ Sounding ☒ Shaft Inspection Device

11/11/24

Location	Depth*	Elevation**
1	16.45'	-110.93
2	16.45'	-110.93
3	16.45'	-110.93
4	16.35'	-110.43
5	16.39'	-110.52

Comments: Average depth @ -110.71 Elevation
Top of casing 17' from

* Depth Reference: Top of casing 17' from
** Elev. BM: 37.23

Verifying the hole – SID Test

- Bottom cleanliness.
- Proper bearing surface.
- SID camera system, Live video monitor.
- Measuring device.

Acceptance criteria:

- 0.5 inch over more than 50 percent of the base.
- 1 inch at any location across the base of the shaft.
- Essential for tip resistance pile.



Shaft Visual Inspection Report
(Bottom of CHD Pile Inspection)

Bridge No. <u>CY 101B</u>	Support <u>P3</u>	File <u>P3K</u>
Bridge No. <u>21-00-1</u>	Inspection Device <u>Mini-SID</u>	D/D (Close Drive Unit)
Contract No. (CAN)	Length	
Structure Rep. <u>Robert Cox</u>	Diameter	
Inspected by <u>20045</u>	Contract <u>20045</u>	
Photo Robot Cage Placed (Yes/No)	Under <u>10/1/14</u>	

Inspection No. 1
Date 8/8/14
Time 10:15

Standard Length Scale

0	1/2"
1	1"
2	1 1/2"
3	2"
4	2 1/2"
5	3"
6	3 1/2"
7	4"
8	4 1/2"
9	5"

North

Views: East, West, South, North

SID Inspection Sequence: Run #1 at Center, Run #2 at East, Run #3 at West, Run #4 at South, and Run #5 at North

Comments

NOT TO SCALE




Rebar cage




- Inspection tubes per plan installed for GGL testing
- Crane used to lift the rebar cage with slings/rigging cables for installation at the CIDH pile

Concrete placement



- Tremie pipe raised as concrete is placed, maintaining 10' min. concrete head.
- Placement rate including the breaks for casing removal (30 mins. 2-3 breaks and 30 min. for end clean up = total cy (361) /hr. +3*30min. +30min.= 8 hours approx.

Pile Acceptance – GGL Testing:



Pile Design Data Form

1 Foundation Testing

Name: Vincent Chu
Phone: 916-227-1050
Date: 12/16/24

Testing Performed: ☒ GGL ☐ CSL

Section B - B


Elev: -10.8 ft to -13.6 ft
Depth: 23.8 ft to 26.6 ft
Diameter: 118.5" / 96"
Depth Ref: Plan Pile Cut-Off Elev.

IP8 IP1
IP7 IP2
IP6 IP3
IP5 IP4

Provide the relevant elevations.

Plan Pile Cut-off Elev: 13.0 ft
Plan Const. Joint Elev: N/A
Plan Top of Pile Pedestal Elev: N/A
Reported Casing Tip Elev: N/A
Reported Pile Tip Elev: -110.7 ft

Anomaly Description:
GGL detected an anomaly at one inspection pipe. May affect up to 13% of the pile cross-section at this depth range.



- NDT test method.
- Nuclear density probe
- Concrete density vs pile depth for homogeneity.
- Electric wench pulls a 4-foot probe through the tubes.

Permanent vs Temporary casing : A comparison

Aspect	Temporary Casing	Permanent Casing
Material Handling	Reusable	One time
Installation	Standard construction practice	Precision placement
Repair risk	Low	High
Performance	No corrosion concerns	Corrosion risk
Side resistance	Can be considered	Usually not considered
Design	Concrete	Composite
Schedule impact	Faster	Slower

Results & Significance

- The need for permanent casing was eliminated.
- Eliminated the need for pump grout and grout tubes that fill the voids in the annular space between the casing and the soil.
- Temporary casing is more practical and flexible for construction.
- Cost savings in material procurement and fabrication.
- No impact on controlling activities or critical path items.
- Concrete placed under its own pressure head against the gravel irregular soil face produce a far better skin friction, as compared to the steel against soil pile.

Conclusion:

- Total cost savings for the proposed change were \$45,676.36
- Construction efficiency and cost effectiveness were improved.
- Inspection and quality control were more straightforward.
- Design considerations were satisfactorily met.
- Overall project risk was reduced.

For sites where excavation support is required only during construction, temporary steel casing provides superior construction efficiency and lower life-cycle risk compared to permanent casing.



Thank you



California Bridge Engineers Seminar 2026



DES

DIVISION OF ENGINEERING SERVICES

