

# **Liquefaction Evaluation**

Timely identification of soil liquefaction is important to minimize project risk and to ensure that potential impacts are properly mitigated. Refer to Memos to Designers (MTD) 20-14, "Quantifying the Impacts of Soil Liquefaction and Lateral Spreading on Project Delivery."

## This module presents:

- The criteria for *preliminary screening, which is the* assessment of liquefaction potential using available information (e.g., published liquefaction hazard maps, AsBuilt Log of Test Boring, etc.). The results of preliminary screening are typically reported in the DPGR, SPGR.
- Guidance for site investigations in potentially liquefiable soils.
- The methodology for performing quantitative analysis of liquefaction potential to determine if liquefaction will occur based on site-specific field exploration and laboratory testing data in accordance with Youd et al (2001) and Boulanger and Idriss (2006). The results of quantitative analysis are typically reported in the PFR, FR, PGDR, and GDR.
- Appendix A: Cone Penetration Test (CPT) Example (Youd et al., 2001)
- Appendix B: Standard Penetration Test (SPT) Example (Youd et al., 2001)

## **Preliminary Screening of Potentially Liquefiable Soils**

Preliminary screening involves the evaluation of a site for soil liquefaction potential using existing information such as liquefaction hazard maps such as <a href="State">State</a> "Seismic Hazard and <a href="Zones of Required Investigation Maps">Zones of Required Investigation Maps</a>" and <a href="USGS">USGS</a> "Liquefaction Hazards Maps"</a>, groundwater information, reports, as-built plans/subsurface data, and in some cases existing sampling and testing. The purpose of the preliminary screening is to alert the PDT of the potential for soil liquefaction to occur at the site.

Use the following five (5) criteria for preliminary screening evaluation of soil liquefaction potential at a project site.

- 1. Groundwater Table (historic, current, or anticipated future level)
- Age of Soil
- 3. Soil Type
- 4. In-situ Soil Density/Initial State
- 5. Design Peak Ground Acceleration and Earthquake Moment Magnitude



Use all five (5) criteria to make a preliminary screening assessment. If the preliminary screening indicates no liquefaction potential, the site investigation may be planned as if liquefaction is not expected. If there is a potential for liquefaction, or the potential is unknown, the Geoprofessional must report as discussed below, and the field investigation planned to include appropriate (CPT) soundings, drilling method and SPT blow count measurements, and sampling of the potentially liquefiable soils.

#### 1. Groundwater Table

Sites with potentially liquefiable soils and groundwater table within 50 feet of the ground surface are generally considered to be most susceptible to liquefaction. If the groundwater table is anticipated to be shallower than 50 feet, the Geoprofessional should anticipate the need for and plan to collect samples and perform necessary field tests for liquefaction potential, unless the potential for liquefaction hazard can be confidently ruled out based on other criteria (items 2-5 above). If the groundwater is known to be below 70 feet, the site may be considered non-liquefiable for preliminary screening purposes.

Sources of groundwater data include "As-Built" boring logs, County well log data, water wells (<u>Department of Water Resources</u>), and historic ground water levels (<u>USGS</u>) and ground water plates published in the <u>State Seismic Hazard Zone</u> map reports.

## 2. Age of Soil

Holocene deposits (younger than 11,000 years) and man-made fills ranging from very loose to medium dense are susceptible to liquefaction. Geologic deposits older than Holocene age (> 11,000 years) are considered to have low liquefaction susceptibility. A source of soil age data is the <u>CGS California Geologic Map</u> for the site.

#### 3. Soil Type

Soil types that are susceptible to liquefaction are sand, silty sand, low plasticity (PI<7) silt and, in unusual cases, gravel. Rock and most clay soils are not liquefiable.

#### 4. In-situ Soil Density/Initial State

Granular/cohesionless soils with an initial state represented by a normalized, clean-sand equivalent CPT resistance  $(q_{c1N})_{cs} > 160$ , or SPT blow count  $(N_1)_{60cs} > 30$  are considered not susceptible to liquefaction irrespective of the other criteria or conditions.

# 5. Peak Ground Acceleration and Earthquake Magnitude

Liquefaction potential increases with increasing Peak Ground Acceleration (PGA) and earthquake magnitude (M). The site design PGA and M typically correspond to a return period of 975-years and are obtained from ARS Online webtool.



## Field Investigation

If preliminary screening indicates liquefaction potential exists or is unknown, the field investigation should gather information for liquefaction assessment including the soil characteristics (classification/type, grain size distribution, density, Atterberg Limits) and spatial distribution of the potentially liquefiable soil, and the groundwater level. Typical field investigations use rotary wash or auger SPT sample borings and laboratory test samples, and/or CPT soundings as per applicable ASTM Standards. The depth of the exploration must be 70 feet below ground surface or 20 feet below the pile design tip elevation, whichever is greater.

Because the presence of liquefiable soils can substantially increase project costs, it is important to thoroughly characterize the site. The site exploration needs to determine if the liquefiable soils are extensive enough, both laterally and vertically, to constitute a hazard. Depending on the field conditions, geophysical methods, and CPT soundings can provide information on the lateral extent of liquefiable layers more economically than SPT borings.

# CPT Soundings

CPT soundings offer advantages over other methods of estimating liquefaction resistance in both the detection of thin layers that may influence liquefaction triggering and subsequent pore pressure redistribution and in the reproducibility of results. CPT results are less dependent on the equipment operator than most other in situ test methods and CPT can be performed quickly and cheaply. The seismic CPT can also measure soil shear wave velocity (National Academies of Sciences, 2016) CPT does not only identify the presence of liquefiable soils, but it can also show if the liquefiable soils are extensive enough, both laterally and vertically, to constitute a hazard.

When the CPT, without collecting any soil samples, is the primary investigative tool it is highly recommended that at least one SPT boring be performed "side by side" to a CPT sounding location for each bridge structure. This provides soil samples for laboratory testing to determine the required soil parameters (e.g., fines content, Atterberg Limits) and at least some limited site-specific correlations between SPT and CPT results. Whenever feasible, consider using CPT in the final liquefaction evaluation, in particular for sites with thinly bedded and/or highly variable subsurface soil conditions.

#### Standard Penetration Test (SPT)

SPT has been the most commonly used investigative tool for liquefaction evaluation. For large or important projects, in particular with highly variable subsurface conditions, SPT should be supplemented with CPT. Unlike the CPT, the SPT provides actual soil samples that can be visually examined and tested in the laboratory to evaluate soil parameters needed for more reliable liquefaction analysis.

Do not use hollow stem augers below the water table, or any non-standard exploration and/or testing methods for liquefaction assessment using either the SPT and/or the CPT.



## Ground Water Level

Measure the elevation of the stabilized groundwater table or, where appropriate, of the piezometric surface in the borehole or piezometer. The CPT pore pressure dissipation test can also be used to determine the elevation of the groundwater table or the piezometric surface. Use a higher elevation than measured only if there is clear evidence for seasonal or long-term fluctuations. Do not use abnormally high or temporary groundwater level.

#### Geophysical Investigation

In gravelly soils where SPT blow counts are unreliable (or at depths greater than 70 feet) consider the shear wave velocity (Vs) method for performing liquefaction assessments (Andrus and Stokoe, 2000; Youd et al., 2001). The seismic cone, P-S logging, or surface wave methods are available to obtain shear wave velocity.

# **Laboratory Testing**

Laboratory tests for quantitative liquefaction evaluation include:

- Particle Size Analysis (ASTM D 422)
- % Finer Than the No. 200 (75 μm) Sieve (ASTM D 1140)
- Atterberg Limits (ASTM D 4318)

The exact type(s) and the number of laboratory tests performed shall be selected based on the visual-manual description and identification (ASTM D2488), and the extent and field variability of the identified potentially liquefiable soils.

Results from Atterberg Limit test(s) are necessary when the amount (%) and/or the plasticity index of the fines content are used in the final determination of an otherwise liquefaction susceptible soil as not liquefiable.

# **Quantitative Liquefaction Analysis**

Quantitative liquefaction analysis uses site-specific field and laboratory test data. Use the procedure of Youd, et al (2001): Liquefaction Resistance of Soils: Summary Report from the 1996 NCEER and 1998 NCEER/NSF Workshops on Evaluation of Liquefaction Resistance of Soils October 2001 for quantitative liquefaction analysis. The procedure for CPT and SPT analysis consists of the following general steps:

- 1. Determine the design PGA and earthquake moment magnitude (M).
- 2. Determine the design groundwater table elevation.
- 3. Determine which soil layers are susceptible to liquefaction and thus need to be evaluated based on a quantitative liquefaction analysis.
- 4. Determine the total soil unit weight for all soil layers or sublayer located above the bottom elevation of the lowest soil layer susceptible to liquefaction. Then perform



the following steps for each of the soil layer/sub layer identified in Step 3 as susceptible to liquefaction.

- 5. Determine the Cyclic Stress Ratio (CSR) at the mid elevation.
- 6. Determine the representative values of the field measured CPT tip and frictional resistances or the SPT blow count.
- 7. Correct and normalize the measured CPT tip resistance/SPT Blow Count.
- 8. Determine the Fines Content Correction and the clean-sand equivalent CPT.
- 9. Determine the clean-sand equivalent normalized CPT tip resistance/SPT Blow Count and Calculate Cyclic Resistance Ratio (CRR)<sub>7.5</sub>.
- 10. Calculate the Magnitude Scaling Factor (MSF), overburden correction ( $K_{\sigma}$ ) and the sloping ground correction factor ( $K_{\alpha}$ ).
- 11. Calculate the Factor of Safety Against Liquefaction.

Modifications or elaborations to Youd et al (2001) are as follows:

- Use Youd et al (2001) to depths of 50 feet; with caution to 70 feet; do not use below 70 feet.
- Liquefaction evaluation below 70 feet require special analysis and consideration that is beyond the scope of this module.
- Do not combine liquefaction analysis with other extreme events or conditions (e.g., vessel impact, and abnormally high or temporary groundwater levels).
- Consider scour in liquefaction evaluation as specified in Article 10.5.5.3 of the AASHTO LRFD Bridge Design Specifications with California Amendments.
- Do not use the "Modified Chinese Criteria" as it is unconservative for determining
  if certain fine-grained soils are liquefiable. Use Boulanger and Idriss (2006) to
  determine if fine grained soils are likely to behave as sand-like material and are
  thus should be considered as susceptible to liquefaction.
- Use the design PGA (5% probability of exceedance in 50 years or 975-year return period) in units of g (e.g., PGA=0.4g) evaluated as per Appendix B of the Seismic Design Criteria (SDC) and using ARS Online webtool. Here, g is acceleration of gravity. (Note: Youd et al, 2001 uses the parameter a<sub>max</sub> for PGA in units of g)
- Use the de-aggregated mean earthquake moment magnitude (M) for PGA as the design earthquake magnitude (M<sub>w</sub>). (Note: Youd et al, 2001, uses both the symbols M and M<sub>w</sub> to denote the moment magnitude of the design earthquake)
- Use a factor of safety against liquefaction of 1.0
- See Appendices A and B for examples of CPT and SPT based liquefaction evaluation, respectively.



## Reporting

Discuss liquefaction in the "Other Seismic Hazards" section of all reports.

Language used in reporting liquefaction potential must be clear and direct. Do not use indefinite terms such as "low", "moderate" and/or "high". Acceptable language is:

- "Liquefaction potential exists"
- "Liquefaction potential is unknown or cannot be determined based on the available information" preliminary reports only>
- "Liquefaction potential does not exist"

Include the following in the <u>Recommendations</u> section of the Preliminary Geotechnical Design Report, Geotechnical Design Report, Preliminary Foundation Report, and Foundation Report.

- Groundwater elevation used for liquefaction
- Liquefaction Potential table

 Location
 Liquefaction Elevation (feet)

 Station 0+00 to 0+50
 Elev. 20 to 15 Elev. 0 to -10

 Station 0+50 to 0+80
 Elev. 10 to -5

 Station 0+80 to 1+30
 Elev. 20 to 10

Table X: Liquefaction Potential

If requested by the client, include a three-dimensional plot of liquefiable soils.



#### References

- 1. Andrus, R. D. and Stokoe, K. H., 2000, "Liquefaction Resistance of Soils from Shear-Wave Velocity," Journal of Geotechnical and Geo-Environmental Engineering, ASCE, Vol. 126, No. 11
- 2. Boulanger, R. W. and Idriss, I. M., 2006, "Liquefaction Susceptibility Criteria for Silts and Clays," Journal of Geotechnical and Geo-Environmental Engineering, ASCE, Vol. 132, No. 11
- 3. Caltrans, AASHTO LRFD Bridge Design Specifications with California Amendments
- 4. California Department of Conservation, Division of Mines and Geology (California Geological Survey), 2008, "Guidelines for Evaluating and Mitigating Seismic Hazards in California," CDMG Special Publication 117A
- 5. Caltrans, Memo to Designers 20-14, "Quantifying the Impacts of Soil Liquefaction and Lateral Spreading on Project Delivery," Caltrans Division of Engineering Services, Office of Earthquake Engineering
- 6. Caltrans, "Foundation Report Preparation for Bridges," Caltrans Division of Engineering Services, Geotechnical Services.
- 7. Caltrans, "Guidelines for Preparing Geotechnical Design Reports, Version 1.3," Caltrans Division of Engineering Services, Geotechnical Services.
- 8. National Academies of Sciences, Engineering, and Medicine, "State of the Art and Practice in the Assessment of Earthquake-Induced Soil Liquefaction and its Consequences", Committee on the State of the Art and Practice in Earthquake Induced Soil Liquefaction Assessment; Board on Earth Sciences and Resources; Division on Earth and Life Studies, 2016.
- 9. Kulhawy, F.H and Mayne, P.W. "Manual on Estimating Soil Properties for Foundation Design," Electric Power Research Institute, Palo Alto, Ca. 1990.
- 10. Seed, H.B., Tokimatsu, K., Harder, L. F., and Chung, R, 1985. "Influence of SPT Procedures in Soil Liquefaction Resistance Evaluation," Journal of Geotechnical and Geo-Environmental Engineering, ASCE, Vol. 111, No. 12
- 11. Youd, T.L., et al., 2001, "Liquefaction Resistance of Soils: Summary Report from the 1996 NCEER and 1998 NCEER/NSF Workshops on Evaluation of Liquefaction Resistance of Soils," in Journal of Geotechnical and Geo-Environmental Engineering, October 2001



# **Liquefaction Evaluation Example (CPT Method)**

Seal Beach Blvd Overcrossing Bridge replacement is a proposed 2 span cast-in-place prestressed concrete box girder structure. A quantitative liquefaction analysis is required following the procedures described in Youd et al, (2001).

The following information is required:

- Seismic design ground motion parameters including peak ground acceleration (PGA) corresponding to a return period of 975-years, and the de-aggregated mean earthquake moment magnitude (M) for PGA. These data are obtained by running ARS Online webtool using the latitude and longitude 33.7736 N, -118.0749 W.
- Soil data from CPT results. (Figure 1)
- Groundwater data as shown on the LOTB dated April 24, 2008. (Figure 2)




Figure 1: CPT Sounding Data

Poorly graded SAMO with SILT (SP-SM): very dense, dark gray, moist, about 90% fine SAMO, about 10% fines, trace shall fragment, namplastic

Clayey Soil

Clayey Soil



50/5.5"11.41 3

(0)(M)

4812.41 6 W (M) PP -

REF 12.41.4

6711.41.5

15.58

15.75

-0.6

-0.8

Clay

Clay

R 08 003 SAMDY SILT (M.I. hard, dark gray, maist, about 45% fine SAMD, about 55% fines, frace rootlets, mapplastic frace rootlets, mapplastic fines, and samples for fines, and samples for fines, frace rootlets, madium plasticity 90% fines, trace rootlets, madium plasticity 90% fines, trace rootlets, madium plasticity shows 10% fine to medium SAMD, about 10% fines, rooc rootlets, medium plasticity gray, moist, about 70% fines frace rootlets, medium plasticity gray, moist, obout 70% fine SAMD, about 90% fines, trace mico, with lense of lean (LAY, nonpolastic becomes about 80% fine SAMD, about 20% fines, trace mico, with lense of lean (LAY, nonpolastic 5"----El. +15.00 ft 50/472.41 8 //1 N (M)(PP) SILTY SAND with GRAVEL (SN) encountered LEAN CLAY (CL): dark gray, moist, medium stiff, high plasticity 50/512.4[10 (N)(N)(P) \ ..... REF1.4[11] GWE 0 ft VA 24/2008 VA 2.9 1 SILT to SANDY SILT (ML): medium stiff, brown, REF[1.4]12 LEAN CLAY (CL): dark gray, maist, 4% fine SAND, 96% fines, trace mica, medium plasticity REF[1.4]13

(REF) 1.4| 14

HEFT1.4115 W

(NEF11.4117)

Figure 2: Log of Test Boring (LOTB)

Step 1: Determine Groundwater Elevation

Poorly graded SAND (SP) encountered

The design groundwater elevation is the level shown on the LOTB for boring R 08 003. There is no reason to adjust the groundwater elevation. GW elevation is 0 feet, 15 feet below the ground surface. (Figure 1)

Step 2: Identify the Soil Layers for Quantitative Liquefaction Analysis.

PROFILE

VERTICAL 1" = 10'
HORIZONTAL 1" = 40'

The CPT 08-152 sounding provides the soil behavior type in increments of 0.16 feet. The following table illustrates <u>some</u> representative layers throughout the depth, where the <u>soil</u> behavior type is evaluated.

Soil Layer Depth Elevation Potential for Behavior Thickness Reason for Evaluation (feet) (feet) Liquefaction Type (feet) 1.15 13.9 0.16 Not Liquefiable Above Ground Water Surface Sand 15.09 -0.1Sand 0.16 Liquefiable **Below Ground Water** 15.26 -0.3Sand 0.16 **Below Ground Water** Liquefiable 15.42 -0.4 Sand 0.16 Liquefiable **Below Ground Water** 

0.16

0.16

Table 1: Liquefaction Evaluation for CPT-08-152.

Not Liquefiable

Not Liquefiable



The layer at depth of 15.26 feet (elevation of -0.3 feet) shows the potential for liquefaction based on Table 1. For this example, this sandy layer will be analyzed.

Step 3: Obtain CPT Data

Obtain cone tip bearing and sleeve friction values from the CPT printout.

Cone Tip bearing: q<sub>c</sub> = 40.2 tsf (depth 15.26 feet)

and

Cone Sleeve Friction: fs = 0.6 tsf (Obtained from the CPT report.)

Step 4: Soil Unit Weight

Determine soil unit weight = 0.06 tcf

Step 5: Calculate/Determine the CPT Soil Behavior Type Index

From Youd et al (2001), equation (14)

Ic: Soil Behavior Index

 $I_c = [(3.47 - \log Q)^2 + (1.22 + \log F)^2]^{0.5} = 2.30$ 

Where,

Q: Dimensionless normalized CPT penetration resistance

F: Normalized friction ratio

From Youd et al (2001), equation (15)

Q = 
$$[(q_c - \sigma_{v0})/P_a][(P_a/\sigma'_{vo})^n] = 43.16$$

and

From Youd et al (2001), equation (16)

 $F = [f_s/q_c - \sigma_{vo}] \times 100\% = 1.48\%$ 

n: Exponent = 1.0 (clay)

 $\sigma_{v0}$ : Total Overburden Pressure = 15.26 x 0.06 = 0.92 tsf

 $\sigma'_{vo:}$  Effective Overburden Pressure = (15.26 -15) x (0.06 - 0.031) + (15 x 0.06) = 0.91 tsf



Pa = Atmospheric Pressure = 1.04 tsf

First calculate Soil Behavior Index ( $I_c$ ) with n=1. If the calculated  $I_c$  is greater than 2.6, the soil behavior is clayey and is not liquefiable. If the calculated  $I_c$  is less than 2.6, the soil is most likely granular in nature and Q should be recalculated using an exponent, n = 0.5.

Since Ic < 2.6, Q is recalculated, with n= 0.5

From Youd et al (2001), equation (17)

Q =  $[(q_c - \sigma_{v0})/P_a][(P_a/\sigma'_{vo})^n] = 37.8 \times 1.07 = 40.48$ 

n: Exponent = 0.5 (sand)

 $P_a$  = Atmospheric Pressure = 1.04 tsf

 $\sigma_{v0}$ : Total Overburden Pressure = 15.26 x 0.06 = 0.92 tsf

 $\sigma'_{vo}$ : Effective Overburden Pressure = (15.26 -15) x (0.06 - 0.031) + (15 x 0.06) = 0.91 tsf

Step 6: Normalize Cone Penetration Resistance

Cone penetration resistance is corrected for overburden stress as follows:

From Youd et al (2001), equation (12)

q<sub>c1N</sub>: Dimensionless cone penetration resistance corrected for overburden stress

 $q_{c1N} = C_Q (q_c/P_a) = 41.42$ 

Where,

From Youd, equation (13)

 $C_Q = (P_a/\sigma'_{vo})^n = 1.07$ 

C<sub>Q</sub> is a normalizing factor for cone penetration resistance.

Step 7: Calculate Clean Sand Equivalent Normalized Cone Penetration Resistance

Correct the normalized penetration resistance,  $(q_{c1N})$ , of sands with fines to an equivalent clean sand value,  $(q_{c1N})_{cs}$ :

From Youd et al (2001), equation (18)

 $(q_{c1N})_{cs} = K_c q_{c1N} = 84.16$ 



Where the CPT correction factor for grain characteristics, Kc, is defined as:

From Youd et al (2001), equation (19a)

For  $I_c \le 1.64 \text{ K}_c = 1.0$ 

From Youd et al (2001), equation (19b)

For  $I_c > 1.64 \text{ Kc} = -0.403 I_c^4 + 5.581 I_c^3 - 21.63 I_c^2 + 33.75 I_c - 17.88$ 

 $I_c = 2.3$  and  $K_c = 2.03$  (8)

Step 8: Calculate Cyclic Resistance Ratio: CRR

From Youd et al (2001), equation (11b)

Step 9: Determine Cyclic Stress Ratio (CSR)

From Youd et al (2001), equation (1)

CSR =  $0.65 \text{ a}_{\text{max}}(\sigma_0 / \sigma'_0) r_d$ 

Where:

- $\sigma_0$  and  $\sigma'_0$  are total and effective vertical overburden stresses, respectively.
- a<sub>max</sub> is peak horizontal acceleration (PGA) in g.
- *r<sub>d</sub>* is a stress reduction coefficient.

For this example:

 $a_{max} = 0.6g$ 

Determine Stress Reduction Coefficient, rd.

Depth (z) is 15.26'= 4.65 m

 $r_d$ =1.0-0.00765 · z for z≤9.15 m

 $r_d = 1.0 - 0.00765 \cdot 4.65 = 0.96$ 



Step 10: Calculate the Magnitude Scaling Factor (MSF)

For this example,  $M_W$  = Mean Earthquake Moment Magnitude, M = 7.0

$$MSF = 10^{2.24}/M_w^{2.56} = 10^{2.24}/7.0^{2.56} = 1.19$$

Step 11: Calculate the Factor of Safety against Liquefaction

$$FS = (CRR_{7.5}/CSR) \times MSF$$

$$FS = (.14/.38) \times 1.19 = 0.42$$

Since the FS < 1, the geotechnical report must state that liquefaction is predicted to occur in this layer.

To complete the liquefaction analysis for the site, repeat the above steps for each layer identified as susceptible to liquefaction.



## **Liquefaction Evaluation Example (SPT Method)**

Live Oak Creek Bridge is a proposed single span bridge crossing Live Oak Creek. Preliminary screening, based on the "As-Built" LOTBs for the existing Live Oak Creek Bridge (Br. No. 57-0070), indicate the possibility of liquefaction. A quantitative liquefaction analysis is required following the SPT procedures described in Youd et al, (2001).

The following information is required:

- Seismic design ground motion parameters including peak ground acceleration (PGA) corresponding to a return period of 975-years and the de-aggregated mean earthquake moment magnitude (M). These data are obtained by running the ARS Online webtool using the latitude and longitude 33.31525 N, -117.194225W.
- Soil data from SPT results. Hammer efficiency and soil descriptions are shown on the LOTB dated 11-1-2012 (Attachment 1).
- Groundwater data as shown on the LOTB dated 11-1-2012 (Attachment 1).

### Step 1: Determine Groundwater Elevation

The design groundwater elevation is the level shown on the LOTB for Boring RC-11-001. There is no reason to adjust the groundwater elevation.

Step 2: Identify the Soil Layers for Quantitative Liquefaction Analysis.

The LOTB shows two borings with soil data to be evaluated: RC-11-001 and RC-11-002.

RC-11-001 shows five soil layers; preliminary liquefaction evaluation results are presented in Table 1.



Table 1: Preliminary Liquefaction Evaluation for Boring RC-11-001.

Layer	Elevation	Soil Type	Thickness	Preliminary Evaluation	Reason for Evaluation
1	210-205	SP	5'	Not Liquefiable	Above groundwater table
2	205-200	SM	5'	Not Liquefiable	Above GW table, fines content > 30%
3	200-194	SP	3'	Not Liquefiable above 197'	Above the groundwater table
3	200-194	<b>5</b> F	3'	Liquefiable below 197'	Granular, <5% fine, SPT N<30, below the GW table
4	194-179	SW	15'	Liquefiable	Granular, <5% fines, SPT N<30, below the GW table.
5	179-150	SP	29'	Liquefiable	Granular, <5% fines, SPT N<30, below the GW table

Most of the soils below groundwater table show the potential for liquefaction based on preliminary qualitative analysis. Only the soil layer 4 at RC-11-001 is quantitively analyzed herein as an example.

Effective unit weights of the soil layers (from Soil Properties Module) are:

- Layer 1: 120 pcf.
- Layer 2: 110 pcf.
- Layer 3: 120 pcf from 200' to 197', 57.6 pcf from 197' to 193'.
- Layer 4: 67.6 pcf.



# Step 3: Correct SPT Blow Count Data

From Youd et al (2001), equation (8 and Table 2) the corrected SPT N-value is:

 $(N_1)_{60} = N_m C_N C_E C_B C_R C_S$ , where

- (N<sub>1</sub>)<sub>60</sub> = corrected normalized SPT blow count.
- N<sub>m</sub>= measured SPT blow count.
- $C_N$  = depth correction factor =  $C_N$ =  $(P_a/\sigma'_{VO})^{0.5}$  from Youd et al (2001) equation (9)
  - $_{\odot}$  P<sub>a</sub> = 1 atm = 2116 psf and  $_{\odot}$ vo = effective overburden pressure at the time the SPT was done.
- C<sub>E</sub> = hammer energy correction factor (ER<sub>i</sub> / 60)
- C<sub>B</sub> = borehole diameter correction factor.
- C<sub>R</sub> = rod length correction factor
- Cs = correction factor for samplers with or without liner.

#### For this example:

- N<sub>m</sub>= 16 (Measured Blow count at 25' depth)
- $C_N = (2116/2225)^{0.5} = 0.975$
- $C_E = 68 / 60 = 1.13$
- C<sub>B</sub> = 1
- C<sub>R</sub> = .95
- C<sub>S</sub> = 1.2 (no liner used)

#### Thus

$$(N_1)_{60} = N_m C_N C_E C_B C_R C_S$$
  
= 16 x 0.975 x 1.13 x 1 x .95 x 1.2  
= 20

# Step 4: Determine Cyclic Stress Ratio (CSR)

From Youd et al (2001), equation (1), CSR = 0.65  $a_{max}(\sigma_{Vo}/\sigma'_{Vo})r_d$ 

#### Where:

- $\sigma_{VO}$  and  $\sigma'_{VO}$  are total and effective vertical overburden stresses, respectively.
- a<sub>max</sub> is peak horizontal acceleration (PGA) in g.
- *r<sub>d</sub>* is a stress reduction coefficient.



For this example:

$$a_{max} = PGA = 0.4g$$

Step 4A: Calculate Overburden Stresses.

Use the approximate center elevation of the layer at 185' (depth = 25').

$$\sigma'_{v0}$$
=120 x 5 + 110 x 5 + 120 x 3 + 3 x 57.6 + 67.6 x 8 =2225 psf

$$\sigma_{v0}$$
 = 120 x 5 +110 x 5 + 120 x 6 + 130 x 8 = 2910 psf

Step 4B: Determine Stress Reduction Coefficient, rd.

Depth (z) is 25'= 7.6m

From Youd et al (2001), equation (2a),

$$r_d = 1.0 - 0.00765 \cdot z$$

for z≤9.15 m

$$r_d = 1.0 - 0.00765 \cdot 7.6 = 0.94$$

Step 4C: Determine CSR

From Youd et al (2001), equation (1)

CSR = 
$$0.65 \text{ a}_{\text{max}}(\sigma_{\text{Vo}}/\sigma'_{\text{Vo}})r_{\text{d}}$$

CSR= 
$$0.65 \times (0.4) \times (2910/2225) \times 0.94 = 0.32$$

#### Step 5: Fines Content Correction

From Youd et al (2001), equation (5)

$$(N_1)_{60cs} = \alpha + \beta(N_1)_{60}$$
, where

- (N<sub>1</sub>)<sub>60cs</sub> is the blow count corrected for fines content
- α and β are coefficients that depend on the fines content.

#### For this example

- $\alpha$ = 0 (Youd et al, 2001, equation 6a since the sample has < 5% fines)
- β= 1.0 (Youd et al, 2001, equation 7a since the sample has <5% fines)

$$(N_1)_{60cs} = \alpha + \beta (N_1)_{60}$$



$$(N_1)_{60cs} = 0 + 1(20)$$

Step 6: Calculate Cyclic Resistance Ratio (CRR)7.5

From Youd et al (2001), equation (4)

$$CRR_{7.5} = \frac{1}{34 - (N_1)_{60cs}} + \frac{(N_1)_{60cs}}{135} + \frac{50}{[10(N_1)_{60cs} + 45]^2} - \frac{1}{200}$$

For this example:

 $(N_1)_{60cs} = 20$ 

$$CRR_{7.5} = \frac{1}{34 - 20} + \frac{20}{135} + \frac{50}{[10(20) + 45]^2} - \frac{1}{200}$$

$$CRR_{7.5} = 1/14 + 20/135 + 50/245^2 - 1/200$$
  
= 0.071+0.148+0.001 - .005  
= 0.22

CRR<sub>7.5</sub> can alternatively be read directly from Youd et al (2001) Figure 2 replacing ( $N_1$ )<sub>60</sub> with ( $N_1$ )<sub>60cs</sub> and using the liquefaction boundary curve identified as "SPT Clean Sand Base Curve".

Step 7: Calculate the Magnitude Scaling Factor (MSF)

For this example,  $M_W = M = 7.6$ 

From Youd et al (2001) equation (24)

$$MSF = 10^{2.24}/M_w^{2.56}$$

$$MSF = 10^{2.24}/7.6^{2.56} = 0.97$$

Step 8: Calculate the High Confining Pressure Correction Factor (Ko)

From Youd et al (2001) equation (31)

$$K_{\sigma} = (\sigma'_{v0}/P_a)^{(f-1)}$$

σ΄ v0: Effective Overburden Pressure



Pa: Atmospheric Pressure

f: exponent that is a function of site conditions, including relative density, stress history, aging and overconsolidation ratio

From Kulhawy and Mayne (1990), Equation 2-16:

 $D_r^2 = (N_1)_{60} / (C_p.C_A.C_{OCR})$ 

For normally consolidated (NC) unaged sand:

 $C_p = 60 + 25 \log D_{50}$ 

Cp: Parameter for grain size

D<sub>r</sub>: Relative density (%)

D<sub>50:</sub> Median diameter of sand (mm)

For aged sand:

 $C_A = 1.2 + 0.05 \log (t/100)$ 

C<sub>A</sub>: Parameter for aging

t: Time since deposition in years

For overconsolidated (OC) sand:

C<sub>OCR</sub> = OCR<sup>0.18</sup>

Cocr: Parameter for overconsolidation

OCR: Overconsolidation ratio:  $\sigma'_p/\sigma'_{v0}$ 

Where:

σ'p: Preconsolidation pressure

 $\vec{\sigma_{v0:}}$  Effective overburden pressure



For this example:

Soil is normally consolidated sand and unaged

$$C_p = 60 + 25 \log D_{50}$$

$$D_{50} = 0.5 \text{ mm}$$

$$C_p = 60 + 25 \log (0.5) = 52.47$$

$$C_A = 1$$

$$D_r^2 = (N_1)_{60cs} / (C_p.C_A.C_{OCR})$$

$$(N_1)_{60} = 20$$

$$D_r^2 = 20/52.47 = 0.36$$

$$D_r = 60\%$$

From Youd et al (2001), figure 15

For 
$$D_r = 60\%$$
,  $f = 0.7$ 

$$K_{\sigma} = (2225/2116)^{(0.7-1)}$$

$$= 0.985$$

Step 9: Calculate the Sloping Ground Correction Factor (Ka)

For this example:

Level ground:  $K_{\alpha} = 1$ 

α: Static stress ratio

$$\alpha = \tau_h / \sigma'_{v0}$$

Th: Static shear stress on the horizontal plane

σ΄ <sub>v0:</sub> Effective overburden pressure



Step 10: Calculate the Factor of Safety against Liquefaction

From Youd et al (2001), equation (30):

FS = (CRR<sub>7.5</sub>/CSR) x MSF x  $K_{\sigma}$  x  $K_{\alpha}$ 

 $FS = (.22/.32) \times .97 \times 1.0 \times 0.985$ 

=0.66

Since FS is less than 1, the geotechnical report needs to state that liquefaction is predicted to occur in this layer.

To complete the liquefaction analysis for the site, repeat the above steps for all other soil layer identified as potentially liquefiable.



## **Attachment 1**

