

Mechanically Stabilized Embankment Construction Checklist

I. SOURCES OF INFORMATION

- [Bridge Design Specifications](#), Section 5, *Retaining Walls*.
- [Bridge Design Aids](#) – Chapter 3-8, *Mechanically Stabilized Embankments*.
- [Caltrans Highway Design Manual](#) – Chapter 200, Topic 210, *Reinforced Earth Slopes and Earth Retaining Systems*.
- Earth Retaining Systems Committee web page at <https://des.onramp.dot.ca.gov/structure-policy-innovation/earth-retaining-systems>

II. PROPRIETARY EARTH RETAINING SYSTEMS

The contract Special Provisions usually gives the contractor the option of choosing one of the proprietary systems listed in the Department’s current list of pre-qualified earth retaining systems. These systems are alternatives to the fully detailed State system shown on the contract plans. The pre-qualified list can be accessed from the SC home page under “[Field Resources](#).”

III. POTENTIAL PROBLEMS

Observation	Potential Cause
Wall Distortion:	
<ul style="list-style-type: none"> • Differential settlement that causes panels to contact each other resulting in chipping or spalling. • Low spot in the wall profile. • Overall wall leaning. 	<ul style="list-style-type: none"> • Weak or improper bearing material. • Inadequate compaction and/or poor-quality foundation material 1. • Leveling pad not constructed per the tolerances specified in the approved shop plans.
Wall Leaning Out (away from backfill).	
<ul style="list-style-type: none"> • Backfill material pushed against back of wall before being compacted on the strips. • Excessive or vibratory compaction on uniform fine sand (more than 60% passing a No. 40 sieve). 	<ul style="list-style-type: none"> • Panels not battered sufficiently. • Large backfill placing and/or compaction equipment working within the 3' zone from the back of the wall. • Backfill material dumped too close to the free end of reinforcing strips, then spread towards back of wall, causing bulge in strips and pushing panels out.

	<ul style="list-style-type: none"> • Backfill material too wet. • Backfill contains excessive fines materials (beyond the Specifications for percent of materials passing a No. 200 sieve). • Wedges not seated securely. • Excessive lift thickness. • Clamps not tight. • Plasticity Index of backfill material in excess of the specification limit.
Observation	Potential Cause
Wall Leaning In (towards backfill).	<ul style="list-style-type: none"> • Excessive batter set in panels for select granular backfill material being used. • Inadequate compaction of backfill. • Panels excessively battered. • Improper Compaction of lower backfill levels. • Settlement of the original ground behind the wall.
Localized differential distortion between adjacent panels that causes points of inflection and excessively wide joints.	<ul style="list-style-type: none"> • Adjacent panels set at different battered angles.