

**2020 SHOPP As of August 2023 Close-Out
(\$1,000)**

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
10	Alpine	89	10.300/R19.400	Near Markleeville and Alpine Village, from 0.3 mile north of Route 4 to 1.0 miles south of Diamond Valley Road (south). Remove hazardous trees and debris, replace damaged fencing, and place erosion control.	1N690	3523	1022000012	201.130	21-22	\$10	\$7,346	\$7,346	9/9/21	NH	\$120	\$40	\$50	\$500	\$8,066	1	Location(s)	
10	Alpine	89	15.200/R16.900	Near Markleeville, from 0.3 mile north of Montgomery Street to 0.4 mile south of Turtle Park Road. Replace culverts to increase hydraulic capacity, install erosion control and sediment capturing devices, and install rock slope protection (RSP).	1P060	3542	1022000065	201.130	21-22	\$75	\$4,457	\$4,457	8/18/22	NH	\$150	\$175	\$50	\$600	\$5,507	5	Location(s)	
10	Amador	49	0.000	Near Jackson, at Mokelumne River Bridge No. 26-0012. Upgrade bridge rails, widen shoulders, and apply polyester concrete overlay on bridge deck.	0X752	3219	1017000004	201.112	21-22	\$58	\$4,254	\$4,581	10/12/22	HBRR-S	\$1,590	\$2,010	\$135	\$2,055	\$10,102	810.0	Linear feet rail	
10	Amador	88	7.900/R65.800	Near Jackson, from 0.5 mile east of Route 104 to 5.5 miles west of Kirkwood Meadows Road at various locations. Upgrade guardrail to make standard.	1C360	3199	1016000136	201.015	20-21	\$35	\$3,693	\$4,130	6/23/21	STP	\$536	\$1,000	\$0	\$800	\$6,064	5.0	Collision(s) reduced	
10	Amador	88	15.000/R38.500	Near Jackson, Pine Grove, Pioneer, and Barton, from 0.1 mile east of Court Street to 1.7 miles west of Omo Ranch Road. Remove hazardous trees, brush, and debris, and repair drainage ditches and pavement.	1P670	3544	1022000150	201.130	21-22	\$10	\$2,736	\$2,736	1/26/22	NH	\$120	\$40	\$50	\$200	\$3,156	1	Location(s)	
10	Amador	88	20.770	Near Pine Grove, at the intersection with Irishtown Road. Replace failed culvert, headwall and wing-walls, place rock slope protection (RSP), and repair roadway.	1N020	3504	1021000074	201.130	20-21	\$0	\$2,801	\$2,801	12/7/20	NH	\$10	\$35	\$3	\$200	\$3,049	1	Location(s)	
10	Amador	88	R62.000/71.000	Near Kirkwood, from 0.8 mile west of Tragedy Springs Road to 0.4 mile west of Kirkwood Meadows Drive; also in Alpine County from 1.0 mile east of Amador County line to 0.3 mile east of Schneider Cow Camp Road. Repair fire damaged drainage systems and pavement, remove hazardous trees and debris.	1N870	3536	1022000046	201.130	21-22	\$5	\$5,200	\$5,200	10/6/21	NH	\$30	\$25	\$5	\$425	\$5,690	11	Location(s)	
10	Amador	88	R69.000/70.000	Near Kirkwood, from 2.3 miles to 1.3 miles west of Kirkwood Meadows Drive. Repair fire damaged avalanche control system.	1N880	3537	1022000047	201.130	21-22	\$0	\$860	\$860	10/6/21	NH	\$10	\$20	\$5	\$60	\$955	8	Location(s)	
10	Calaveras	4	R14.700/16.100	Near Copperopolis and Angels Camp, from Pool Station Road to west of Appaloosa Way. Realign roadway, implement safety features by improving shoulder width, and rehabilitate culverts. Financial Contribution Only (FCO) to Calaveras County.	0E531	3067A	1018000164	201.120	20-21	\$0	\$10,325	\$10,325	6/23/21	NH	\$0	\$0	\$0	\$0	\$10,325	2.6	Lane mile(s)	
10	Calaveras	4	15.900/16.300	Near Angels Camp, at West Branch Cherokee Creek Bridge No. 30-0036. Replace bridge with new structure which meets current standards and provides shoulders for disabled vehicles, maintenance workers, pedestrians and bicycles. (Additional \$300,000 for PS&E from local contribution.)	1H500	3255	1017000154	201.110	21-22	\$278	\$5,786	\$5,313	8/18/22	HBRR-S	\$605	\$1,392	\$103	\$1,500	\$9,664	1	Bridge(s)	
10	Calaveras	4	36.000/50.000	Near Arnold, from Horseshoe Drive to 0.4 mile east of Meko Drive; also on Route 140 from 0.7 mile west of Rosa Road to 1.4 miles west of Lincoln Boulevard (PM 15.0/22.0). Remove debris and hazardous trees at various locations.	1P680	3545	1022000151	201.130	21-22	\$10	\$1,590	\$1,590	1/25/22	NH	\$100	\$30	\$40	\$150	\$1,920	2	Location(s)	
10	Calaveras	26	30.000	Near West Point, at South Fork Mokelumne River Bridge No. 30-0022 (PM 30.0), and at North Fork Mokelumne River Bridge No. 30-0049 (PM 38.3). Upgrade bridge railing at two structures, also seismic retrofit at one location.	0X751	3247	1015000128	201.112	21-22	\$685	\$5,094	\$3,848	10/12/22	HBRR-S	\$757	\$1,663	\$60	\$1,844	\$10,103	808.0	Linear feet rail	

**2020 SHOPP As of August 2023 Close-Out
(\$1,000)**

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
10	Mariposa	140	12.000/22.100	In and near the Mariposa community, from 1.7 miles east of Cathays Valley Park to the north Route 49 Junction. Rehabilitate pavement by repairing localized failure, grinding roadway, and overlaying with asphalt to extend pavement service life and improve ride quality. Work includes upgrading guardrail, rumble strips, and ADA curb ramps, and replacing drainage systems.	0Y770	3252	1015000008	201.121	21-22	\$318	\$17,363	\$16,832	3/23/23	NH	\$1,025	\$1,095	\$416	\$1,689	\$21,906	23.6	Lane mile(s)	
10	Mariposa	140	25.300/51.800	Near the community of Mariposa and El Portal, from East Whitlock Road to Yosemite National Park entrance. Rehabilitate pavement by grinding and overlaying asphalt. This project will extend and preserve pavement service life and improve ride quality and safety.	0Y780	3167	1016000025	201.121	21-22	\$162	\$23,765	\$24,334	8/18/22	NH	\$900	\$1,900	\$30	\$2,330	\$29,087	54.8	Lane mile(s)	
10	Mariposa	140	32.200	Near Briceburg, at 2.1 miles west of Bull Creek Road. Repair slope slipout and erosion damage at large culvert pipe outlet.	0Y340	3194	1014000182	201.150	20-21	\$40	\$2,800	\$2,205	8/18/21	NH	\$0	\$955	\$155	\$925	\$4,875	1	Location(s)	
10	Mariposa	140	42.000/42.700	Near El Portal and Yosemite National Park, at 0.5 miles west of South Fork Merced River. Construct rock shed. This is a Construction Manager/General Contractor (CMGC) project. (PS&E, R/W Sup Only)	0P921	0280	1014000148	201.131	20-21	\$0	\$0	\$0		NH	\$0	\$5,500	\$100	\$0	\$5,600	1	Location(s)	Mar-2019 / SHOPP-P-1819-11B
10	Mariposa	140	42.000/42.700	Near El Portal and Yosemite National Park, 0.5 miles west of South Fork Merced River. Early Work Package No. 1 for Ferguson Slide Construction Manager/General Contractor (CMGC) parent project EA 0P921. Remove rock talus.	0P923	0280B	1020000099	201.131	20-21	\$0	\$27,000	\$22,717	1/27/21	NH	\$0	\$0	\$0	\$8,000	\$35,000	0	Location(s)	
10	Merced	5	0.500/0.800	Near Los Banos and Firebaugh, at the John "Chuck" Erreca Safety Roadside Rest Area (SRRRA). Rehabilitate northbound and southbound SRRRA facilities.	1C790	3215	1016000046	201.250	20-21	\$5	\$23,913	\$25,602	5/12/21	NH	\$925	\$2,970	\$10	\$3,150	\$30,973	2	Location(s)	Mar-2019 / SHOPP-P-1819-11B
10	Merced	5	19.400	Near Santa Nella and Los Banos, at various locations. Apply polyester concrete overlay to bridge decks. (Bridge Deck Preservation)	1N430	3529	1021000185	201.119	21-22	\$0	\$1,982	\$1,638	5/18/22	RMRA	\$25	\$200	\$0	\$360	\$2,567	6	Bridge(s)	
10	Merced	5		In Merced, San Joaquin, Mariposa and Stanislaus Counties, on various routes at various locations. Scour mitigation and preventative structural maintenance measures at thirteen bridges.	1C810	3102	1015000038	201.119	20-21	\$496	\$3,200	\$3,441	3/24/21	HBRR-S	\$819	\$950	\$542	\$1,200	\$7,207	13	Bridge(s)	
10	Merced	99	R1.200	Near Merced, at 2.2 miles south of Plainsburg Road. Repair pavement settlement by injecting polyurethane under pavement.	1N710	3541	1022000014	201.130	21-22	\$0	\$1,800	\$1,800	11/23/21	NH	\$10	\$60	\$5	\$150	\$2,025	1	Location(s)	
10	Merced	99	4.600	Near the city of Merced, at 1.3 miles north of Plainsburg Road. Repair fire damaged pavement, culvert, and Traffic Management System (TMS) element.	1M470	3486	1020000189	201.130	20-21	\$0	\$370	\$370	7/27/20	NH	\$5	\$15	\$0	\$60	\$450	1	Location(s)	
10	Merced	99	19.700/20.200	In and near Atwater, at Atwater-Merced Expressway Interchange. Landscape mitigation for roadway rehabilitation project EA 3A720.	3A721	5431Y	1019000020	201.122	21-22	\$5	\$1,514	\$1,784	8/18/22	NH	\$400	\$690	\$10	\$1,100	\$3,719	0.0	Lane mile(s)	
10	Merced	99		In Merced County, in the cities of Merced, Atwater, and Livingston, on Routes 59 and 99, at various locations. Construct hardened fence and repair slope damage.	1N600	3554	1022000001	201.130	21-22	\$0	\$4,435	\$4,435	2/17/22	NH	\$250	\$0	\$30	\$627	\$5,342	6	Location(s)	
10	Merced	140	2.300/49.000	In and near the cities of Gustine and Merced, from Outside Canal Bridge No. 39-0055 to 1.3 miles west of Mariposa County line, at various locations. Replace bridge approach guardrail on two bridges and remove obstructions from clear recovery zone at twelve locations. Work also includes constructing headwalls and extending culverts. This project will reduce the number and severity of collisions.	0Y130	3074	1013000243	201.015	21-22	\$1,416	\$4,225	\$3,234	3/23/23	STP	\$1,279	\$769	\$252	\$1,172	\$9,113	8.0	Collision(s) reduced	

**2020 SHOPP As of August 2023 Close-Out
(\$1,000)**

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
10	Merced	152	11.300	Near Los Banos, at Route 33 Interchange; also on Route 5 (PM 6.3) at Route 165 Interchange. Improve the truck turn radius.	0T680	3214	1017000005	201.310	21-22	\$274	\$2,216	\$2,590	1/26/22	NH	\$495	\$850	\$64	\$630	\$4,529	48.0	Daily vehicle hour(s) of delay (DVHD)	
10	Merced	152	21.000	In Los Banos, at the intersection with South 11th Street. Improve safety by installing new traffic signal.	1J300	3417	1018000101	201.010	20-21	\$300	\$1,527	\$1,394	11/3/20	STP	\$480	\$1,045	\$93	\$596	\$4,041	10.0	Collision(s) reduced	
10	Merced	152	26.300/R40.700	Near Los Banos, from 0.4 mile east of Midway Road to 0.2 mile west of Route 59. Upgrade guardrail to make standard.	1C370	3740	1017000043	201.015	20-21	\$13	\$2,598	\$2,767	12/2/20	STP	\$650	\$939	\$12	\$745	\$4,957	4.0	Collision(s) reduced	
10	San Joaquin	4	R17.300	In Stockton, at Aurora Street Undercrossing. Repair highway facilities.	1M610	3491	1021000015	201.130	20-21	\$0	\$600	\$600	8/24/20	NH	\$10	\$20	\$0	\$120	\$750	1	Location(s)	
10	San Joaquin	5	R13.000	Near Lathrop, at Paradise Cut Bridge No. 29-0032R; also on Route 205 at the eastbound Route 205 to northbound 5 Connector Bridge No. 29-0032G (PM R13.11). Replace approach slabs, apply polyester concrete overlay to bridge decks and replace joint seals. (Bridge Deck Preservation)	1N570	3528	1021000212	201.119	21-22	\$0	\$2,813	\$2,834	5/18/22	RMRA	\$60	\$200	\$0	\$550	\$3,623	2	Bridge(s)	
10	San Joaquin	5	R21.400/27.900	In and near Stockton, on Route 5 at various locations; also on Route 4 (PM 14.6/26.0) and Route 99 (PM 15.8/18.5) at various locations. Install Transportation Management System (TMS) elements. This project will improve traffic management and keep the system network operating at a high level of reliability.	1F400	3250	1016000053	201.315	21-22	\$335	\$10,373	\$8,420	8/18/22	NH	\$820	\$2,550	\$380	\$1,805	\$16,263	28	Field element(s)	
10	San Joaquin	5	26.100/26.500	In Stockton, at the Stockton Channel Viaduct Bridge No. 29-0176L/R. Bridge rehabilitation to address structural and load carrying capacity deficiencies. This is a Design-Build project. (PA&ED and PS&E Only)	0X460	3133	1012000259	201.110	20-21	\$0	\$0	\$0		HBRR-S	\$4,169	\$18,802	\$0	\$0	\$22,971	0	Bridge(s)	
10	San Joaquin	5	45.900	Near Thorton, at Beaver Slough Bridge No 29-0247R. Repair bridge joints, unsound concrete, and place polyester concrete overlay.	1N200	3508	1021000104	201.130	20-21	\$0	\$1,000	\$1,000	2/4/21	NH	\$15	\$50	\$0	\$435	\$1,500	1	Location(s)	
10	San Joaquin	5	49.000/49.300	Near Thorton, on northbound Route 5 from 0.2 mile south to 0.1 mile north of Barber Road Undercrossing. Repair failed pavement.	1Q200	3559	1022000252	201.130	21-22	\$0	\$923	\$923	6/10/22	NH	\$20	\$0	\$0	\$250	\$1,193	1	Location(s)	
10	San Joaquin	12	R4.400	Near Terminous, at Little Potato Slough Bridge No. 29-0101. Replace joint seals and bearing pads using temporary pile supports.	1F760	3273	1017000024	201.119	20-21	\$300	\$3,700	\$3,117	8/18/21	HBRR-S	\$553	\$1,005	\$2	\$1,280	\$6,840	1	Bridge(s)	
10	San Joaquin	12	17.400/18.100	In Lodi, from Stockton Street to Route 99. Upgrade pedestrian facilities to make compliant with the Americans with Disabilities Act (ADA) standards.	1G510	3254	1017000016	201.361	21-22	\$479	\$2,793	\$2,846	3/16/22	NH	\$286	\$770	\$915	\$637	\$5,880	10	Curb ramp(s)	
10	San Joaquin	26	1.110	Near Stockton, at Route 26/99 Separation No. 29-0142 (PM 1.11). Establish standard vertical clearance.	1F170	3169	1016000032	201.322	20-21	\$7	\$11,536	\$8,353	6/23/21	RMRA	\$598	\$1,827	\$13	\$3,221	\$17,202	1	Bridge(s)	
10	San Joaquin	88	13.700/14.000	Near Lockeford, from 0.1 mile north of East Jack Tone Road to 0.1 mile south of north Tully Road intersection; also near Kirkwood, in Alpine County (PM 0.2/2.5). Replace culverts.	0S740	3141	1013000260	201.151	20-21	\$1,306	\$4,090	\$3,782	6/23/21	NH	\$795	\$900	\$290	\$875	\$8,256	39	Culvert(s) (ea)	
10	San Joaquin	99	4.600/5.300	In Manteca, from south of Austin Road to south of Route 99/120 Separation. Operational improvements by lengthening and reconstructing overcrossing and railroad overhead, eliminate one interchange, and upgrade safety barriers. Financial Contribution Only (FCO) to San Joaquin Council of Governments (SJCOG) for construction implementation.	1E74U	3126A	1018000159	201.310	21-22	\$0	\$28,736	\$0		NH	\$263	\$20	\$0	\$0	\$29,019	2,385.0	Daily vehicle hour(s) of delay (DVHD)	
10	San Joaquin	99	14.400/29.400	In and near Stockton and Lodi, at various locations from 0.3 mile south of Arch Road Undercrossing to South Lodi Overcrossing. Pave areas behind the gore and slopes to reduce maintenance and improve highway worker safety.	1C760	3237	1017000015	201.235	20-21	\$23	\$1,922	\$2,296	1/27/21	NH	\$495	\$1,130	\$15	\$790	\$4,375	26	Location(s)	

2020 SHOPP As of August 2023 Close-Out
(\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
10	San Joaquin	99	19.700/33.600	In and near Stockton and Lodi, at various locations from Eastside Underpass to Acampo Road; also on Route 4 at the Route 4/5 Separation (PM R16.10) and on Route 120 in Lathrop at Mossdale Underpass (PM R0.5). Upgrade drainage pump plants to reduce maintenance and repair costs, and increase reliability and efficiency. This project will keep the pump plants functioning at design capacity, ensuring stormwater is removed from the roadway and improve safety at these locations.	1E610	3229	1017000022	201.151	21-22	\$260	\$5,169	\$6,147	6/29/22	NH	\$439	\$1,530	\$59	\$1,289	\$8,746	5	Pump plant(s) (ea)	
10	San Joaquin	99	20.100	Near Stockton, at 0.2 mile south of Route 88. Repair fire-damaged bridge.	1N460	3518	1021000191	201.130	20-21	\$5	\$1,195	\$1,195	6/29/21	NH	\$15	\$80	\$5	\$550	\$1,850	1	Location(s)	
10	San Joaquin	99		In San Joaquin County, on Route 99 and Route 205, Merced County on Route 99, and also in Tuolumne County on Route 120 at various locations. Apply High Friction Surface Treatment (HFST).	1K960	3480	1019000163	201.010	21-22	\$0	\$2,740	\$2,104	12/15/21	STP	\$280	\$550	\$0	\$490	\$4,060	121.0	Collision(s) reduced	
10	San Joaquin	99		In the cities of Stockton, Lodi, and Ripon, on Routes 99, 4, and 5, at various locations. Construct hardened fence and repair slope damage.	1N490	3543	1021000199	201.130	21-22	\$0	\$8,587	\$8,587	2/8/22	NH	\$300	\$0	\$55	\$1,079	\$10,021	8	Location(s)	
10	San Joaquin	120	R0.600/R6.100	In and near Manteca and Lathrop, from Route 5 to Route 99; also on Route 5 at PM R13.34 and on Route 99 at PM 4.56. Install fiber optic cable as part of the Transportation Management System (TMS).	1C960	3230	1017000021	201.315	20-21	\$97	\$4,500	\$5,086	8/18/21	NH	\$373	\$1,221	\$5	\$1,375	\$7,571	8.9	Mile(s) of cable	
10	San Joaquin	120		In San Joaquin, Amador, Calaveras, Merced, Mariposa, Stanislaus, and Tuolumne Counties, on Routes 4, 5, 26, 33, 49, 59, 99, 104, 108, 120, 132, 140, 152 and 205 at various locations. Repair or replace damaged and nonfunctioning Traffic Management System (TMS) elements.	1G990	3226	1017000074	201.315	20-21	\$33	\$3,100	\$3,006	3/24/21	NH	\$632	\$1,191	\$107	\$1,243	\$6,306	20	Field element(s)	
10	San Joaquin	205	R4.500/R9.000	In Tracy, from Byron Road Undercrossing to Paradise Road Overcrossing. Install ramp meters and other Transportation Management System (TMS) elements.	1C330	3146	1014000146	201.315	21-22	\$1,923	\$20,100	\$19,983	10/13/21	NH	\$1,057	\$3,500	\$979	\$5,600	\$33,159	21	Field element(s)	Dec-2018 / SHOPP-P-1819-09B
10	Stanislaus	99	R10.000/R16.800	In and near Ceres and Modesto, at various locations from Mitchell Road to Kansas Avenue; also in Merced County, on Route 59 near the city of Merced, at Childs Avenue (PM 14.0). Upgrade drainage pump plants.	1E620	3251	1016000017	201.151	20-21	\$13	\$6,440	\$6,960	6/23/21	NH	\$278	\$1,142	\$93	\$1,991	\$9,957	6	Pump plant(s) (ea)	
10	Stanislaus	99		In the cities of Modesto, Turlock, and Ceres, at various locations. Construct hardened fence and repair slope damage.	1N610	3555	1022000002	201.130	21-22	\$0	\$6,900	\$6,900	2/9/22	NH	\$290	\$0	\$75	\$823	\$8,088	6	Location(s)	
10	Stanislaus	132	27.100/28.100	In Waterford, from 0.1 mile west of Reinway Avenue to E Street. Upgrade curb ramps and sidewalks to comply with the Americans with Disabilities Act (ADA) standards.	1G420	3241	1017000013	201.361	21-22	\$84	\$3,464	\$4,119	12/8/22	NH	\$683	\$1,337	\$723	\$718	\$7,009	29	Curb ramp(s)	
10	Tuolumne	108	R18.900/38.800	Near Long Barn, from 0.1 mile west of East Long Barn Road Connection to 2.3 miles east of Cow Creek Road. Pavement rehabilitation.	46210	0157	1013000266	201.121	20-21	\$8	\$16,406	\$15,433	5/12/21	NH	\$687	\$1,152	\$8	\$2,092	\$20,353	41.8	Lane mile(s)	
10	Tuolumne	108		At various locations, from Sonora to Dardanelle; also on Route 49 in Sonora (PM 17.6), on Route 120 near Chinese Camp (PM R6.0 to 11.3) and in Stanislaus County on Route 108 in and near Riverbank (PM 28.5 to 33.1) and Route 120 near Oakdale (PM 12.22). Upgrade guardrail to make standard. This project will reduce the number and severity of collisions.	1C400	3234	1017000025	201.015	21-22	\$194	\$4,508	\$5,362	8/18/22	STP	\$634	\$1,370	\$11	\$896	\$7,613	3.0	Collision(s) reduced	
10	Tuolumne	108		In Tuolumne County, in Sonora on Route 108, also in Amador County, in Jackson on Route 49 at various locations. Construct hardened fence and repair slope damage.	1N620	3556	1022000003	201.130	21-22	\$0	\$3,974	\$3,974	2/17/22	NH	\$165	\$0	\$100	\$496	\$4,735	6	Location(s)	