

2022 SHOPP As of January 2026 Close-Out

(x\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Con Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
03	Butte	32	4.166	Near Chico, at the intersection with Meridian Road. Install traffic signal to improve safety. This project will reduce the number and severity of collisions. (Additional contribution of \$500,000 for Const Cap from the Butte County Association of Governments (BCAG)).	2J860	2120	0322000116	201.010	22-23	\$80	\$2,600	\$2,600	3/23/23	STP	\$310	\$580	\$160	\$790	\$4,520	7.00	Collision(s) reduced	
03	Butte	32	5.000/10.200	In and near Chico, from Muir Avenue to Route 99 (PM 5.0/10.2L/R). Rehabilitate pavement, install signals and lighting, upgrade Transportation Management System (TMS) elements, rehabilitate drainage systems, and upgrade facilities to Americans with Disabilities Act (ADA) standards. This project will extend the pavement service life and improve ride quality.	4H760	2115	0319000046	201.121	23-24	\$2,430	\$24,900	\$29,568	1/26/24	NH	\$2,000	\$1,500	\$1,500	\$2,500	\$34,830	18.60	Lane mile(s)	
03	Butte	32	7.100/R8.400	In and near Chico, from West 8th Avenue to West 2nd Street. Add green bike lane treatment, install signs, and construct curb ramps to improve pedestrian and bicyclist safety. This project will reduce the number and severity of collisions.	0J921	6257A	0321000159	201.010	22-23	\$6	\$450	\$472	1/26/24	STP	\$0	\$39	\$10	\$45	\$550	5.00	Collision(s) reduced	
03	Butte	32	R9.500/R9.570	In Chico, at Main Street and Oroville Avenue (PM R9.5R/L to PM R9.57R/L). Upgrade traffic signals, install pedestrian push buttons and countdown signals, and restripe crosswalks to improve pedestrian safety. This project will reduce the number and severity of collisions.	1J910	2119	0321000143	201.010	23-24	\$269	\$1,205	\$791	1/26/24	STP	\$212	\$390	\$72	\$268	\$2,416	9.00	Collision(s) reduced	
03	Butte	32	R16.000/R23.000	Near Chico, from 2.0 miles west of Santos Way to 0.6 mile west of Forest Ranch Way. Remove storm damaged trees and debris.	4J570	2124	0323000208	201.130	22-23	\$0	\$1,800	\$1,800	4/11/23	NH	\$0	\$0	\$0	\$360	\$2,160	5.00	Location(s)	
03	Butte	70	35.000/36.000	Near Yankee Hill, from 0.4 mile south to 0.6 mile north of Deadwood Road. Stabilize slope and roadway, and install a slope inclinometer to monitor slope movement.	0N790	2308	0324000191	201.130	23-24	\$0	\$750	\$750	2/20/24	NH	\$0	\$0	\$0	\$240	\$990	1.00	Location(s)	
03	Butte	70	46.000/47.000	Near Paradise, from 0.8 mile west to 0.2 mile east of Shady Rest Area. Restore and repair damaged roadway by raising the existing vertical alignment by approximately five feet and protecting the embankment against future flooding with a soldier pile retaining wall, replace Bear Creek Bridge, and construct concrete barrier.	3H540	2293	0318000012	201.131	22-23	\$1,371	\$31,230	\$31,230	8/18/22	NH	\$0	\$0	\$0	\$5,000	\$37,601	1.00	Location(s)	
03	Butte	99	R3.100/5.000	In and near Gridley, from Hollis Lane to 0.4 mile north of Ford Avenue. Rehabilitate pavement, upgrade Transportation Management System (TMS) elements, rehabilitate drainage systems, and upgrade facilities to Americans with Disabilities Act (ADA) standards. This project will extend the pavement service life and improve ride quality. Additional \$4,256,000 contribution for PS&E, R/W Cap, and Const Cap from the City of Gridley, Butte County Association of Governments (BCAG), and Congestion Mitigation and Air Quality (CMAQ) Program.	1H140	2435	0316000060	201.121	23-24	\$947	\$16,600	\$19,754	10/18/24	NH	\$650	\$1,180	\$510	\$2,080	\$21,967	6.80	Lane mile(s)	
03	Butte	99	5.600	Near Gridley, at 0.5 mile north of Ord Ranch Road. Replace failed culverts and repair sinkhole.	4J180	2445	0323000128	201.130	22-23	\$0	\$600	\$600	2/7/23	NH	\$0	\$0	\$0	\$120	\$720	1.00	Location(s)	

2022 SHOPP As of January 2026 Close-Out

(x\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Con Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
03	Butte	99	R31.498	In Chico, at East 20th Street Overcrossing No. 12-0169. Repair damaged bridge girders.	0N480	2450	0324000120	201.130	23-24	\$0	\$800	\$800	11/16/23	NH	\$0	\$0	\$0	\$200	\$1,000	1.00	Location(s)	
03	Butte	99	R34.300	In Chico, at Cohasset Highway Overcrossing No. 12-0168. Apply polyester concrete overlay to bridge deck and replace joint seals. (Bridge Deck Preservation)	2G600	2442	0322000038	201.119	22-23	\$5	\$3,355	\$690	3/23/23	RMRA	\$180	\$375	\$30	\$525	\$4,470	1.00	Bridge(s)	
03	Butte	99	R36.305	Near Chico, at Eaton Road Overcrossing No. 12-0160. Repair damaged bridge girder.	0N470	2449	0324000119	201.130	23-24	\$0	\$450	\$450	11/29/23	NH	\$0	\$0	\$0	\$130	\$580	1.00	Location(s)	
03	Butte	162	20.700	Near Oroville, at Ward Boulevard. Replace culverts.	3J800	2642	0323000005	201.130	22-23	\$0	\$500	\$500	10/13/22	NH	\$0	\$0	\$0	\$100	\$600	1.00	Location(s)	
03	Colusa	5	R3.000/R9.000	Near Arbuckle, from 0.2 mile south of Greenbay Road Overcrossing to 1.3 miles south of Hahn Road. Repair failed pavement.	4J210	2797	0323000140	201.130	22-23	\$0	\$1,500	\$1,500	3/9/23	NH	\$0	\$0	\$0	\$300	\$1,800	5.00	Location(s)	
03	Colusa	20	R0.600/R1.200	Near Williams, from 0.6 mile east to 1.2 mile east of Lake County line; also at the intersection with Route 16 (PM 3.5). Upgrade existing signs, add new signs and flashing beacons, grind and replace existing pavement with asphalt and High Friction Surface Treatment (HFST), and upgrade guardrail to improve safety. This project will reduce the number and severity of collisions.	2J950	2796	0322000142	201.010	22-23	\$20	\$2,210	\$2,220	5/5/23	STP	\$360	\$640	\$90	\$620	\$3,940	11.00	Collision(s) reduced	
03	El Dorado	49		In El Dorado County on Routes 49, 50, and 193 at various locations. Remove debris, restore slopes, place erosion control, clean drainage inlets, regrade ditches, replace culverts, and restore pavement.	4J160	3167	0323000125	201.130	22-23	\$0	\$6,000	\$6,000	2/21/23	NH	\$0	\$0	\$0	\$1,200	\$7,200	46.00	Location(s)	
03	El Dorado	50	16.100	In Placerville, at 0.3 mile east of Forni Road. Repair and replace failed culvert.	4J800	3351	0323000269	201.130	22-23	\$0	\$470	\$470	5/18/23	NH	\$0	\$0	\$0	\$140	\$610	1.00	Location(s)	
03	El Dorado	50	18.000/58.000	In and near Placerville, Pollock Pines, and Strawberry, from Bedford Avenue to Strawberry Lane. Remove dead, dying, and hazardous trees.	4J910	3352	0323000288	201.130	22-23	\$0	\$2,100	\$2,100	6/26/23	NH	\$0	\$0	\$0	\$630	\$2,730	251.00	Location(s)	
03	El Dorado	50	67.200	Near South Lake Tahoe, at 0.1 mile west of Echo Summit Sidehill Viaduct. Remove rock debris, and provide slope stabilization and rockfall mitigation by installing cable net.	0N650	3365	0324000168	201.130	23-24	\$0	\$800	\$800	2/6/24	NH	\$0	\$0	\$0	\$250	\$1,050	1.00	Location(s)	
03	El Dorado	50	75.400/80.000	In South Lake Tahoe, from Route 89 to Pioneer Trail. Install lighting, pedestrian signals at mid-block crossings, signs, and green bike lane treatment, and modify intersections for bicycle turning phases to improve safety for pedestrians and bicyclists. This project will reduce the number and severity of collisions.	4H890	3469	0319000072	201.010	22-23	\$2,320	\$19,140	\$22,430	10/23/23	STP	\$1,610	\$1,470	\$2,720	\$2,920	\$30,180	13.00	Collision(s) reduced	
03	El Dorado	50	77.000/80.440	In South Lake Tahoe, from 0.1 mile east of Rubicon Trail to Nevada State line. Grind pavement, place asphalt, and replace striping.	0L280	3356	0324000074	201.130	23-24	\$0	\$3,100	\$3,100	9/1/23	NH	\$0	\$0	\$0	\$930	\$4,030	20.00	Location(s)	
03	El Dorado	89	16.000/18.000	Near Emerald Bay, from 1.5 miles south to 0.5 mile north of Eagles Fall Viaduct No. 25-0103. Remove and replace bridge rail and stabilize slope by rock scaling.	4J670	3475	0323000227	201.130	22-23	\$0	\$700	\$700	4/20/23	NH	\$0	\$0	\$0	\$210	\$910	1.00	Location(s)	

2022 SHOPP As of January 2026 Close-Out

(x\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Con Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
03	Nevada	20	R12.200/20.000	In and near Grass Valley and Nevada City, from Route 20/49 Separation to east of Stonehill Road/Dow Road. Rehabilitate pavement, replace sign panels, upgrade Transportation Management System (TMS) elements, rehabilitate drainage systems, and upgrade facilities to Americans with Disabilities Act (ADA) standards. This project will extend the pavement service life and improve ride quality.	4H070	4002	0318000158	201.121	22-23	\$250	\$19,100	\$20,940	6/29/23	NH	\$1,030	\$1,570	\$340	\$1,700	\$23,990	22.90	Lane mile(s)	
03	Nevada	20	21.500	Near Nevada City, at 0.8 mile west of Harmony Ridge Road. Repair sinkhole and replace failed culvert.	4J130	4006	0323000109	201.130	22-23	\$0	\$500	\$500	1/13/23	NH	\$0	\$0	\$0	\$100	\$600	1.00	Location(s)	
03	Nevada	20	30.100	Near Nevada City, at 0.5 mile east of White Cloud Campground Road. Remove slide material, stabilize slope, and place Rock Slope Protection (RSP).	2H621	4009	0324000269	201.130	23-24	\$0	\$7,000	\$7,000	5/1/24	NH	\$0	\$0	\$0	\$1,000	\$8,000	1.00	Location(s)	
03	Nevada	20	39.000/46.000	Near Yuba Pass, from 0.5 mile east of Lowell Hill Road to Route 80. Repair eroded shoulder and drainage systems.	0L220	4008	0324000065	201.130	23-24	\$0	\$3,000	\$3,000	9/19/23	NH	\$0	\$0	\$0	\$900	\$3,900	12.00	Location(s)	
03	Nevada	49	1.700	Near Auburn, at Streeter Road. Replace culvert.	3J770	4142	0323000001	201.130	22-23	\$0	\$550	\$550	10/13/22	NH	\$0	\$0	\$0	\$110	\$660	1.00	Location(s)	
03	Nevada	80	0.000/R2.700	Near Kingvale, from Placer County line to 0.2 mile east of Donner Pass Road (PM 0.0/R2.7L/R); also in Placer County, from 0.2 mile west of Troy Road Undercrossing to Nevada County line (PM 68.3/69.7). Rehabilitate roadway, construct truck climbing lane in eastbound direction, replace Kingvale Undercrossing No. 19-0107R and Troy Road Undercrossing No. 19-0106R, replace sign panels, upgrade lighting and Transportation Management System (TMS) elements, and rehabilitate drainage systems. This project will improve safety and ride quality.	1H990	5111	0317000043	201.122	22-23	\$1,687	\$70,239	\$79,450	6/29/23	NH	\$3,000	\$3,000	\$500	\$9,000	\$87,426	10.40	Lane mile(s)	May-2022 / SHOPP-P-2122-06B
03	Nevada	80	0.000/16.500	In and near Truckee, from the Placer County line to Route 89. Grind pavement, place polyester concrete, replace concrete slabs, replace striping, and rehabilitate drainage systems.	0L260	4329	0324000072	201.130	23-24	\$0	\$16,790	\$16,790	10/10/23	NH	\$0	\$0	\$0	\$4,930	\$21,720	35.00	Location(s)	
03	Nevada	80	0.000/16.500	In and near Truckee, from the Placer County line to Route 89. Grind pavement, place polyester concrete, replace concrete slabs, replace striping, and rehabilitate drainage systems. The project will utilize the Emergency Force Account (EFA) contract method. This project will be combined with EA 0L260/PPNO 03-4329 for construction.	0N380	4331	0324000097	201.131	23-24	\$0	\$11,400	\$11,400	10/19/23	NH	\$0	\$0	\$0	\$3,400	\$14,800	17.00	Location(s)	
03	Nevada	80	16.500/31.783	In and near Truckee, from Route 267 to the Sierra County line; also in Sierra County, from the Nevada County line to the Nevada State line (PM 0.0/1.59). Grind pavement, place polyester concrete, replace concrete slabs, replace striping, and rehabilitate drainage systems.	0L270	4330	0324000076	201.130	23-24	\$0	\$13,500	\$13,500	10/9/23	NH	\$0	\$0	\$0	\$4,050	\$17,550	37.00	Location(s)	

2022 SHOPP As of January 2026 Close-Out

(x\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Con Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
03	Nevada	80	16.500/31.783	In and near Truckee, from Route 267 to the Sierra County line; also in Sierra County, from the Nevada County line to the Nevada State line (PM 0.0/1.59). Grind pavement, place polyester concrete, replace concrete slabs, replace striping, and rehabilitate drainage systems. The project will utilize the Emergency Force Account (EFA) contract method. This project will be combined with EA 0L270/PPNO 03-4330 for construction.	0N390	4332	0324000098	201.131	23-24	\$0	\$10,100	\$10,100	10/19/23	NH	\$0	\$0	\$0	\$3,000	\$13,100	18.00	Location(s)	
03	Nevada	80	25.500/27.400	Near Floriston, from 1.9 miles east of Hinton Road Undercrossing to Truckee River Bridge. Restore pavement surface to increase friction, repair drainage and replace damaged concrete barrier to improve safety. This project will reduce the number and severity of collisions.	2J910	4322	0322000136	201.010	23-24	\$20	\$2,900	\$3,258	5/5/23	STP	\$350	\$530	\$20	\$600	\$4,420	71.00	Collision(s) reduced	
03	Nevada	80	R58.700/R60.200	Near Whitmore, from 0.7 mile west to 0.8 mile east of Yuba Pass Separation and Overhead No. 17-0023L/R (PM R58.7L/R/PM R60.2); also in Placer County, from PM R58.5L/R to PM R58.7L/R; also in Nevada County on Route 20 at PM 45.7. Replace and widen bridges, construct retaining walls in the median, rehabilitate drainage systems, and install Roadway Weather Information Systems (RWIS).	3H560	4305	0318000014	201.116	22-23	\$836	\$84,500	\$99,875	12/7/23	BFP	\$3,620	\$4,210	\$430	\$8,500	\$102,096	2.00	Bridge(s)	Aug-2022 / SHOPP-P-2223-01B
03	Nevada	80	R58.712/R62.541	Near Crystal Lake, from 0.2 mile west of Crystal Lake Road to 0.5 mile east of Eagle Lakes Road; also in Placer County from 0.5 mile east of Eagle Lakes Road to 0.5 mile east of Kingvale Undercrossing (PM R62.747R/69.7). Grind pavement, place polyester concrete, replace concrete slabs, replace striping, and rehabilitate drainage systems.	0N250	5165	0324000071	201.130	23-24	\$0	\$9,600	\$9,600	10/10/23	NH	\$0	\$0	\$0	\$2,860	\$12,460	8.00	Location(s)	
03	Nevada	80	R58.712/R62.541	Near Crystal Lake, from 0.2 mile west of Crystal Lake Road to 0.5 mile east of Eagle Lakes Road; also in Placer County from 0.5 mile east of Eagle Lakes Road to 0.5 mile east of Kingvale Undercrossing (PM R62.747R/69.7). Grind pavement, place polyester concrete, replace concrete slabs, replace striping, and rehabilitate drainage systems. The project will utilize the Emergency Force Account (EFA) contract method. This project will be combined with EA 0L250/PPNO 03-5165 for construction.	0N370	5167	0324000096	201.131	23-24	\$0	\$6,600	\$6,600	10/19/23	NH	\$0	\$0	\$0	\$1,900	\$8,500	11.00	Location(s)	
03	Placer	28	0.085/11.000	Near Tahoe City and Kings Beach, from Route 89 to Nevada State line. Rehabilitate pavement, rehabilitate drainage systems, upgrade guardrail, and upgrade facilities to Americans with Disabilities Act (ADA) standards. This project will extend pavement service life and improve ride quality.	0J010	4681	0319000184	201.121	23-24	\$2,077	\$19,100	\$22,727	6/28/24	NH	\$1,160	\$1,420	\$740	\$1,780	\$26,277	20.50	Lane mile(s)	
03	Placer	28	0.200/0.500	In Tahoe City, from Mackinaw Road to Grove Street. Place green bike lane treatment or High Friction Surface Treatment (HFST), install recessed striping, rectangular flashing beacons, and signs, and construct curb ramps. This project will reduce the number and severity of collisions.	0J922	6257B	0321000161	201.010	22-23	\$5	\$250	\$298	6/28/24	STP	\$0	\$16	\$13	\$25	\$309	2.00	Collision(s) reduced	
03	Placer	28		In Placer County, on Routes 28, 89, 267 at various locations. Repair pavement.	4J720	4683	0323000247	201.130	22-23	\$0	\$6,200	\$6,200	5/15/23	NH	\$0	\$0	\$0	\$1,860	\$8,060	117.00	Location(s)	

2022 SHOPP As of January 2026 Close-Out

(x\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Con Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
03	Placer	80	2.000/7.000	In Roseville and Rocklin, from Douglas Boulevard to 0.4 mile west of Sierra College Boulevard. Grind and replace pavement.	4J560	5159	0323000207	201.130	22-23	\$0	\$7,000	\$7,000	4/27/23	NH	\$0	\$0	\$0	\$1,400	\$8,400	1.00	Location(s)	
03	Placer	80	24.000/26.000	Near Applegate, from 0.6 mile east of Clipper Gap Overcrossing to 0.2 mile west of Applegate Road Overcrossing. Replace failed culverts, repair sinkhole and failed pavement, and restore eroded slope.	4J170	5158	0323000126	201.130	22-23	\$0	\$800	\$800	1/31/23	NH	\$0	\$0	\$40	\$160	\$1,000	2.00	Location(s)	
03	Placer	80	R26.300/29.500	Near Applegate, from 0.1 mile east of Crother Road Overcrossing to 0.2 mile east of Weimar Cross Road Overcrossing; also near Magra, from PM 39.4 to PM 41.5; also near Emigrant Gap, from PM 52.8R to PM R55.2. Rehabilitate roadway, construct truck climbing lanes in eastbound direction, widen shoulders, replace or widen structures, upgrade median barrier and Transportation Management System (TMS) elements. This project will improve safety and ride quality.	3H590	5131	0318000017	201.122	23-24	\$2,972	\$93,500	\$129,514	10/17/25	NH	\$4,000	\$5,000	\$500	\$9,500	\$115,472	13.60	Lane mile(s)	Aug-2023 / SHOPP-P-2324-01B
03	Placer	80	27.400	Near Applegate, at the Applegate Road onramp. Remove slide material, round slope, and place erosion control.	4J660	5160	0323000224	201.130	22-23	\$0	\$500	\$500	5/8/23	NH	\$0	\$0	\$0	\$125	\$625	1.00	Location(s)	
03	Placer	80	33.000/44.850	In and near Colfax, from 0.1 mile west of Route 174 to 0.1 mile east of Alta Bonnybrook Road. Grind pavement, place asphalt, and replace striping.	0L230	5163	0324000069	201.130	23-24	\$0	\$6,920	\$6,920	10/9/23	NH	\$0	\$0	\$0	\$2,080	\$9,000	15.00	Location(s)	
03	Placer	80	42.700/49.300	Near Gold Run, from 0.5 mile west of Monte Vista Overcrossing to 0.3 mile east of Drum Forebay Overcrossing. Rehabilitate roadway, construct truck climbing lane, replace or widen structures, upgrade median concrete barrier, sign panels, and Transportation Management System (TMS) elements, and rehabilitate drainage systems. This project will improve safety and ride quality.	3H610	5133	0318000019	201.122	22-23	\$2,165	\$78,688	\$124,800	8/17/23	NH	\$3,000	\$3,000	\$230	\$6,500	\$93,583	13.20	Lane mile(s)	Dec-2022 / SHOPP-P-2223-03B
03	Placer	80	44.850/R58.712	Near Emigrant Gap, from 0.1 mile east of Alta Bonnybrook Road to the Nevada County line. Grind pavement, place polyester concrete, replace concrete slabs, replace striping, and rehabilitate drainage systems.	0L240	5164	0324000070	201.130	23-24	\$0	\$13,060	\$13,060	10/9/23	NH	\$0	\$0	\$0	\$3,920	\$16,980	25.00	Location(s)	
03	Placer	80	44.850/R58.712	Near Emigrant Gap, from 0.1 mile east of Alta Bonnybrook Road to the Nevada County line. Grind pavement, place polyester concrete, replace concrete slabs, replace striping, and rehabilitate drainage systems. The project will utilize the Emergency Force Account (EFA) contract method. This project will be combined with EA 0L240/PPNO 03-5164 for construction.	0N360	5166	0324000095	201.131	23-24	\$0	\$10,100	\$10,100	10/19/23	NH	\$0	\$0	\$0	\$3,000	\$13,100	12.00	Location(s)	
03	Placer	89	8.900	Near Tahoe City, at the Tahoe City Maintenance Station. Install a new enclosed building for switchboard and generator, and upgrade electrical systems.	4H980	5290	0319000129	201.352	23-24	\$40	\$3,600	\$4,679	8/15/25	ST-CASH	\$690	\$710	\$90	\$560	\$5,690	1.00	Location(s)	
03	Placer	174		In Placer, Nevada, Yuba, and Sierra Counties, on Routes 20, 49, and 174 at various locations. Remove storm damaged trees and debris.	4J510	4454	0323000181	201.130	22-23	\$0	\$1,500	\$1,500	4/3/23	NH	\$0	\$0	\$0	\$300	\$1,800	16.00	Location(s)	

2022 SHOPP As of January 2026 Close-Out

(x\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Con Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
03	Sacramento	5	25.000/28.000	In city of Sacramento, from 0.2 mile north of American River Bridge to Arena Boulevard. Rehabilitate storm damaged pavement.	0N310	5887	0324000084	201.130	23-24	\$0	\$4,330	\$4,330	10/9/23	NH	\$0	\$0	\$0	\$1,300	\$5,630	3.00	Location(s)	
03	Sacramento	5	25.000/28.000	In the city of Sacramento, from 0.2 mile north of American River Bridge to Arena Boulevard. Grind pavement, place hot mix asphalt, and replace striping. The project will utilize the Emergency Force Account (EFA) contract method. This project will be combined with EA 0N310/PPNO 03-5887 for construction.	0N350	5888	0324000094	201.131	23-24	\$0	\$14,100	\$14,100	10/19/23	NH	\$0	\$0	\$0	\$4,200	\$18,300	5.00	Location(s)	
03	Sacramento	12	0.000/0.500	Near Rio Vista, at the Sacramento River (Rio Vista) Bridge No. 23-0024; also in Solano County from PM 26.1 to 26.4. Repair and upgrade electrical, mechanical, and structural damaged components of bridge.	3J330	5965	0322000251	201.131	22-23	\$0	\$16,220	\$16,200	8/18/22	NH	\$0	\$0	\$0	\$3,100	\$19,320	1.00	Location(s)	
03	Sacramento	16	10.200/10.700	Near Sloughhouse, at the intersection with Eagles Nest Road. Add traffic signal and widen lanes and shoulders to improve safety. This project will reduce the number and severity of collisions.	2J320	6003	0321000222	201.010	23-24	\$11	\$2,846	\$3,343	10/23/23	STP	\$557	\$544	\$198	\$633	\$4,789	5.00	Collision(s) reduced	
03	Sacramento	50	12.130	In the city of Sacramento, at 5900 Folsom Boulevard. Repair HVAC system at the Transportation Laboratory. This project will utilize the Emergency Force Account contract method.	0N620	6265	0324000162	201.131	23-24	\$0	\$15,000	\$15,000	1/26/24	NH	\$0	\$0	\$0	\$3,500	\$18,500	1.00	Location(s)	
03	Sacramento	50	12.500	In Rancho Cordova, at the District 3 Regional Transportation Management Center (RTMC) (3165 Gold Valley Drive). Install new Heating Ventilation and Air Conditioning (HVAC) system, install new roof, and replace roofing insulation.	4H970	6255	0319000128	201.352	22-23	\$0	\$4,300	\$4,516	6/28/24	ST-CASH	\$430	\$860	\$20	\$770	\$6,380	1.00	Location(s)	
03	Sacramento	51	0.200	In Sacramento, at the Fort Sutter Viaduct No. 24-0188L/R. Repair hinge diaphragms and girders.	4J500	6416	0323000177	201.130	22-23	\$0	\$1,413	\$1,413	4/20/23	NH	\$0	\$141	\$0	\$282	\$1,836	1.00	Location(s)	
03	Sacramento	51	2.000/3.500	In the city of Sacramento, from north of B Street Underpass to north of Exposition Boulevard Overcrossing at the American River Bridge No. 24-0003 and Cal Expo Undercrossing No. 24-0133. Outcome/Output: Widen and replace bridge deck and construct 0.14 mile of Class 1 bike and pedestrian path as a complete streets element. This is a Construction Manager/General Contractor (CMGC) project. Additional \$2,700,000 contribution for Const Cap from the city of Sacramento and \$350,000 for Const Sup from Sacramento Area Council of Governments (SACOG).	3F070	6402	0312000054	201.110	22-23	\$7,634	\$62,209	\$145,300	8/17/23	HBRR-S	\$4,340	\$12,000	\$600	\$10,550	\$97,333	2.00	Bridge(s)	May-2021 / SHOPP-P-2021-06B
03	Sacramento	51	5.500	In the city of Sacramento, at Marconi Avenue Overcrossing No. 24-0117. Remove damaged bridge rail, construct concrete barrier with sidewalk, and install traffic signal.	0N080	6418	0324000025	201.130	23-24	\$0	\$2,000	\$2,000	8/4/23	NH	\$0	\$0	\$0	\$600	\$2,600	1.00	Location(s)	
03	Sacramento	51	5.600/5.900	In the city of Sacramento, between Marconi Avenue and Howe Avenue. Construct outer separation barrier in northbound direction, replace guardrail, drainage inlets, and culvert, and install lighting. This project will reduce the number and severity of collisions.	3H730	6414	0318000055	201.015	22-23	\$62	\$3,100	\$3,392	3/23/23	STP	\$410	\$740	\$90	\$530	\$4,932	6.00	Collision(s) reduced	

2022 SHOPP As of January 2026 Close-Out

(x\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Con Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
03	Sacramento	99	5.000/8.300	Near Elk Grove, from 1.0 mile south of Arno Road to 0.9 mile north of Dillard Road. Remove debris, repair guardrail, drainage, pavement, and bridge scour, and place rock slope protection and erosion control.	4J150	4943	0323000124	201.130	22-23	\$0	\$2,000	\$2,000	2/7/23	NH	\$0	\$0	\$0	\$400	\$2,400	3.00	Location(s)	
03	Sacramento	99	12.700/16.300	In Elk Grove, from Elk Grove Boulevard to Calvine Road. Construct two southbound auxiliary lanes, upgrade culvert, construct concrete median barrier, extend storage lane at southbound Elk Grove Boulevard offramp, and upgrade five ramp metering systems. This project will reduce congestion, improve highway operation and mobility.	1H630	6930	0316000193	201.310	22-23	\$320	\$19,700	\$23,096	8/17/23	NH	\$810	\$1,550	\$250	\$2,000	\$24,630	298.00	Daily vehicle hour(s) of delay (DVHD)	
03	Sacramento	160	L1.000/L6.000	Near Rio Vista, from Contra Costa County line to 0.9 mile south of Sherman Island Road. Replace failed culvert and repair sinkhole.	4J810	7297	0323000272	201.130	22-23	\$0	\$570	\$570	6/12/23	NH	\$0	\$0	\$0	\$170	\$740	1.00	Location(s)	
03	Sacramento	160		Near Rio Vista, at Sacramento River (Isleton) Bridge No. 24-0051 (PM 5.86), Three Mile Slough Bridge No. 24-0121 (PM L6.98), Steamboat Slough Bridge No. 24-0052 (PM 19.76), and Sacramento River (Paintersville) Bridge No. 24-0053 (PM20.87). Repair failing and obsolete mechanical and electrical components at four bridges. This project will utilize the Emergency Force Account contract method.	1N010	7298	0324000268	201.131	23-24	\$50	\$20,000	\$20,000	5/17/24	NH	\$0	\$0	\$0	\$3,000	\$23,050	4.00	Location(s)	
03	Sacramento	Var		In Sacramento, Yolo, and Placer Counties, on various routes at four maintenance stations. Install fencing, gates, lighting, and camera systems to improve security. This project will utilize the Emergency Limited Bid contract method.	0N990	6728	0324000237	201.352	23-24	\$0	\$3,439	\$3,439	6/28/24	ST-CASH	\$0	\$0	\$0	\$0	\$3,439	4.00	Location(s)	
03	Sierra	49	2.500/3.500	Near Camptonville, from 1.2 miles south to 0.2 mile south of North Yuba River Bridge. Stabilize slope, remove damaged retaining wall and construct viaduct.	4J200	7812	0323000130	201.130	22-23	\$0	\$2,500	\$2,500	2/7/23	NH	\$0	\$0	\$0	\$500	\$3,000	1.00	Location(s)	
03	Sierra	49	3.560/3.580	Near Camptonville, at 0.1 mile south of North Yuba River Bridge. Remove guardrail anchored retaining wall, construct soldier pile retaining wall, replace guardrail, and place erosion control.	0N670	7816	0324000170	201.130	23-24	\$0	\$2,000	\$2,000	2/22/24	NH	\$0	\$0	\$0	\$600	\$2,600	1.00	Location(s)	
03	Sierra	49	15.900	Near Downieville, at 1.7 miles west of Saddleback Road. Repair culvert and backfill sinkhole.	4J490	7813	0323000175	201.130	22-23	\$0	\$700	\$700	3/14/23	NH	\$0	\$0	\$0	\$140	\$840	1.00	Location(s)	
03	Sierra	49	29.500	Near Sierra City, at 0.1 mile south of Church Street. Install new culvert and drainage inlets.	0L090	7815	0324000031	201.130	23-24	\$0	\$600	\$600	8/21/23	NH	\$0	\$0	\$0	\$180	\$780	1.00	Location(s)	
03	Yolo	5	R6.640	In Woodland, at 0.1 mile north of East Main Street. Replace failed section of the culvert, replace downdrain, provide erosion control, and restore pavement.	4J030	8576	0323000051	201.130	22-23	\$0	\$500	\$500	11/22/22	NH	\$0	\$0	\$0	\$100	\$600	1.00	Location(s)	
03	Yolo	50	2.200/2.700	In West Sacramento, from Westacre Road to Drever Street. Repair slipouts, reset guardrail, and replace damaged pavement.	4J580	8787	0323000209	201.130	22-23	\$0	\$420	\$420	4/5/23	NH	\$0	\$0	\$0	\$84	\$504	2.00	Location(s)	
03	Yolo	128	1.000/6.000	Near Winters, from 1.0 mile east of the Napa County line to 1.3 miles west of County Road 87D. Repair slipouts by placing Rock Slope Protection (RSP) and constructing a soldier pile tieback wall.	4J680	9307	0323000228	201.130	22-23	\$0	\$3,700	\$3,700	5/8/23	NH	\$0	\$0	\$0	\$1,110	\$4,810	2.00	Location(s)	

2022 SHOPP As of January 2026 Close-Out

(x\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Con Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
03	Yuba	65	R0.500/1.800	In and near Wheatland, from 0.1 mile north of State Street to 0.3 mile north of Evergreen Drive. Rehabilitate pavement, add bike lanes, rehabilitate drainage systems, upgrade facilities to Americans with Disabilities Act (ADA) standards, and construct Class 1 multi-use path, modify driveways, and enhance crosswalk visibility as complete streets elements, and add a traffic signal at the intersection with McDevitt Drive. This project will extend the pavement service life and improve ride quality.	0H370	9732	0315000151	201.121	22-23	\$270	\$7,650	\$9,087	1/26/23	NH	\$400	\$830	\$510	\$580	\$10,240	2.50	Lane mile(s)	
03	Yuba	70	14.800/15.700	In and near Marysville, from 0.1 mile south of 14th Street to 0.1 mile north of Cemetery Road. Early Work Package No. 1 for Construction Manager/General Contractor (CMGC) parent project EA 0H160. Construct new pump plant at Marysville Underpass and reconstruct pump plant at Binney Junction Underpass.	0H161	9820A	0323000025	201.120	22-23	\$0	\$13,000	\$13,000	5/18/23	NH	\$0	\$0	\$0	\$1,600	\$14,600	0.00	Lane mile(s)	
03	Yuba	Var		In Yuba and Butte Counties, on various routes at four maintenance stations. Install fencing, gates, lighting, and camera systems to improve security. This project will utilize the Emergency Limited Bid contract method.	1N000	9833	0324000238	201.352	23-24	\$0	\$4,160	\$4,160	6/28/24	ST-CASH	\$0	\$0	\$0	\$0	\$4,160	4.00	Location(s)	