

2022 SHOPP As of June 2024 Close-Out
(\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
05	Monterey	1	0.000/20.900	Near Gorda, from San Luis Obispo County Line to Limekiln State Park; also in San Luis Obispo County, from Ragged Point Inn to Monterey County line (PM 72.8/74.324). Repair storm damage, including slopes, drainage systems, guardrail, and pavement.	1Q760	3144	0523000073	201.130	22-23	\$100	\$18,350	\$18,350	3/30/23	NH	\$0	\$300	\$50	\$5,000	\$23,800	30.0	Location(s)	
05	Monterey	1	7.200/9.200	Near Gorda, from 0.1 mile north to 2.1 miles north of Villa Creek Bridge. Restore and repair access routes, repair Rock Slope Protection (RSP) revetment, and replace damaged gabion baskets.	1R190	3174	0523000167	201.130	23-24	\$200	\$51,000	\$51,000	2/8/24	NH	\$0	\$0	\$0	\$15,300	\$66,500	2.0	Location(s)	
05	Monterey	1	20.900/42.200	Near Big Sur, from Limekiln State Park to 0.9 mile south of Castro Canyon Bridge. Repair storm damage, including slide mitigation, restoring rockfall barrier systems, and replacing culverts.	1Q770	3145	0523000074	201.130	22-23	\$100	\$45,600	\$45,600	3/13/23	NH	\$0	\$0	\$0	\$10,000	\$55,700	25.0	Location(s)	
05	Monterey	1	22.000	Near Lucia, at 0.5 mile north of Pitkins Curve Bridge; also at 0.3 mile north of Big Creek Bridge (PM 28.4); also in Monterey, at 0.1 mile south of Soledad Drive (PM R75.9). Clean out catchment, repair rockfall barrier, and line culvert and repair sinkhole.	1Q050	3098	0522000145	201.130	22-23	\$10	\$800	\$800	12/14/22	NH	\$0	\$0	\$0	\$250	\$1,060	3.0	Location(s)	
05	Monterey	1	27.800	Near Lucia, at 0.3 mile south of Big Creek Bridge. Remove slide material from top down, haul off slide material, restore roadway, and install rockfall protection and provide erosion control.	1R640	3208	0524000098	201.130	23-24	\$200	\$31,000	\$31,000	3/28/24	NH	\$0	\$0	\$0	\$9,000	\$40,200	1.0	Location(s)	
05	Monterey	1	29.500	Near Lucia, at 1.4 miles north of Big Creek Bridge. Remove slide material, restore roadway, and install rockfall netting.	1R630	3207	0524000097	201.130	23-24	\$25	\$1,800	\$1,800	3/18/24	NH	\$0	\$0	\$0	\$540	\$2,365	1.0	Location(s)	
05	Monterey	1	44.700/69.800	Near Big Sur, from 0.9 mile south of Sycamore Canyon Road to 0.1 mile north of Corona Road. Repair storm damage, including clearing or repairing culverts, restoring slopes, and clearing debris.	1Q800	3146	0523000090	201.130	22-23	\$40	\$25,400	\$25,400	3/30/23	NH	\$0	\$0	\$0	\$7,000	\$32,440	11.0	Location(s)	
05	Monterey	1	45.400/45.600	Near Big Sur, at the Pfeiffer Canyon Bridge No. 44-0060. Environmental mitigation (utility relocation) for project EA 1J130.	1K081	2855X	0522000107	201.131	23-24	\$1,600	\$0	\$0		NH	\$0	\$0	\$110	\$0	\$1,710	0.0	Location(s)	
05	Monterey	1	47.800	Near Big Sur, at 0.2 mile south of Juan Higuera Creek Bridge. Divert river to dewater the toe, remove existing concrete wall, construct Rock Slope Protection (RSP) revetment, and restore site.	1R210	3176	0523000169	201.130	23-24	\$50	\$7,500	\$7,500	2/14/24	NH	\$0	\$0	\$0	\$1,950	\$9,500	1.0	Location(s)	
05	Monterey	1	60.000	Near Nottleys Landing, at 0.2 mile south of Rocky Creek Bridge. Stabilize slope due to rock slide.	1S040	3222	0524000162	201.130	23-24	\$100	\$9,400	\$9,400	4/23/24	NH	\$0	\$0	\$0	\$2,820	\$12,320	1.0	Location(s)	
05	Monterey	1	63.000	Near Carmel-by-the-Sea, at the Garrapata Creek Bridge No. 44-0018. Replace bridge railing to meet current traffic safety standards.	1H800	2696	0516000163	201.112	22-23	\$58	\$3,642	\$0		HBRR-S	\$1,600	\$1,900	\$130	\$1,391	\$8,721	650.0	Linear feet rail	
05	Monterey	1	R78.900	In the city of Monterey, at Cabrillo Highway; also near the city of Monterey, from 0.2 mile west of Scenic Drive to Scenic Drive. Reconstruct slopes and repair culverts and sinkhole damage.	1R130	3168	0523000148	201.130	22-23	\$0	\$700	\$700	5/24/23	NH	\$0	\$0	\$0	\$200	\$900	4.0	Location(s)	
05	Monterey	1	96.400/96.600	Near Moss Landing, at Elkhorn Slough Bridge No. 44-0074. Regrade site, install anchors to restrain the abutment and sheet pile wall, install Rock Slope Protection (RSP), and fencing.	1P390	3084	0522000037	201.130	22-23	\$20	\$750	\$750	10/13/22	NH	\$0	\$0	\$0	\$250	\$1,020	1.0	Location(s)	
05	Monterey	25		In Monterey and San Benito counties on route 25, 101, and 198 at various locations. Repair storm damage, including drainage systems, embankments, and roadway.	1Q810	3147	0523000076	201.130	22-23	\$10	\$2,800	\$2,800	3/9/23	NH	\$0	\$200	\$10	\$590	\$3,610	8.0	Location(s)	
05	Monterey	68	0.200/15.700	In and near the city of Monterey, from west of Sunset Drive to west of Toro Park Undercrossing. Rehabilitate drainage systems and lighting, and install Transportation Management System (TMS) elements. Additional contribution of \$639,000 from county of Monterey.	1J880	2787	0518000083	201.151	23-24	\$992	\$7,600	\$0		RMRA	\$1,900	\$2,600	\$2,300	\$1,950	\$17,342	34.0	Culvert(s) (ea)	
05	Monterey	101	R6.700	Near Paso Robles, at San Antonio River Bridge No 44-0141L/R. Environmental mitigation monitoring for project EA 1F820.	1F821	2565A	0520000070	201.113	23-24	\$0	\$0	\$0		RMRA	\$0	\$0	\$0	\$20	\$20	0.0	Bridge(s)	

2022 SHOPP As of June 2024 Close-Out
(\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement	
05	Monterey	101	R41.900/49.800	Near King City, from Jolon Road to Lagomarsino Avenue. Rehabilitate pavement, drainage systems, and lighting, and install Transportation Management System (TMS) elements. (G13 Contingency)	1K440	2900	0518000208	201.121	23-24	\$156	\$0	\$0			NH	\$1,151	\$2,021	\$224	\$0	\$3,552	28.0	Lane mile(s)	
05	Monterey	101	98.800/100.300	Near Prunedale, from 0.4 mile north of Crazy Horse Canyon Road to 1.1 miles south of San Juan Road. Rehabilitate drainage culverts.	1H691	2679X	0521000065	201.151	23-24	\$521	\$5,100	\$0		RMRA	\$1,000	\$1,606	\$875	\$1,809	\$10,911	35.0	Culvert(s) (ea)		
05	Monterey	101	99.000	Near Salinas, at 0.4 mile north of Echo Valley Road; also in San Benito County near San Juan Batista on Route 156 at Route 101 (PM 0.0). Repair storm damaged facilities, including washed out embankments, drainage systems, and dikes.	1Q900	3156	0523000096	201.130	22-23	\$0	\$950	\$950	3/14/23	NH	\$0	\$0	\$0	\$280	\$1,230	2.0	Location(s)		
05	Monterey	183	R2.100/R8.300	Near Salinas and Castroville, from 0.2 mile north of South Davis Road to 0.1 mile south of Del Monte Avenue. Rehabilitate pavement and lighting, replace sign panels, and install Transportation Management System (TMS) elements. This project will extend the pavement service life and improve ride quality.	1K430	2899	0518000207	201.121	22-23	\$13	\$6,950	\$6,696	8/17/23	NH	\$634	\$1,430	\$43	\$1,308	\$10,378	12.7	Lane mile(s)		
05	Monterey	183	R8.400/9.800	In Castroville, from Del Monte Avenue to Washington Street, a multi-objective Asset Management Pilot Project. Rehabilitate pavement, repair bridge, construct storm drainage system improvements, construct Transportation Management System (TMS) elements, improve pedestrian, bicycle, and Americans with Disabilities Act (ADA) facilities.	1H650	2678	0516000118	201.999	22-23	\$2,300	\$21,300	\$0		ST-CASH	\$2,600	\$3,000	\$6,600	\$4,200	\$40,000	1.0	Location(s)		
05	Monterey	198	20.800	Near Parkfield Junction, at 1.8 miles west of North Fork Road. Remove and reconstruct the damaged roadway with a reinforced structural section and construct a v-ditch.	1R150	3170	0523000151	201.130	22-23	\$0	\$3,000	\$3,000	5/24/23	NH	\$0	\$0	\$0	\$900	\$3,900	1.0	Location(s)		
05	Monterey	Var		In Monterey, San Benito, and Santa Cruz Counties, at four maintenance stations. Replace perimeter fencing and gates, and install security camera systems to improve security. This project will utilize the Emergency Limited Bid contract method.	1S290	3231	0524000189	201.352	23-24	\$0	\$615	\$615	5/17/24	ST-CASH	\$0	\$0	\$0	\$67	\$682	4.0	Location(s)		
05	San Benito	25	53.700/54.300	Near Hollister, at the intersection of Route 25 and Route 156 (R11.1/R11.7). Environmental mitigation landscape and monitoring for project EA 1J480.	1J481	2746Y	0521000064	201.010	22-23	\$0	\$200	\$394	8/17/23	STP	\$0	\$442	\$0	\$458	\$1,100	0.0	Collision(s) reduced		
05	San Benito	101	R4.000	Near San Juan Bautista, at 0.2 mile south of Anzar Road Undercrossing. Repair damaged pavement.	1Q040	3097	0522000142	201.130	22-23	\$0	\$650	\$650	9/28/22	NH	\$0	\$0	\$0	\$130	\$780	1.0	Location(s)		
05	San Luis Obispo	1	0.000/0.300	Near Guadalupe, at the Santa Maria River Bridge No. 49-0042; also in Santa Barbara County (PM 50.3/50.6). The bridge is scour critical and needs to be replaced. The existing bridge will be used for traffic handling during construction and then demolished. The highway will need to be realigned as a result of the new bridge location. The new bridge will provide standard lane and shoulder widths and include a protected walkway.	1H440	2650	0516000074	201.110	22-23	\$1,030	\$32,640	\$0		HBRR-S	\$2,294	\$3,517	\$455	\$9,660	\$49,596	1.0	Bridge(s)	Mar-2021 / SHOPP-P-2021-05B	
05	San Luis Obispo	1	R12.600	Near Oceano, at Oceano Overhead No. 49-0012. Replace bridge damper blocks, restore eroded void and shoulder, install concrete wedges, and pave slope.	1Q060	3099	0522000146	201.130	22-23	\$10	\$700	\$700	1/9/23	NH	\$0	\$0	\$0	\$200	\$910	1.0	Location(s)		
05	San Luis Obispo	1	32.600	In Morro Bay, at Toro Creek Bridge. Environmental mitigation (biological monitoring) for project EA 0L721.	0L724	0072C	0519000054	201.110	23-24	\$9	\$0	\$0		RMRA	\$0	\$0	\$0	\$37	\$46	0.0	Bridge(s)		
05	San Luis Obispo	1	34.500	In Morro Bay, at Old Creek Bridge No. 49-0070R. Environmental mitigation (biological monitoring) for project EA 0L722.	0L725	0072D	0519000055	201.110	23-24	\$9	\$0	\$0		RMRA	\$0	\$0	\$0	\$37	\$46	0.0	Bridge(s)		
05	San Luis Obispo	1	64.000/R67.200	Near San Simeon, from north of Piedras Blancas Road to north of the Arroyo de la Cruz Bridge. Planting, wetland and California Red-Legged Frog mitigation at Toro Preserve for PPNO 05-4928A.	49286	4928R	0522000106	201.150	23-24	\$3,300	\$7,040	\$6,674	12/7/23	NH	\$0	\$730	\$150	\$2,300	\$13,520	0.0	Location(s)		

2022 SHOPP As of June 2024 Close-Out
(\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
05	San Luis Obispo	1	71.800	Near Ragged Point, at 0.5 mile north of San Carpoforo Creek. Install drainage system, remove slide material, and install drapery mesh and erosion control.	1Q650	3138	0523000060	201.130	22-23	\$100	\$4,100	\$4,100	2/14/23	NH	\$0	\$0	\$25	\$700	\$4,925	1.0	Location(s)	
05	San Luis Obispo	41	3.100	Near Morro Bay, 3.1 miles north of Route 1. Environmental mitigation for parent project EA 1K720 for biological monitoring.	1K721	2927X	0522000134	201.131	23-24	\$17	\$0	\$0		NH	\$0	\$0	\$21	\$133	\$171	0.0	Location(s)	
05	San Luis Obispo	41	6.700/13.000	In and near Atascadero, from 0.5 mile south of Cerro Alto Road to 0.4 mile north of Old Morro Road; also on Route 101 in the city of San Luis Obispo from 0.3 mile north of Prado Road to Marsh Street (PM 27.0/28.0). Repair storm damage, including slide and debris removal, roadway restoration, and revegetation construction and repair.	1Q970	3162	0523000107	201.130	22-23	\$15	\$3,800	\$3,800	4/3/23	NH	\$0	\$0	\$0	\$750	\$4,565	7.0	Location(s)	
05	San Luis Obispo	46	R4.800/R5.200	Near Cambria, from 2.4 miles to 2.8 miles east of North Green Valley Road. Repair roadway, reconstruct slope, construct retaining wall, and place asphalt curb dike.	1P400	3085	0522000038	201.130	22-23	\$0	\$900	\$900	10/13/22	NH	\$0	\$0	\$0	\$300	\$1,200	2.0	Location(s)	
05	San Luis Obispo	46	29.800/32.200	In Paso Robles, from Route 101 to east of Airport Road. Rehabilitate pavement, replace roadside signs and sign panels, install Transportation Management System (TMS) elements, and upgrade facilities to Americans with Disabilities Act (ADA) standards. This project will extend the pavement service life and improve ride quality.	1K460	2903	0518000210	201.121	22-23	\$124	\$7,550	\$8,583	3/23/23	NH	\$477	\$1,424	\$75	\$1,693	\$11,343	8.2	Lane mile(s)	
05	San Luis Obispo	58	1.800/6.900	Near Santa Margarita, from I Street to Route 229. Rehabilitate pavement and drainage, replace sign panels, and install Transportation Management System (TMS) elements.	1J970	2845	0518000095	201.121	23-24	\$856	\$7,817	\$0		NH	\$1,622	\$2,253	\$968	\$2,103	\$15,619	11.7	Lane mile(s)	
05	San Luis Obispo	58	3.100	Near Santa Margarita, at Trout Creek Bridge. Environmental mitigation (biological monitoring) for project EA 0L723.	0L726	0072E	0519000056	201.110	23-24	\$9	\$0	\$0		RMRA	\$0	\$0	\$0	\$37	\$46	0.0	Bridge(s)	
05	San Luis Obispo	101	7.800/16.500	In and near Pismo Beach, Arroyo Grande, and Nipomo, from Los Barros Road to south of Hinds Avenue Overcrossing. Rehabilitate pavement, drainage systems, enhance highway worker safety, designate bikeways with pavement delineation, add bike lanes and curb ramps, and install Transportation Management System (TMS) elements. (G13 Contingency)	1J860	2778	0518000081	201.121	23-24	\$206	\$0	\$0		NH	\$1,610	\$3,209	\$655	\$0	\$5,680	34.7	Lane mile(s)	
05	San Luis Obispo	101	28.600/29.600	In the city of San Luis Obispo, from south of Broad Street to north of California Boulevard. Improve sight distance at gores by placing contrasting surface treatment and vegetation control, relocate guide signs, and widen shoulders.	1N340	3039	0520000168	201.010	23-24	\$480	\$2,024	\$0		STP	\$0	\$1,475	\$114	\$930	\$5,023	163.0	Collision(s) reduced	
05	San Luis Obispo	101	56.900	In Paso Robles, at 13th Street. Upgrade pumps and electrical system.	1Q890	3155	0523000095	201.130	22-23	\$20	\$1,300	\$1,300	2/7/23	NH	\$0	\$0	\$0	\$450	\$1,770	1.0	Location(s)	
05	San Luis Obispo	101		In San Luis Obispo and Santa Barbara Counties, on Routes 1, 41, 46, 101, and 135 at various locations. Improve safety by constructing centerline and edge line rumble strips and re-stripe with high visibility striping and markings. This project will reduce the number and severity of collisions.	1M740	3026	0520000058	201.010	22-23	\$0	\$2,510	\$2,796	8/30/22	STP	\$0	\$827	\$25	\$834	\$4,196	111.0	Collision(s) reduced	
05	San Luis Obispo	101		In San Luis Obispo County, in and near Santa Maria, Santa Margarita, Atascadero at various locations; also in Monterey County at North Bradley Undercrossing No. 44-0142R (PM R7.94). Apply polyester concrete overlay and replace joint seals. (Bridge Deck Preservation)	1P230	3078	0522000002	201.119	22-23	\$0	\$2,218	\$1,431	3/23/23	RMRA	\$75	\$330	\$10	\$650	\$3,283	6.0	Bridge(s)	
05	San Luis Obispo	101		In San Luis Obispo, at the Caltrans District 5 Office at 50 Higuera Street. Repair electrical systems damaged by basement flood.	1Q840	3150	0523000079	201.130	22-23	\$0	\$400	\$400	3/1/23	NH	\$0	\$0	\$0	\$160	\$560	1.0	Location(s)	

2022 SHOPP As of June 2024 Close-Out
(\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
05	San Luis Obispo	101		In San Luis Obispo, at the Caltrans District 5 Office at 50 Higuera Street. Repair or replace servers and networking equipment damaged by basement flood.	1Q850	3151	0523000080	201.130	22-23	\$0	\$4,036	\$4,036	3/1/23	NH	\$0	\$0	\$0	\$900	\$4,936	1.0	Location(s)	
05	San Luis Obispo	101		In San Luis Obispo, at the Caltrans District 5 Office at 50 Higuera Street. Reconstruct flooring, drywall, doors, and HVAC systems damaged by basement flood.	1Q860	3152	0523000081	201.130	22-23	\$0	\$1,800	\$1,800	3/30/23	NH	\$0	\$0	\$0	\$360	\$2,160	1.0	Location(s)	
05	San Luis Obispo	101		In San Luis Obispo, at the Caltrans District 5 Office at 50 Higuera Street. Remove and dispose of drywall, flooring, and furniture damaged by basement flood.	1Q880	3154	0523000094	201.130	22-23	\$0	\$1,250	\$1,250	3/1/23	NH	\$0	\$0	\$0	\$300	\$1,550	1.0	Location(s)	
05	San Luis Obispo	227	R6.800	Near Edna, at 0.1 mile north of Corbett Canyon Road; also on Route 46 near Harmony at 0.1 mile west and 2.1 mile east of South Green Valley Road (PM 3.3, 5.5). Replace culverts, place Rock Slope Protection (RSP), and restore roadway and embankments.	1Q070	3101	0522000147	201.130	22-23	\$10	\$650	\$650	1/9/23	NH	\$0	\$0	\$0	\$160	\$820	3.0	Location(s)	
05	San Luis Obispo			In San Luis Obispo County, on routes 1, 41, 58, 101, and 229 at various locations. Repair storm damage, including clearing debris, repairing damaged drainage systems, and restoring roadway damage.	1Q820	3148	0523000077	201.130	22-23	\$25	\$3,300	\$3,300	2/16/23	NH	\$0	\$0	\$0	\$650	\$3,975	15.0	Location(s)	
05	Santa Barbara	1	16.000	Near Lompoc, at 1.8 miles south of Santa Rosa Road. Construct revetment to restore slope, shoulder, and lane and reconstruct barrier.	1Q910	3157	0523000097	201.130	22-23	\$20	\$5,100	\$5,100	3/28/23	NH	\$0	\$0	\$0	\$1,100	\$6,220	1.0	Location(s)	
05	Santa Barbara	1	R36.300/49.200	Near Orcutt and Guadalupe, from Solomon Road to Route 166 Junction. Widen shoulders, install rumble strips, upgrade guardrails and relocate objects from within the clear recovery zone.	1H610	2667	0516000097	201.015	23-24	\$2,362	\$18,848	\$0		STP	\$1,736	\$1,942	\$1,237	\$3,948	\$30,073	0.38	Annual fatal and serious injury collision(s)	
05	Santa Barbara	1	49.200/50.400	In Guadalupe, from Route 166 (West Main Street) to 0.1 mile south of Santa Maria River Bridge; also on Route 166, from Route 1 to Obispo Street (PM 0.0/0.2). Upgrade curb ramps and other facilities to Americans with Disabilities Act (ADA) standards, construct new sidewalks, buffered bike lanes, bulb outs, and install flashing beacons as complete streets elements.	1E030	2466	0513000026	201.361	23-24	\$1,284	\$6,192	\$0		NH	\$1,229	\$2,233	\$2,963	\$1,447	\$15,348	28.0	Curb ramp(s)	
05	Santa Barbara	1		In Santa Barbara County on Routes 1, 101, 135, 166, and 246 at various locations. Repair storm damage, including debris removal, embankment restoration, and repair bridge rail.	1Q870	3153	0523000093	201.130	22-23	\$20	\$3,000	\$3,000	3/27/23	NH	\$0	\$0	\$0	\$650	\$3,670	19.0	Location(s)	
05	Santa Barbara	101	2.600/R4.800	In Carpinteria, from Casitas Pass Overcrossing to 0.5 mile south of South Padaro Lane. Environmental mitigation (biological monitoring) for EA 1C821.	1C8A2	2426X	0520000053	201.120	23-24	\$7	\$0	\$0		NH	\$0	\$0	\$0	\$33	\$40	0.0	Lane mile(s)	
05	Santa Barbara	101	4.400/R7.700	Near Summerland, from 0.9 mile south of South Padaro Lane Undercrossing to 0.6 mile north of Padaro Lane Overcrossing. Landscape and environmental mitigation (highway planting) for EA 1C822.	1C8B1	2427Y	0520000063	201.120	22-23	\$0	\$2,250	\$0		NH	\$0	\$400	\$0	\$600	\$3,250	0.0	Lane mile(s)	
05	Santa Barbara	101	4.400/R7.700	Near Summerland, from 0.9 mile south of South Padaro Lane Undercrossing to 0.6 mile north of Padaro Lane Overcrossing. Environmental mitigation (biological monitoring) for EA 1C822.	1C8B2	2427X	0520000064	201.120	23-24	\$5	\$0	\$0		NH	\$0	\$0	\$0	\$35	\$40	0.0	Lane mile(s)	
05	Santa Barbara	101	R5.300/10.500	Near the city of Santa Barbara, from South Padaro Lane Undercrossing to East Olive Mill Road Overcrossing. Clear rocks, sediment, and debris from creek beds at bridges and restore shoulder backing.	1Q750	3143	0523000072	201.130	22-23	\$10	\$750	\$750	2/17/23	NH	\$0	\$0	\$0	\$180	\$940	5.0	Location(s)	
05	Santa Barbara	101	R7.300/9.200	Near Summerland, from 0.2 mile north of Padaro Lane Overcrossing to 0.2 mile north of Sheffield Avenue. Environmental mitigation (biological monitoring) for EA 1C823.	1C8C2	2429X	0520000147	201.120	23-24	\$5	\$0	\$0		NH	\$0	\$0	\$0	\$35	\$40	0.0	Lane mile(s)	

2022 SHOPP As of June 2024 Close-Out
(\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
05	Santa Barbara	101	9.200/9.700	Near the city of Santa Barbara, from 0.2 mile north of Sheffield Drive to 0.3 mile south of San Ysidro Road. Upgrade median barrier, enhance highway worker safety, rehabilitate drainage systems and pavement, and install Transportation Management System (TMS) elements. This is a Construction Manager/General Contractor (CMGC) project. (Local contribution: \$966,000 PA&ED, \$3,433,000 PS&E, and \$156,000 R/W Support as part of STIP project EA 0N70B.)	1C824	2426D	0519000053	201.015	22-23	\$0	\$12,935	\$12,935	3/22/24	STP	\$0	\$0	\$0	\$4,600	\$17,535	0.12	Annual fatal and serious injury collision(s)	
05	Santa Barbara	101	31.000/67.000	Near Las Cruces, from 0.9 mile north of Dos Pueblos Creek Undercrossing to 1.8 miles south of Alisos Canyon Road. Repair storm damage, such as clearing debris, restoring drainage systems, and reconstructing embankments.	1Q670	3140	0523000062	201.130	22-23	\$20	\$5,500	\$5,500	3/23/23	NH	\$0	\$0	\$0	\$1,300	\$6,820	13.0	Location(s)	
05	Santa Barbara	101	R36.000/R37.000	Near Gaviota, from 0.6 mile south and 0.4 mile north of Refugio Road Undercrossing No. 51-0215L/R and Canada del Refugio No. 51-0030S. Replace two bridges and upgrade bridge railing on one bridge.	1C950	2448	0513000018	201.110	22-23	\$622	\$40,900	\$49,771	10/19/23	HBRR-S	\$2,200	\$6,260	\$320	\$11,200	\$61,502	3.0	Bridge(s)	Jun-2021 / SHOPP-P-2021-07B
05	Santa Barbara	101	46.500/48.000	Near Gaviota, from 0.1 mile north of Gaviota Beach Road to 0.8 mile south of Route 1. Clear rocks and debris and replace and repair damaged rockfall systems.	1Q660	3139	0523000061	201.130	22-23	\$0	\$1,700	\$1,700	2/16/23	NH	\$0	\$0	\$0	\$400	\$2,100	3.0	Location(s)	
05	Santa Barbara	101	46.700/48.000	Near Gaviota, from 0.3 mile north of Gaviota Beach Road to 0.8 mile south of Route 1. Clear catchment areas and repair rockfall fences.	1S020	3220	0524000160	201.130	23-24	\$0	\$600	\$600	3/28/24	NH	\$0	\$0	\$0	\$150	\$750	1.0	Location(s)	
05	Santa Barbara	101	47.000/47.300	Near Gaviota, from 1.8 to 1.5 miles south of Route 1. Construct secant pile wall and restore roadway.	1R140	3169	0523000150	201.130	22-23	\$25	\$15,000	\$15,000	5/11/23	NH	\$0	\$0	\$0	\$3,700	\$18,725	1.0	Location(s)	
05	Santa Barbara	101	R52.300/R56.100	Near Buellton, from Old Coast Highway to south of Santa Rosa Road Overcrossing. Rehabilitate pavement and drainage systems. (G13 Contingency)	1K450	2902	0518000209	201.121	23-24	\$188	\$0	\$0		NH	\$1,312	\$1,963	\$189	\$0	\$3,652	14.4	Lane mile(s)	
05	Santa Barbara	101	54.850	Near Buellton, at Nojoqui Creek Bridge No. 51-0074R. Repair bridge railing.	1R200	3175	0523000168	201.130	23-24	\$0	\$600	\$600	2/29/24	NH	\$0	\$0	\$0	\$120	\$720	1.0	Location(s)	
05	Santa Barbara	101	55.660	Near Buellton, at Nojoqui Creek No. 51-0019R. Reconstruct bridge railing.	1S120	3225	0524000172	201.130	23-24	\$0	\$550	\$550	4/30/24	NH	\$0	\$0	\$0	\$100	\$650	1.0	Location(s)	
05	Santa Barbara	101	55.900/R56.200	Near Buellton, from 0.1 mile south of Nojoqui Creek Bridge No. 51-0018L/R to 0.3 mile south of Santa Rosa Road Overcrossing. Environmental mitigation for bridge rail replacement and widening project EA 1F790.	1F791	2561A	0520000139	201.112	22-23	\$10	\$0	\$0		RMRA	\$0	\$0	\$0	\$123	\$133	0.0	Linear feet rail	
05	Santa Barbara	101	65.000/84.100	Near Los Alamos and Orcutt, from 1.8 miles north of Route 154 to 0.2 mile south of South Santa Maria Undercrossing. Rehabilitate drainage systems and lighting, and install Transportation Management System (TMS) elements.	1K510	2918	0518000215	201.151	23-24	\$464	\$4,523	\$0		RMRA	\$1,478	\$1,900	\$214	\$1,629	\$10,208	14.0	Culvert(s) (ea)	
05	Santa Barbara	101	82.200	Near Santa Maria, at Clark Avenue Overcrossing No. 51-0232. Replace and repair damaged bridge girders and provide traffic control.	1R160	3171	0523000152	201.130	22-23	\$0	\$1,900	\$1,900	6/23/23	NH	\$0	\$0	\$0	\$500	\$2,400	1.0	Location(s)	
05	Santa Barbara	101		In Santa Barbara County, on Routes 101, 144, 150, and 192 at various locations. Repair storm damage including clearing debris deposits, restoring hydraulic capacity in impacted channels, and repair bridge scour damage.	1Q830	3149	0523000078	201.130	22-23	\$50	\$3,600	\$3,600	3/13/23	NH	\$0	\$0	\$50	\$800	\$4,500	15.0	Location(s)	
05	Santa Barbara	135		In Santa Barbara County, on Routes 1, 135, and 246 at various locations. Repair storm damage, including drainage systems, slopes, and roadway.	1R120	3167	0523000147	201.130	22-23	\$20	\$2,200	\$2,200	4/11/23	NH	\$0	\$0	\$0	\$550	\$2,770	16.0	Location(s)	
05	Santa Barbara	154	R0.000/32.800	In Santa Barbara County, at various locations. Rehabilitate drainage systems and install Transportation Management System (TMS) elements.	1K520	2919	0518000216	201.151	23-24	\$317	\$12,979	\$0		RMRA	\$1,926	\$2,044	\$558	\$2,342	\$20,166	31.0	Culvert(s) (ea)	
05	Santa Barbara	154	2.000/R31.500	Near the city of Santa Barbara, from 0.4 mile west of Foxen Canyon Road to Route 192 (Foothill Road); also on Route 246 in Solvang at Alamo Pintado Road (PM 30.3). Repair storm damage, including debris removal, drainage system repair, and roadway restoration.	1Q680	3141	0523000063	201.130	22-23	\$50	\$7,400	\$7,400	3/13/23	NH	\$0	\$0	\$0	\$1,500	\$8,950	12.0	Location(s)	

2022 SHOPP As of June 2024 Close-Out
(\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
05	Santa Barbara	154	26.000/30.200	Near Santa Barbara, from 0.7 mile west of San Marcos/Painted Cave Road to San Antonio Creek Bridge at various locations. Clear catchment areas, repair rockfall fences, repair downdrain, clear landslides, and stabilize slopes.	1R650	3209	0524000099	201.130	23-24	\$100	\$4,200	\$4,200	3/28/24	NH	\$0	\$0	\$0	\$900	\$5,200	4.0	Location(s)	
05	Santa Barbara	192	5.100	In the city of Santa Barbara, at 0.9 mile west of Route 144. Construct a retaining wall and concrete barrier, modify drainage systems, and reconstruct the roadway.	1S030	3221	0524000161	201.130	23-24	\$50	\$3,800	\$3,800	4/19/24	NH	\$0	\$0	\$0	\$950	\$4,800	1.0	Location(s)	
05	Santa Barbara	192		In Santa Barbara county, on Routes 192 and 144 at various locations. Replace failed drainage system, repair slopes and slipouts, clear debris and rocks, repair rockfall fence, and clear creek debris.	1R620	3206	0524000096	201.130	23-24	\$25	\$2,500	\$2,500	3/8/24	NH	\$0	\$0	\$0	\$550	\$3,075	12.0	Location(s)	
05	Santa Barbara	246	10.910/R19.380	Near Lompoc, from 0.9 mile east of Sweeney Road to 0.8 mile east of Drum Canyon Road. Establish roadside ditch, reconstruct downdrain, clear sediment in box culvert, construct Rock Slope Construction (RSP) pad, and provide erosion control.	1R660	3210	0524000100	201.130	23-24	\$5	\$550	\$550	3/11/24	NH	\$0	\$0	\$0	\$100	\$655	3.0	Location(s)	
05	Santa Barbara	Var		In Santa Barbara and San Luis Obispo Counties, at six maintenance stations. Replace perimeter fencing and gates, and install security camera systems to improve security. This project will utilize the Emergency Limited Bid contract method.	1S280	3230	0524000188	201.352	23-24	\$0	\$2,090	\$2,090	5/17/24	ST-CASH	\$0	\$0	\$0	\$228	\$2,318	6.0	Location(s)	
05	Santa Cruz	1	0.000/R1.000	In and near Watsonville, from Monterey County line to Beach Street and at Pajaro River Bridge No. 44-0069; also in Monterey County, from 0.5 mile south of Salinas Road to Santa Cruz County line (PM 100.5/R102.031). Repair bridge scour, remove debris, and rebuild abutment slope.	1Q960	3161	0523000106	201.130	22-23	\$50	\$1,850	\$1,850	4/3/23	NH	\$0	\$0	\$0	\$700	\$2,600	1.0	Location(s)	
05	Santa Cruz	1	R0.000/R7.900	In and near Watsonville, from Monterey County line to north of Larkin Valley Road; also in Monterey County (PM R101.53). Rehabilitate drainage systems and lighting, install Transportation Management System (TMS) elements, pave areas behind the gore and construct Maintenance Vehicle Pullouts (MVPs) to reduce maintenance and enhance highway worker safety.	1K640	2926	0518000239	201.151	23-24	\$296	\$5,869	\$0		RMRA	\$1,570	\$2,456	\$43	\$1,813	\$12,047	16.0	Culvert(s) (ea)	
05	Santa Cruz	1	R5.000/8.200	Near Aptos, from 0.9 mile north of Buena Vista Drive to 0.1 mile south of Freedom Boulevard. Widen shoulders and install rumble strips. This project will improve safety and reduce the number and severity of collisions.	1P180	3074	0521000181	201.010	23-24	\$29	\$4,482	\$5,291	6/21/24	STP	\$0	\$2,173	\$37	\$1,319	\$8,040	64.0	Collision(s) reduced	
05	Santa Cruz	1	8.200/10.600	Near Capitola, from 0.2 mile south of Freedom Boulevard to State Park Drive. Upgrade concrete barrier, rehabilitate drainage systems, enhance highway worker safety, and replace highway lighting.	1J961	2843A	0523000185	201.015	23-24	\$0	\$9,051	\$0		STP	\$0	\$0	\$0	\$3,191	\$12,242	9.0	Collision(s) reduced	
05	Santa Cruz	1	8.200/26.000	In and near the cities of Capitola and Santa Cruz, from north of Larkin Valley Road Undercrossing to Laguna Road; also in Monterey County (PM R101.53). Rehabilitate drainage systems, enhance highway worker safety, replace lighting and install Transportation Management System (TMS) elements.	1J960	2843	0518000093	201.151	23-24	\$212	\$0	\$0		RMRA	\$2,206	\$3,264	\$779	\$0	\$6,461	0.0	Culvert(s) (ea)	
05	Santa Cruz	1	10.600/26.000	In and near the cities of Capitola and Santa Cruz, from State Park Drive to Laguna Road. Rehabilitate drainage systems, enhance highway worker safety, replace highway lighting, and install Transportation Management System (TMS) elements.	1J962	2843B	0523000198	201.151	23-24	\$0	\$9,942	\$0		RMRA	\$0	\$0	\$0	\$2,909	\$12,851	29.0	Culvert(s) (ea)	
05	Santa Cruz	1	13.300	In Capitola, at Soquel Creek Bridge No. 36-0013. Landscape and plant establishment for parent project EA 1H480.	1H481	2736Y	0521000112	201.119	22-23	\$0	\$300	\$355	8/17/23	RMRA	\$0	\$150	\$0	\$400	\$850	0.0	Bridge(s)	
05	Santa Cruz	1	13.300	In Capitola, at Soquel Creek Bridge No. 36-0013. Biological monitoring for parent project EA 1H480.	1H482	2736X	0522000017	201.119	22-23	\$25	\$0	\$0		RMRA	\$0	\$0	\$0	\$40	\$65	0.0	Bridge(s)	

2022 SHOPP As of June 2024 Close-Out
(\$1,000)

Dist	County	Route	Post Miles	Location/Description	EA	PPNO	Project ID	Prog Code	FY	RW	Con	Vote	Vote Date	Fund Type	PA&ED	PS&E	RW Sup	Con Sup	Total Cap & Sup	Performance Value	Performance Measure	Approved Baseline Agreement
05	Santa Cruz	1	31.900/35.700	Near Davenport, from 1.4 miles north of Swanton Road to 0.6 mile south of Waddell Creek. Environmental mitigation biological monitoring for project EA 0J200.	0J201	1967X	0522000010	201.151	22-23	\$10	\$0	\$0		RMRA	\$0	\$0	\$0	\$100	\$110	0.0	Culvert(s) (ea)	
05	Santa Cruz	1	33.000	Near Swanton, at 2.6 miles north of Swanton Road. Restore storm damaged slope.	1Q940	3159	0523000104	201.130	22-23	\$0	\$450	\$450	4/11/23	NH	\$0	\$0	\$0	\$180	\$630	1.0	Location(s)	
05	Santa Cruz	9	8.500/25.500	Near Ben Lomond, from Holiday Lane to 4.7 miles north of the northern junction of Routes 236/9. Replace failed culverts systems and construct energy dissipaters.	1G950	2627	0516000005	201.335	22-23	\$328	\$7,179	\$0		NH	\$1,445	\$2,377	\$1,078	\$2,025	\$14,432	15.4	Acre(s) treated/pollutant	
05	Santa Cruz	9	9.330	In the community of Ben Lomond, at Hillside Avenue; also at Jacobson Lane (PM 10.04). Replace culverts, reconstruct slope, reconstruct roadway, reset guardrail, and replace traffic delineation.	1R170	3172	0523000165	201.130	23-24	\$0	\$1,410	\$1,410	9/28/23	NH	\$0	\$0	\$0	\$420	\$1,830	2.0	Location(s)	
05	Santa Cruz	9		In Santa Cruz County, on Routes 9, 17, 35, and 236 at various locations. Clear fallen or hazardous trees, remove debris, and stabilize slopes.	1Q930	3158	0523000103	201.130	22-23	\$0	\$1,200	\$1,200	3/28/23	NH	\$0	\$0	\$0	\$360	\$1,560	15.0	Location(s)	
05	Santa Cruz	17	3.200/11.270	In and near Scotts Valley, from 0.2 mile south of Mount Hermon Road to 0.6 mile north of Glenwood Drive. Grind pavement, place Hot Mix Asphalt (HMA), and apply High Friction Surface Treatment (HFST) and contrasting surface treatment to improve safety. This project will reduce the number and severity of collisions.	1M730	3025	0520000055	201.010	22-23	\$0	\$6,923	\$6,644	5/8/23	STP	\$0	\$1,049	\$31	\$560	\$8,563	856.0	Collision(s) reduced	
05	Santa Cruz	35	3.000	Near Lexington Hills, at 0.3 mile north of Zayante Road. Install soldier pile wall, restore slope, roadway, and shoulder, and place erosion control.	1Q690	3142	0523000064	201.130	22-23	\$20	\$2,750	\$2,750	2/28/23	NH	\$0	\$50	\$50	\$700	\$3,570	1.0	Location(s)	
05	Santa Cruz	129	10.000/0.600	In and near Watsonville, from Route 1 to east of Blackburn Street; also on Route 152 (West Lake Avenue) from Main Street to Wagner Avenue (PM T2.8/1.33). Rehabilitate pavement and lighting, replace sign panels, install Transportation Management System (TMS) elements, construct new sidewalk, curb ramps, high visibility crosswalks, flashing beacons, and Class 2 and Class 3 bike lanes as complete streets elements.	1J830	2775	0518000078	201.121	23-24	\$943	\$8,440	\$0		NH	\$1,143	\$2,616	\$2,022	\$1,904	\$17,068	6.8	Lane mile(s)	
05	Santa Cruz	129		In Santa Cruz County, on Routes 129 and 152 at various locations. Clear slide debris and clear culverts.	1Q950	3160	0523000105	201.130	22-23	\$10	\$2,900	\$2,900	5/10/23	NH	\$0	\$0	\$0	\$850	\$3,760	34.0	Location(s)	
05	Santa Cruz	236	5.400	Near Boulder Creek, at 0.6 mile south of Lodge Road. Construct retaining wall to stabilize slope, widen shoulder, repair pavement, improve drainage systems and install erosion control.	1M450	3017	0519000153	201.131	22-23	\$8	\$2,521	\$2,184	10/12/22	NH	\$0	\$1,450	\$45	\$831	\$4,855	1.0	Location(s)	
05	Santa Cruz			Near Scotts Valley and Felton, on Routes 1, 9, 17, and 236 at various locations. Repair storm damage, including slope restoration, culvert replacement, roadway reconstruction, and debris removal.	1Q080	3102	0522000148	201.130	22-23	\$100	\$14,300	\$14,300	3/1/23	NH	\$0	\$300	\$50	\$3,920	\$18,670	13.0	Location(s)	