

Kings County BPMP Project List No.1

PM00144

County Location	Implementing Agency	Bridge number from Inspection Report	Facility Carried (Roadway)	Feature Intersected (Crossing)	Location	Sufficiency Rating	SD/FO Status	Health Index	PCI	Work Description	Width (ft)	Length (ft)	Deck Area (ft2)	Total Participating Cost (See Notes)	Unit Cost (\$/ft2)	Federal Share	Running Fed Summary	Local Share	Running Local Share
										BPMP Project List Administration				\$ 25,000.00		\$ 22,133	\$ 22,133	\$ 2,868	\$ 2,868
KIN	Kings County	45C0033	LACEY BLVD	LAST CHANCE DITCH	NEAR 13TH AVE	97.60	---	100.00		1. Repair the deck popout spalls. 2. Treat the bridge deck with methacrylate.	40.35	62.34	2,516	\$ 256,000	\$69.72	\$ 226,637	\$ 248,769	\$ 29,363	\$ 29,363
KIN	Kings County	45C0044	LACEY BLVD	LEMOORE CANAL	@ 17TH AVE	91.60	---	100.00		1. Treat the bridge deck with methacrylate.	32.15	65.62	2,110	\$ 97,000	\$29.25	\$ 85,874	\$ 334,643	\$ 11,126	\$ 40,489
KIN	Kings County	45C0081	6TH AVE	E BRANCH LAKELAND CANAL	3.3 MI S OF KANSAS AVE	98.70	---	100.00		1. Treat the deck with methacrylate	28.54	108.27	3,090	\$ 102,000	\$21.04	\$ 90,301	\$ 424,944	\$ 11,699	\$ 52,189
KIN	Kings County	45C0095	21ST AVE	KINGS RIVER (CLARKS FK)	S/O FAIRFAX AVE	97.00	---	70.00		1. Treat the bridge deck with methacrylate	32.48	193.57	6,287	\$ 116,000	\$12.04	\$ 102,695	\$ 527,639	\$ 13,305	\$ 65,494
KIN	Kings County	45C0096	24TH AVE	KINGS RIVER	0.2 M S ELGIN AVE	97.00	---	100.00		1. Treat the bridge deck with methacrylate.	31.82	167.32	5,325	\$ 112,000	\$13.62	\$ 99,154	\$ 626,792	\$ 12,846	\$ 78,340
KIN	Kings County	45C0113	LACEY BLVD	KINGS RIVER CLARKS FORK	0.3 MI W OF 23RD AVE	51.00	SD	40.00		1. Backfill the soil erosion under the end span (west) at abutment 1. 2. Treat the bridge deck with methacrylate	31.82	193.57	6,160	\$ 219,000	\$24.13	\$ 193,881	\$ 820,673	\$ 25,119	\$ 103,459
KIN	Kings County	45C0006	6TH AVE	TULE RIVER	0.5 MI S QUEBEC AVE	78.90	---	100.00		1. (NP) Repair the AC approach at abutment 12 2. Repair slope protection at abutment 12 3. Mitigate pile exposure conditions at both abutments	25.92	242.78	6,293	\$ 241,000	\$26.15	\$ 213,357	\$ 1,034,030	\$ 27,643	\$ 131,102
KIN	Kings County	45C0015	22ND AVE	CLARKS FORK KINGS RIVER	0.2 MI N/O GRANGEVILLE BL	82.30	---	97.91		1. Repair the soil erosion on the left embankment under abutment 10.	25.92	190.29	4,932	\$ 190,000	\$25.93	\$ 168,207	\$ 1,202,237	\$ 21,793	\$ 152,895
KIN	Kings County	45C0101	EVERETT AVE	LAST CHANCE DITCH	0.2 MI E OF 13TH AVE	87.10	---	100.00	100.00	1. Repair the area of peeled paint on girder 3 near abutment 2.	27.56	32.81	904	\$ 99,000	\$69.98	\$ 87,645	\$ 1,289,882	\$ 11,355	\$ 164,250
KIN	Kings County	45C0114	LAUREL AVE	KINGS RIVER	0.65 MI W 21ST AVE	82.10	---	74.60	50.00	1. Paint all the steel elements. 2. Treat the bridge deck with methacrylate 3. Replace the joint seals at bents 3 & 4 4. Repair the undermining and slope erosion at both abutments.	26.25	147.64	3,875	\$ 242,000	\$42.72	\$ 214,243	\$ 1,504,125	\$ 27,757	\$ 192,008
KIN	Kings County	45C0013	SANTA FE AVE	SWEET CANAL	1.5 MI S SHERMAN AVE	66.20	---	65.77		1. (NP) Repair potholes on the AC approach at abutment 1. 2. Repair the soil erosion at the left wingwall at abutment 1. 3. (NP) Repair the end section of the timber railing near abutment 1 right and abutment 5 left. 4. (NP) Repaint both timber bridge rails.	25.92	68.90	1,786	\$ 190,000	\$71.62	\$ 168,207	\$ 1,672,332	\$ 21,793	\$ 213,801
KIN	Kings County	45C0119	18TH AVE	TULARE LAKE CANAL	JUST SO MANTECA AVE	76.50	---	60.88		1. Repair the rotten timber lagging on the left side between piles 1 & 2 at abutment 1. 2. Mitigate the erosion condition at the embankment under both abutments. 3. Replace all rotten timber diagonal cross bracing at the pile bents.	20.01	68.90	1,379	\$ 276,000	\$137.64	\$ 244,343	\$ 1,916,675	\$ 31,657	\$ 245,458

(NP) = Non-Participating.
NP costs are removed from project costs.