# Federal Fiscal Year 2016/2017 Bridge Preventive Maintenance Program

PM00158

City of Santa Maria BPMP

| Facility Carried | Feature Intersected | Location | Sufficiency Rating | SD/FO Status | Work Description | Deck Area ($ft^2$) | Preliminary Engineering | Construction | Total Particip. Cost | Unit Cost ($/ft^2$) | Federal Share | Running Fed Summary | Local Share | Running Local Share | PE Schedule (FY) | Anticipated Constuction Execution (FY) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Suey Crossing Road | Santa Maria River | East of Suey Park | 82.0 | N/A | 1) Blast, Clean, and Paint Structural Steel, 2) Deck Joint Repair | 10,220 | $17,040 | $68,160 | $85,200 | 8 | 75,428 | 75,428 | 9,772 | 9,772 | 16/17 | 17/18 |
| Rancho Verde Street | Blosser Channel | At Blosser Road | 94.8 | SD | 1) Methacrylate Deck 2) Remove and Repair Unsound Concrete on Bridge Deck 3) Remove and Repair Unsound at Spall Locations | 1,885 | $7,333 | $29,330 | $36,663 | 19 | 32,457 | 107,885 | 4,205 | 13,978 | 16/17 | 17/18 |
| Taylor Street | Blosser Channel | At Blosser Road | 97.8 | N/A | 1) Epoxy Inject Cracks in Bridge Rail 2) Remove and Repair Unsound Concrete at Spall Locations | 1,885 | $6,375 | $25,500 | $31,875 | 17 | 28,219 | 136,104 | 3,656 | 17,634 | 17/18 | 18/19 |
| Carlotti Drive | Bradley Channel | 0.2 M S of Seaward Drive | 100.0 | N/A | Methacrylate Deck | 2,580 | $6,505 | $26,020 | $32,525 | 13 | 28,794 | 164,898 | 3,731 | 21,364 | 16/17 | 17/18 |
| Magellan Drive | Bradley Channel | 0.2 M N of Donovan Road | 100.0 | N/A | Epoxy Inject Cracks Noted | 1,000 | $10,899 | $43,595 | $54,494 | 54 | 48,243 | 213,142 | 6,250 | 27,615 | 17/18 | 18/19 |
| W Donovan Road | Blosser Channel | At N Blosser Road | 100.0 | N/A | Methacrylate Deck | 3,230 | $7,750 | $31,000 | $38,750 | 12 | 34,305 | 247,447 | 4,445 | 32,059 | 16/17 | 17/18 |
| | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | **Sum:** | | | **$279,506** | | **$247,447** | | **$32,059** | | | |
| | | | | | | | | | | | | | | | | |
| | | | | | | PE | 38,627.50 | 16/17 | | | | | | | | |
| | | | | | | PE | 17,273.75 | 17/18 | | | | | | | | |
| | | | | | | CON | 154,510.00 | 17/18 | | | | | | | | |
| | | | | | | CON | 69,095.00 | 18/19 | | | | | | | | |
| | | | | | | | 279,506.25 | | | | | | | | | |
| | | | | | | | | | | | | | | | | |