

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft2)	Total Particip. Cost (1)	Unit Cost (\$/ft2)	Federal Share	Running Federal Summary	Local Share	Running Local Share
0	10-CAL	Calaveras County			Various	Various	Various			PS&E		\$200,000		\$177,060	\$177,060	\$22,940	\$22,940
1	10-CAL	Calaveras County	30C0022	30C0022	Gold Strike Rd	Murray Creek	1.7 MI SW/O SR 49	84.4		- Repair Bearing Supports - Clean and Paint Bearing - Repair Embankment and Place Erosion Control	1587	\$22,000	\$14	\$19,477	\$196,537	\$2,523	\$25,463
2	10-CAL	Calaveras County	30C0069	30C0069	Milton Rd	Calaveras River	0.8 MI E. OF JENNY LIND RD	99.5		- Methacrylate Deck Treatment - Place Erosion Control	5019	\$38,000	\$8	\$33,641	\$230,178	\$4,359	\$29,822
3	10-CAL	Calaveras County	30C0017	30C0017	Jesus Maria Road	North Fork Calaveras Riv	2.4 MI S/E OF SR 26	99.5		- Remove and Replace Joint Seal	2650	\$12,000	\$5	\$10,624	\$240,802	\$1,376	\$31,198
4	10-CAL	Calaveras County	30C0023	30C0023	Gold Strike Road	North Fork Calaveras Riv	0.4 MI SW OF SR 49	87.5		- Remove and Replace Joint Seal - Repair Bearing Support - Paint Bridge Railing - Place Erosion Control.	4364	\$60,000	\$14	\$53,118	\$293,920	\$6,882	\$38,080
5	10-CAL	Calaveras County	30C0073	30C0073	Camanche Parkway	Mokelumne River	2.6 MI NE OF BURSON RD	80.9		- Remove and Replace Joint Seal - Methacrylate Deck Treatment - Place Erosion Control	11547	\$109,000	\$9	\$96,498	\$390,417	\$12,502	\$50,583
6	10-CAL	Calaveras County	30C0068	30C0068	Warren Rd	Indian Creek	JUST N OF INTERSE CT SR 26	73.7		- Remove and Replace Joint Seal	1124	\$9,000	\$8	\$7,968	\$398,385	\$1,032	\$51,615
7	10-CAL	Calaveras County	30C0040	30C0040	Sheep Ranch Rd	O'Neil Creek	N/W OF SHEEP RANCH	65.8		- Place Erosion Control	1063	\$3,000	\$3	\$2,656	\$401,041	\$344	\$51,959
8	10-CAL	Calaveras County	30C0066	30C0066	Warren Rd	Warren Creek	0.5 MI W/O EVERGRE EN RD	73.7		- Remove and Replace Joint Seals	604	\$12,000	\$20	\$10,624	\$411,665	\$1,376	\$53,336
9	10-CAL	Calaveras County	30C0058	30C0058	Hogan Dam Rd	Calaveras River	3.8 MI S/O SR 26	64.8		- Remove and Replace Joint Seal	3240	\$17,000	\$5	\$15,050	\$426,715	\$1,950	\$55,285
10	10-CAL	Calaveras County	30C0056	30C0056	Hogan Dam Rd	Bear Creek	9.0 MI S/O SR 26	79.1		- Clean and Paint Bearings. - Polyester Concrete Deck Overlay.	654	\$88,000	\$135	\$77,906	\$504,621	\$10,094	\$65,379

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft2)	Total Particip. Cost (1)	Unit Cost (\$/ft2)	Federal Share	Running Federal Summary	Local Share	Running Local Share
11	10-CAL	Calaveras County	30C0057	30C0057	Hogan Dam Rd	Slate Creek	6.3 MI S/O SR 26	73.1	SD	- Remove and Replace Joint Seal - Polyester Concrete Deck Overlay	859	\$107,000	\$125	\$94,727	\$599,348	\$12,273	\$77,652
12	10-CAL	Calaveras County	30C0053	30C0053	Calaveritas Rd	Willow Creek	OF MOUNTA IN RANCH	63.5	SD	- Remove Existing AC Surface - Polyester Concrete Deck Overlay	759	\$189,000	\$249	\$167,322	\$766,670	\$21,678	\$99,330
											Total BPMP Cost:	\$866,000					
(1) Except for BPMP Update Item 0, Total Participating Cost includes the sum of: CON = the sum of the contract items to complete the work description (including 10% mobilization), Contingency = (25%*CON), PE = (25%*CON), and CE = (15%*CON).																	