

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Unit Cost (\$/ft ²)	Federal Share	Local Share	Total Particip. Cost
1	Riverside County	Riverside County	Develop next BPMP				Various places in Riverside County			Develop next BPMP			44,265	5,735	50,000
2	Blythe	Riverside County	56C0122	S8182	RAGSDALE RD	CHUCKWALLA DITCH	1.6 MI. E/O Eagle Mtn Rd	73.8		Backfill erosion behind wingwall. Replace deteriorated timber elements including 3 columns and 1 girder and rehabilitate 1 bent cap.	1,037	98	90,421	11,715	102,136
3	Blythe	Riverside County	56C0121	S8181	RAGSDALE RD	ROCKDALE DITCH	1.3 MI. E/O Eagle Mtn Rd	84.6		Backfill erosion behind wingwalls. Replace deteriorated timber sheathing at abutments. Replace or supplement 4 timber columns. Rehabilitate 2 bent caps.	1,556	34	46,877	6,073	52,950
4	Thermal	Riverside County	56C0582	Not Assigned	HARRISON ST	Solo Ditch	1.5 MI W/O RTE 86S	90.5		Epoxy-inject cracked walls. Remove 3"± existing AC overlay, seal the bridge deck and place a 3" polyester concrete overlay. Repair the side-slope erosion at southwest wingwall	2,260	129	257,621	33,378	290,999
5	Thermal	Riverside County	56C0585	Not Assigned	HARRISON ST	Lundy Ditch	0.7 MI W/O RTE 86S	99.0		Backfill northwest wingwall erosion and place riprap to protect the new material. Epoxy-inject cracked walls.	2,670	30	70,284	9,106	79,390
6	Thermal	Riverside County	56C0454	M8365	62ND AVENUE	WHITEWATER RIVER	1.25 MI. W/O ST RTE 86S	99.8		Backfill erosion at both bridge ends. Clean and seal bridge deck with methacrylate. Inject cracks with epoxy.	18,396	9	139,091	18,021	157,112
7	Blythe	Riverside County	56C0123	S8183	RAGSDALE RD	ROCKLEDGE DITCH	1.9 MI. E/O Eagle Mtn Rd	75.1		Supplement timber caps at Bent 3; strengthen or supplement three columns at bents and one column at Abutment 4; supplement 15 decayed stringers; replace southeast wingwall top brace supplement.	2,024	122	218,238	28,275	246,513
8	Pedley	Riverside County	56C0320	Not Assigned	VAN BUREN BLVD	RCTC & BNSF RY	0.1 MI. W/O Route 215 FWY	83.2	SD	Clean and seal bridge deck with methacrylate.	10,733	5	48,692	6,309	55,000
9	Thermal	Riverside County	56C0586	Not Assigned	HARRISON ST, CA 86	LOWEN DITCH	0.6 MI SW/O RTE 86S	96	SD	Clean and seal bridge deck with methacrylate.	3,337	9	26,109	3,383	29,491
10	Thermal	Riverside County	56C0455	S8211	WASHINGTON ST	WASHINGTON ST OH	0.2 MI S/O ROUTE 10 FWY.	93.8		Clean and seal bridge deck with methacrylate. Inject cracks with epoxy. Replace joint seal	20,948	12	219,182	28,397	247,580
11	Sky Valley	Riverside County	56C0448L	M8320	MONTEREY AVE S/B LN	S.P. RR X-ING	0.1 M S/O I-10 FWY	94		Clean and seal bridge deck with methacrylate. Inject cracks with epoxy.	17,599	7	109,256	14,155	123,411
12	Pedley	Riverside County	56C0269	69E8233	SCHLEISMAN RD	CUCAMONGA CREEK	0.5 MI. W/O Archibald Ave	92.8	SD	Clean and seal bridge deck with methacrylate.	4,717	6	24,788	3,212	28,000
13	Pedley	Riverside County	56C0140	69J8206	JURUPA RD	SAN SEVAINE CHANNEL	100' east of Bain St	95.3	SD	Clean and seal bridge deck with methacrylate. Inject cracks with epoxy.	5,231	17	79,677	10,323	90,000
14	Perris	Riverside County	56C0450	Not Assigned	PLACENTIA AV	PLACENTIA AV OH	0.1 M W/O 215 FWY	96.9	SD	Clean and seal bridge deck with methacrylate. Inject cracks with epoxy.	10,344	6	54,889	7,111	62,000
15	Thermal	Riverside County	56C0587	Not Assigned	HARRISON ST, CA 86	VICD DITCH	0.7 MI SW/O RTE 86S	69	SD	Clean and seal bridge deck with methacrylate.	3,665	9	27,593	3,575	31,168
16	El Cerrito	Riverside County	56C0382	Not Assigned	DAWSON CANYON RD	TEMESCAL WASH	0.2 MI NE/O Temescal CY Rd	48	SD	Repair settled A/C at east approach. Clean and seal bridge deck with methacrylate.	7,270	10	61,772	8,003	69,775
17	Sky Valley	Riverside County	56C0448R	M8325	MONTEREY AVE S/B LN	S.P. RR X-ING	0.1 M S/O I-10 FWY	97		Clean and seal bridge deck with methacrylate. Inject cracks with epoxy.	20,045	8	134,837	17,470	152,307
18	Sky Valley	Riverside County	56C0052	S8163	RAMON RD	S.P. RR X-ING	0.1 MI. W/O Route 10 Fwy	85.7		Clean and seal bridge deck with methacrylate and replace joint seals.	10,792	12	111,862	14,493	126,355
19	Pedley	Riverside County	56C0471	69J8280	COUNTRY VILLAGE RD	SAN SEVAINE/ DECLEZ CHANNEL	0.7 MI. N/O ROUTE 60 FWY	90.1		Replace joint seal. Clean and seal bridge deck with methacrylate. Replace broken approach slabs.	3,820	59	198,307	25,693	224,000
20	El Cerrito	Riverside County	56C0155	S8003	CAJALCO RD	TEMESCAL WASH	0.7 MI E/O RTE 15 FWY	77.1		Clean and seal bridge deck with methacrylate.	6,960	8	46,895	6,076	52,971

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Unit Cost (\$/ft ²)	Federal Share	Local Share	Total Particip. Cost
21	Sky valley	Riverside County	56C0486	M8330-	COOK ST	S.P. RR X-ING & I-10	0.1 MI. S/O ROUTE 10-FWY	91.2		Clean and seal bridge deck with methacrylate.	52,730	5	240,802	31,198	272,000
22	Perris	Riverside County	56C0341	Not Assigned	ALESSANDRO BLVD	RCTC & BNSF RY	100' W/O Route 215 FWY	80.5		Clean and seal bridge deck with methacrylate.	15,020	7	89,362	11,578	100,939
23	Beaumont	Riverside County	56C0244	S8010	SAN TIMOTEO CANYON RD	SAN TIMOTEO CREEK	0.3 MI. W/O Woodhouse Rd	89		Clean and seal bridge deck with methacrylate. Inject cracks with epoxy.	3,336	9	26,828	3,476	30,304
24	Murrieta	Riverside County	56C0526	M8395	WILLOWS AVE	TUCALOCA CREEK	0.1 MI. S/O ROUTE 79 HWY	96.3		Clean and seal bridge deck with methacrylate. Inject cracks with epoxy.	8,933	13	99,052	12,833	111,885
25	Perris	Riverside County	56C0196	Not Assigned	CAJALCO ROAD	RAMONA EXPRESSWAY OH	0.1 MI. W/O RTE 215 Fwy	97.2		Clean and seal bridge deck with methacrylate. Inject cracks with epoxy.	10,469	11	103,868	13,457	117,325
26	Thermal	Riverside County	56C0579	Not Assigned	66TH AVE, CA-195	WHITEWATER RIVER	0.9 MI. W/O ST RTE 86S	95.6		Core and test for ASR. Core and test for ASR. Remove existing AC overlay and install 20mm thick of polyester concrete overlay.	1,730	40	61,971	8,029	70,000
27	Thermal	Riverside County	56C0578	Not Assigned	RTE 111	WHITEWATER RIVER	On Route 111	85.3	SD	Repair A/C approach at both abutment. Replace joint seal. Clean and seal bridge deck with methacrylate and place 1" of polyester concrete overlay.	19,387	54	934,707	121,101	1,055,808
28	Pedley	Riverside County	56C0268	69E8418	HELLMAN AVE	GUCAMONGA CREEK	0.7 MI. S/O Schleisman Rd	96.7		Clean and seal bridge deck with methacrylate. Repair A/C approach at both ends	7,149	8	51,347	6,653	58,000
29	Pedley	Riverside County	56C0414	69J8345	HARREL ST	DAY CREEK CHANNEL	0.2 M W/O Etiwanda Ave	96.9		Clean and seal bridge deck with methacrylate. Repair A/C approach at both ends	3,598	10	31,871	4,129	36,000
30	Hemet	Riverside County	56C0522	M8437	STATE ST	SAN JACINTO RIVER	1.4 MI. N/O RAMONA EXPWY	83.3		Clean and seal bridge deck with methacrylate. Clean and paint column steel shell	53,755	11	533,689	69,145	602,834
31	Perris	Riverside County	56C0451	Not Assigned	STRATTA RD	OLEANDER AVE OH	100' W/O RTE 215 FWY	99.5		Clean and seal bridge deck with methacrylate. Inject cracks with epoxy. Reconstruct the depressed AC approach at abutment 1 to be leveled with the bridge deck.	10,912	12	114,166	14,791	128,958
32	Thermal	Riverside County	56C0584	Not Assigned	HARRISON ST, CA 86	ALMAR DITCH	1.3 MI NW/O RTE 86S	99		Remove 4"± existing AC overlay, seal the bridge deck and place a 4" polyester concrete overlay. Repair the concrete spall 16" x 8" x 6" with rebar exposed at the southeast end of the wingwall.	4,060	140	502,540	65,109	567,650
											Total cost w/o the cost for developing next BPMP =		\$ 4,477,859		
Notes: Work that has been added to the original scope is printed in blue while work that has been removed is struck out in red.															
Rows that have been struck out completely are bridges that have been removed from the funding application as they are no longer in County's jurisdiction.															
											PE =		\$ 980,164		
											CON (Construction Cost+Mobilization + Contingency + CE) =		\$ 3,497,695		
											Total Participating Cost=		\$ 4,477,859		

Project Prioritization

Local Agencies must develop objective procedures to prioritize their preventive maintenance projects. These procedures must be included in the project files for review in future audits. High priority projects should include the repair of scour countermeasure, embankment erosion control and the repair, restoration, and strengthening of structural elements.

Priority should be given to bridges that are not eligible for rehabilitation or replacement under the Federal Highway Bridge Program. The intent of the program is to keep these bridges in structurally good condition to maximize their service life and to conserve limited funds available for bridges that do require major rehabilitation or replacement. (Bridges eligible for rehabilitation or replacement are rated SD or FO and have a sufficiency rating of 80 or less.)

Deadlines:

Local agency transmits the BPMP with cover letter certifying compliance with these program guidelines. The electronic copy (any spreadsheet format) should be included on a CD with the paper transmittal letter. The DLAE's must receive the BPMPs by September 30th for funds to be obligated in the next FFY year, and January 30th of each year for adjustments. No time extensions will be granted.

Accountability:

Local Agencies are responsible for understanding and complying with the program requirements defined in the "Bridge Preventive Maintenance Program Guidelines For Local Agencies."