

Implementing Local Agency Name
 Federal Fiscal Year 20XX/20XX Bridge Preventive Maintenance Program
 (EDIT Federal Fiscal Year as Needed)

Priority (Lowest Number Is Top Priority)	Agency Location	Bridge Number from Inspection Report	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Unit Cost (\$/ft ²)	Federal Share	Local Share	Total Particip. Cost	Phase	Request for Funds FY		
1	City of Salinas	44C0039L	South Sanborn	UPRR	.5 mi West of US 101	71.7	FO	Preliminary Engineering for PS&E for BPMP work	21,200.00	7	128,700	16,675	145,375	PE	17 - 18		
1	City of Salinas	44C0039R	South Sanborn	UPRR	.5 mi West of US 101	71.6	FO	Preliminary Engineering for PS&E for BPMP work	21,700.00	7	143,961	18,652	162,613	PE	17 - 18		
1	City of Salinas	44C0168	East Market Street	East Front St	0.75 mi West of US 101	88.8	FO	Preliminary Engineering for PS&E for BPMP work	5,720.00	6	29,684	3,846	33,530	PE	17 - 18		
2	City of Salinas	44C0105	East Laurel	Natividad Creek	0.55 mi south of Natividad	97.3		Preliminary Engineering for PS&E for BPMP work	3,600.00	15	47,105	6,103	53,208	PE	17 - 18		
2	City of Salinas	44C0201	Las Casitas	Natividad Creek	0.25 mi South of Constitution	80.1		Preliminary Engineering for PS&E for BPMP work	1,612.00	4	5,763	747	6,510	PE	17 - 18		
3	City of Salinas	44C0052	North Main	Little Bear Creek	0.22 mi North of Boronda	94.6		Preliminary Engineering for PS&E for BPMP work	3,440.00	1	3,099	401	3,500	PE	17 - 18		
3	City of Salinas	44C0095	Van Buren	Santa Rita Creek	0.25 mi West of San Juan Grade Road	90.3		Preliminary Engineering for PS&E for BPMP work	1,100.00	2	1,859	241	2,100	PE	17 - 18		
3	City of Salinas	44C0096	West Lake	Main Canal	0.65 mi East of North Davis Road	98.9		Preliminary Engineering for PS&E for BPMP work	1,612.00	8	12,096	1,567	13,663	PE	17 - 18		
											PE Sub Total =						
											\$ 372,267			\$ 48,231	\$ 420,499		
1	City of Salinas	44C0039L	South Sanborn	UPRR	.5 mi West of US 101	71.7	FO	Joint seal replacement, repair spalls in deck, polyester overlay, paint steel girders	21,200.00	27	514,802	66,698	581,500	CON	18 - 19		
1	City of Salinas	44C0039R	South Sanborn	UPRR	.5 mi West of US 101	71.6	FO	Joint seal replacement, repair spalls in deck, polyester overlay, repair spalling in soffit	21,700.00	30	575,843	74,607	650,450	CON	18 - 19		
1	City of Salinas	44C0168	East Market Street	East Front St	0.75 mi West of US 101	88.8	FO	Joint seal replacement, polyester overlay, repair spalling in barrier rail	5,720.00	23	118,736	15,384	134,120	CON	18 - 19		
2	City of Salinas	44C0105	East Laurel	Natividad Creek	0.55 mi south of Natividad	97.3		Culvert Invert/Outlet repair	3,600.00	26	82,182	10,648	92,830	CON	19 - 20		
2	City of Salinas	44C0201	Las Casitas	Natividad Creek	0.25 mi South of Constitution	80.1		Methacrylate Bridge Deck	1,612.00	16	23,053	2,987	26,040	CON	19 - 20		
3	City of Salinas	44C0052	North Main	Little Bear Creek	0.22 mi North of Boronda	94.6		Repair spalling concrete on superstructure	3,440.00	4	12,394	1,606	14,000	CON	19 - 20		
3	City of Salinas	44C0095	Van Buren	Santa Rita Creek	0.25 mi West of San Juan Grade Road	90.3		Repair delaminated concrete near abutment	1,100.00	8	7,437	963	8,400	CON	19 - 20		
3	City of Salinas	44C0096	West Lake	Main Canal	0.65 mi East of North Davis Road	98.9		Repair delaminated concrete on bridge rails, repair scour	1,612.00	34	48,382	6,268	54,650	CON	19 - 20		
											CON Sub Total =						
											\$ 1,382,830			\$ 179,160	\$ 1,561,990		
											Grand Total (PE + CON) =						
											\$ 1,755,097			\$ 227,391	\$ 1,982,489		

*\$30,000 for environmental costs