

CITY OF CHICO BRIDGE PREVENTATIVE MAINTENANCE PLAN (BPMP)
FEDERAL FISCAL YEAR 2018

| Priority | Agency Location | Bridge Number | Facility Carried | Feature Intersected | Location | Sufficiency Rating | SD/FO Status | Work Description | Deck Area (ft ²) | Unit Cost (\$/SF Deck) | Federal Share (88.53%) | Local Share (11.47%) | Total Particip. Cost |
|----------|-----------------|---------------|-------------------|-----------------------------|-----------------------------|--------------------|--------------|--|------------------------------|------------------------|------------------------|----------------------|----------------------|
| 1 | CHICO | | | | | | | Development of following year BPMP | | | \$ 13,279.50 | \$ 1,720.50 | \$ 15,000.00 |
| 2 | CHICO | 12C0277 | VALLOMBROSA AVE | BIG CHICO CREEK | BTW 1ST ST AND MEMORIAL WAY | 58.9 | | RSP, Scour Mitigation | 3108.62 | \$46 | \$ 126,953.88 | \$ 16,448.22 | \$ 143,402.10 |
| 3 | CHICO | 12C0201 | PARK AVE | LITTLE CHICO CREEK | 0.1 MI N OF 11TH ST | 55.0 | | RSP, Scour Mitigation | 4091.36 | \$28 | \$ 100,553.43 | \$ 13,027.76 | \$ 113,581.19 |
| 4 | CHICO | 12C0276 | WARNER ST | BIG CHICO CREEK | BTW 1ST ST & LEGION AVE | 62.3 | | RSP, Scour Mitigation Joint Seal | 2121.57 | \$55 | \$ 103,599.12 | \$ 13,422.36 | \$ 117,021.49 |
| 5 | CHICO | 12C0299 | BRUCE RD | S FORK DEAD HORSE SLOUGH | JUST N OF SR 32 | 85.2 | | RSP, Scour Mitigation | 3148.44 | \$27 | \$ 74,519.81 | \$ 9,654.83 | \$ 84,174.64 |
| 6 | CHICO | 12C0274 | E 5TH AVE (CHICO) | LINDO CHANNEL | AT E. LINDO AVENUE | 89.8 | | RSP, Scour Mitigation Methacrylate Deck | 5121.47 | \$31 | \$ 139,899.37 | \$ 18,125.45 | \$ 158,024.81 |
| 7 | CHICO | 12C0281 | CYPRESS ST | LITTLE CHICO CREEK | BTW HUMBOLDT AV & 12TH ST | 79.3 | | RSP, Scour Mitigation Methacrylate Deck | 2448.79 | \$57 | \$ 124,030.27 | \$ 16,069.44 | \$ 140,099.71 |
| 8 | CHICO | 12C0205 | MAIN STREET | BIG CHICO CREEK | 0.15 MI N 2ND ST | 65.0 | | Joint Seal | 3348.65 | \$11 | \$ 32,140.94 | \$ 4,164.20 | \$ 36,305.14 |
| 9 | CHICO | 12C0273 | MANGROVE AVE | LINDO CHANNEL | BTWN E 10TH & COHASSET | 77.7 | | Spall Repair Joint Seal Methacrylate Deck | 8650.96 | \$19 | \$ 144,172.88 | \$ 18,679.13 | \$ 162,852.01 |
| 10 | CHICO | 12C0363 | WALNUT ST | LITTLE CHICO CREEK | BTWN DAYTON RD & 9TH ST | 97.0 | | RSP, Scour Mitigation Methacrylate Deck | 3020.35 | \$43 | \$ 115,578.60 | \$ 14,974.43 | \$ 130,553.03 |
| 11 | CHICO | 12C0056 | MIDWAY ROAD | COMANCHE CREEK | 0.1 MI S PARK AVE | 58.3 | | Methacrylate Deck Spall Repair | 4546.68 | \$14 | \$ 55,727.27 | \$ 7,220.06 | \$ 62,947.33 |
| 12 | CHICO | 12C0064 | LONGFELLOW AVE | LINDO CHANNEL | BTWN E 1ST ST & MANZANITA | 76.2 | FO | Methacrylate Deck | 5289.39 | \$13 | \$ 61,235.48 | \$ 7,933.71 | \$ 69,169.19 |
| 13 | CHICO | 12C106 | BRUCE RD | LITTLE CHICO CREEK | 0.5 MI S HUMBOLT RD | 59.8 | | Methacrylate Deck | 1829.86 | \$13 | \$ 21,180.79 | \$ 2,744.20 | \$ 23,924.99 |
| 14 | CHICO | 12C0216R | SKYWAY AVENUE | LITTLE CHICO-BUTTE CR DV CH | 0.4 MI NW HUMBBUG ROAD | 71.0 | | Methacrylate Deck | 4257.13 | \$13 | \$ 49,272.10 | \$ 6,383.72 | \$ 55,655.83 |
| 15 | CHICO | 12C0298 | FOREST AVE | LITTLE CHICO CREEK | JUST S OF HUMBOLDT RD | 94.0 | | Methacrylate Deck | 5877.10 | \$13 | \$ 68,028.96 | \$ 8,813.87 | \$ 76,842.83 |
| 16 | CHICO | 12C0275 | MANZANITA AVE | LINDO CHANNEL | BTW EAST AVE & HOOKER OAK | 83.0 | | Methacrylate Deck | 6170.95 | \$13 | \$ 71,430.01 | \$ 9,254.51 | \$ 80,684.52 |
| 17 | CHICO | 12C0338 | MILL ST | LITTLE CHICO CREEK | 0.1 MI N OF 12TH ST | 49.3 | | Methacrylate Deck | 1414.38 | \$13 | \$ 16,372.77 | \$ 2,121.27 | \$ 18,494.03 |
| 18 | CHICO | 12C0212 | MANZANITA AVE | BIG CHICO CREEK | BTW VALLOMBROSA&CENTENNAL | 84.8 | | Methacrylate Deck | 4038.62 | \$13 | \$ 46,742.00 | \$ 6,055.92 | \$ 52,797.92 |
| 19 | CHICO | 12C0422 | COHASSET RD | SYCAMORE CREEK TRIBUTARY | 0.7 MI N/O EATON RD | 92.6 | | Joint Seal | 5812.51 | \$13 | \$ 66,294.56 | \$ 8,589.16 | \$ 74,883.72 |
| 20 | CHICO | 12C0337 | BROADWAY ST | LITTLE CHICO CREEK | JUST S OF 9TH ST | 71.5 | | AC Deck Removal Methacrylate Deck Wingwall and Backwall Repair | 1695.32 | \$151 | \$ 226,413.33 | \$ 29,334.25 | \$ 255,747.58 |
| 21 | CHICO | 12C0280 | PINE ST | LITTLE CHICO CREEK | BTW HUMBOLDT AV & 12TH ST | 79.3 | | Methacrylate Deck | 2350.84 | \$13 | \$ 27,215.00 | \$ 3,525.99 | \$ 30,740.99 |
| 22 | CHICO | 12C0335 | CHESTNUT ST | LITTLE CHICO CREEK | AT W 9TH ST | 97.8 | | Methacrylate Deck | 3151.67 | \$13 | \$ 36,484.14 | \$ 4,726.91 | \$ 41,211.05 |

Revised 09/22/17

Grand Total = \$ 1,721,124 \$ 222,990 \$ 1,944,114