

Priority Number	County Location	District	(8) Structure Number	(7) Facility Carried	(6) Feature Intersected	(9) Location	Sufficiency Rating	Status	BPMP Work Description	Deck Area (ft ²)	Unit Cost (\$/ft ²)	Contract Cost	PE Cost	Federal Share	Local Share	Total Participating Cost
1	109	10							Develop future years BPMP				\$ 35,000	\$ 30,990	\$ 4,010	\$ 35,000
2	109	10	32C0041	Jacksonville Road	Sullivan Creek	6.9 MI N/O SR 120	83		Methacrylate deck treatment; Replace joint seals; Replace asphalt concrete bridge approaches (due to excessive maintenance history)	7,726	\$ 23	\$ 151,980	\$ 26,020	\$ 157,590	\$ 20,410	\$ 178,000
3	109	10	32C0047	Jamestown Road	Woods Creek	0.4 MI NE of SR 49 & 108	99		Methacrylate deck treatment; Replace asphalt concrete bridge approaches (due to excessive maintenance history)	2,628	\$ 48	\$ 111,750	\$ 13,814	\$ 111,170	\$ 14,394	\$ 125,564
4	109	10	32C0055	Ferretti Road	Big Creek	3.3 MI NE of SR 120	89		Inspect Bridge Deck by Sounding; Polyester concrete deck treatment; Repair concrete spalls on structural elements; Replace asphalt concrete bridge approaches (due to excessive maintenance history)	5,113	\$ 42	\$ 193,700	\$ 18,891	\$ 188,210	\$ 24,381	\$ 212,591
5	109	10	32C0012	Wards Ferry Road	Tuolumne River	7.2 MI N of SR 120	96		Methacrylate deck treatment; Replace joint seals	13,086	\$ 12	\$ 134,100	\$ 19,043	\$ 135,580	\$ 17,563	\$ 153,143
6	109	10	32C0019	Rock River Road	Dry Creek	2 MI S Green Spring Road	83		Removal and repair of unsound concrete; Methacrylate deck treatment; Replace asphalt concrete bridge approaches (due to excessive maintenance history)	1,010	\$ 95	\$ 81,950	\$ 13,762	\$ 84,740	\$ 10,972	\$ 95,712
7	109	10	32C0025	Yosemite Road	Turnback Creek	0.3 MI W/O Oak Street	97		Methacrylate deck treatment; Repair to existing erosion control measures	3,218	\$ 32	\$ 89,400	\$ 14,109	\$ 91,640	\$ 11,869	\$ 103,509
8	109	10	32C0029	South Fork Road	South Fork Stanislaus River	3.3 MI NW Confidence South Fork	98		Methacrylate deck treatment; Replace asphalt concrete bridge approaches (due to excessive maintenance history)	2,444	\$ 45	\$ 96,850	\$ 13,722	\$ 97,890	\$ 12,682	\$ 110,572
9	109	10	32C0031	Horse Shoe Bend Road	Mormon Creek	0.1 MI W Springfield Road	87		Methacrylate deck treatment	980	\$ 59	\$ 44,700	\$ 12,990	\$ 51,080	\$ 6,610	\$ 57,690
10	109	10	32C0072	Sprague Road	Big Creek	2.5 MI W Smith Station	85		Methacrylate deck treatment; Repair concrete spalls on structural elements; Repair/replace deteriorated railing; Spot painting	960	\$ 162	\$ 141,550	\$ 14,180	\$ 137,870	\$ 17,860	\$ 155,730
11	109	10	32C0068	Paseo De Los Portales	Sullivan Creek	0.1m N of Phoenix Lake Rd	100		Methacrylate deck treatment; Repair to existing erosion measures	2,341	\$ 32	\$ 59,600	\$ 15,426	\$ 66,430	\$ 8,596	\$ 75,026
12	109	10	32C0040	Clarks Fork Road	Middle Fork Stanislaus River	0.7 mi NE of SR 108	43.1		Methacrylate deck treatment; Replace joint seals; Repair concrete spalls on structural elements; Repair/replace deteriorated railing	6,200	\$ 31	\$ 166,620	\$ 23,350	\$ 168,190	\$ 21,780	\$ 189,970
											Total	\$ 1,272,200	\$ 220,307	\$ 1,321,380	\$ 171,127	\$ 1,492,507