

Federal Fiscal Year 2017/2018 Bridge Preventative Maintenance Program - Added Bridges

| Priority (Lowest Number is Top Priority) | County Location | Implementing Agency | Bridge No. | Year Built | Local Agency Bridge I.D. | Facility Carried | Feature Intersected | Location | Sufficiency Rating | SD/FO Status | Scour Critical Bridges (113) | Work Description | Deck Area (S.F.) | Total Participating Cost (PE + Const.) | Unit Cost (\$/SF) | Federal Share %88.53 | Running Federal Summary | Local Share %11.47 | Running Local Share | Comments |
|--|-----------------|---------------------|------------|------------|--------------------------|--------------------|---------------------------|--------------------------|--------------------|--------------|------------------------------|---|------------------------|--|------------------------|----------------------|-------------------------|--------------------|---------------------|----------|
| 1 | San Joaquin | City of Stockton | 29C0134 | | 29C0134 | Lower Sac. Rd | Mosher Slough | N. of Macduff Ave | 72.7 | SD | 5 | Deck Sealing w/ Methacrylate | 6,997 | \$ 215,507.60 | \$30.80 | \$ 190,788.88 | \$ 190,788.88 | \$ 24,718.72 | \$ 24,718.72 | |
| 2 | San Joaquin | City of Stockton | 29C0058L | 1921 | 29C0058L | Pacific Ave | Calaveras River | 0.25 mi N. Fulton St. | 53.7 | FO | 7 | Cracked AC approach at Abut. 7. | 9,451 | \$ 244,497.37 | \$25.87 | \$ 216,453.52 | \$ 216,453.52 | \$ 28,043.85 | \$ 28,043.85 | |
| 3 | San Joaquin | City of Stockton | 29C0058R | 1921 | 29C0058R | Pacific Ave | Calaveras River | 0.25 mi N. Fulton St. | 72.3 | FO | 7 | Failed joint seals | 8,396 | \$ 225,012.80 | \$26.80 | \$ 199,203.83 | \$ 199,203.83 | \$ 25,808.97 | \$ 25,808.97 | |
| 4 | San Joaquin | City of Stockton | 29C0435 | 1982 | 29C0435 | Producers Drive | N Fork Little Johns Creek | At Industrial Drive | 69.7 | SD | 8 | Methacrylate Culvert | 2,793 | \$ 201,096.00 | \$72.00 | \$ 178,030.29 | \$ 178,030.29 | \$ 23,065.71 | \$ 23,065.71 | |
| 5 | San Joaquin | City of Stockton | 29C0417 | 1937 | 29C0417 | UPRR, BNSF RY | MLK BLVD UP | 0.2 mi w of Airport Way | 41.6 | | N | Deck Sealing w/ Methacrylate; Concrete Bridge rail damage | 3,079 | \$ 201,674.50 | \$65.50 | \$ 178,542.43 | \$ 178,542.43 | \$ 23,132.07 | \$ 23,132.07 | |
| 6 | San Joaquin | City of Stockton | 29C0169 | 1957 | 29C0169 | Airport Way | Mormon Slough | 0.2 mi N. MLK Blvd. | 75.1 | | 5 | Slope repair, Abut. 1 | 3,897 | \$ 233,820.00 | \$60.00 | \$ 207,000.85 | \$ 207,000.85 | \$ 26,819.15 | \$ 26,819.15 | |
| 7 | San Joaquin | City of Stockton | 29C0191 | 1993 | 29C0191 | Thornton Rd. | Bear Creek | 1.4 mi N Davis Rd. | 72.3 | | 5 | Deck Sealing w/ Methacrylate | 17,718 | \$ 422,397.12 | \$23.84 | \$ 373,948.17 | \$ 373,948.17 | \$ 48,448.95 | \$ 48,448.95 | |
| 8 | San Joaquin | City of Stockton | 29C0418 | 1937 | 29C0418 | UPRR, BNSF, AMTRAK | MLK BLVD UP | 0.1 mi W Airport Way | 50.1 | FO | N | Deck Sealing w/ Methacrylate; Concrete Bridge rail damage | 1,744 | \$ 148,240.00 | \$85.00 | \$ 131,236.87 | \$ 131,236.87 | \$ 17,003.13 | \$ 17,003.13 | |
| 9 | San Joaquin | City of Stockton | 29C0431 | 1986 | 29C0431 | MLK Blvd. | Mormon Slough | 0.3 mi E of Mariposa Rd. | 78.0 | | 8 | Erosion channels; Construct AC dike for drainage | 5,060 | \$ 278,300.00 | \$55.00 | \$ 246,378.99 | \$ 246,378.99 | \$ 31,921.01 | \$ 31,921.01 | |
| Total | | | | | | | | | | | | | \$ 2,170,845.39 | | \$ 1,921,583.83 | | \$ 248,961.56 | | | |