County of Ventura PWA - Transportatoin Department
Federal Fiscal Year 2018/2019 Bridge Preventive Maintenance Program

Priority (Lowest Number Is Top Priority)	Agency Location	Bridge Number from Inspection Report	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft^2)	Unit Cost ($/ft^2$)	Federal Share	Local Share	Total Particip. Cost
1	District 7	52C0142	Victoria Avenue	Santa Clara River	1.3 MI South Route	85.2	NA	Clean and seal deck with methacrylate	105,916	3.00	281,260	36,440	317,700
2	District 7	52C0041	Creek Road	San Antonio Creek	W County Club Drive	97.6	NA	Clean and seal deck with methacrylate	4,509	3.00	11,952	1,548	13,500
3	District 7	52C0185	Koenigstein Road	Sisar Creek	0.01 MI N of State Route 150	84.2	NA	Clean and seal deck with methacrylate	1,296	3.00	3,453	447	3,900
4	District 7	52C0110	Santa Ana Road	Coyote Creek	0.7 MI NW State Route 33	55.6	FO	Clean and seal deck with methacrylate	4,453	3.00	11,863	1,537	13,400
5	District 7	52C0011	Old Telegraph Road	West Branch Sespe Creek	1.1 MI NW of 'A' Street	99.1	NA	Clean and seal deck with methacrylate	10,159	3.00	27,002	3,498	30,500
6	District 7	52C0176	Grimes Canyon Road	Grimes Canyon Wash	1.4 MI N of State Route 118	95.1	NA	Clean and seal deck with methacrylate	2,879	3.00	7,614	986	8,600
										Grand Total =	**$ 343,142**	**$ 44,458**	**$ 387,600**