

Federal Fiscal Year 2006/2007 Bridge Preventive Maintenance Program  
**For the City Of Oakland**

CITY OF OAKLAND BRIDGE PREVENTIVE MAINTENANCE PLAN 2012 UPDATED 2019																	
Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft <sup>2</sup> )	Total Participle. Cost	Unit Cost (\$/ft <sup>2</sup> )	Federal Share	Running Fed Summary	Local Share	Running Local Share
1	Alameda	City of Oakland	Develop next year's BPMP								1.00	\$ 18,000	18,000	\$ 15,935	\$ 15,935	\$ 2,065	\$ 2,065
2	Alameda	City of Oakland	33C0028		Adeline Street	UP Rail Track	Just South of 3rd Street	81.1	SD	Repair crack at Abutment, Joint seal replacement, Treat Deck with Methacrylate, repair spalls	63,645.00	\$ 2,384,057	37	\$ 2,110,606	\$ 2,126,541	\$ 273,451	\$ 275,516
3	Alameda	City of Oakland	33C0393		West Grand Avenue	Wood St	04-ALA-018-0-OAK	95.9	SD	Treat Deck with Methacrylate, repair joint plate	307,031.00	\$ 1,544,954	5	\$ 1,367,748	\$ 3,494,289	\$ 177,206	\$ 452,722
4	Alameda	City of Oakland	33C0202		Helgenberger Road	BART, UPRR, San Leandro St.	At San Leandro St.	69.1	SD	Treat Bridge Deck, repair spalls, install new joint seal.	72,000.00	\$ 792,000	11	\$ 701,158	\$ 4,195,446	\$ 90,842	\$ 543,565
5	Alameda	City of Oakland	33C0149		E 8th Street	Lake Merritt Channel	E 8th Street & E 7th Street	94.1	SD	Remove AC, Treat Deck, Overlay Deck with AC	15,600.00	\$ 226,523	15	\$ 200,541	\$ 4,395,987	\$ 25,982	\$ 569,547
6	Alameda	City of Oakland	33C0165		Helgenberger Road	UP Rail Track	.7 Mile North of I -880	89.2	SD	Seal Deck with Methacrylate, Patch spalls at Hinge 1 & 3, Replace jt seal at Abt1,3 & Hg 3	39,727.00	\$ 445,422	11	\$ 394,332	\$ 4,790,319	\$ 51,090	\$ 620,637
7	Alameda	City of Oakland	33C0081		Benedict Drive	San Leandro Creek	North of Lake Chabot Road	88.4	SD	Repair AC at approaches, Treat Deck with Methacrylate	7,632.00	\$ 135,035	18	\$ 119,546	\$ 4,909,866	\$ 15,489	\$ 636,125
8	Alameda	City of Oakland	33C0031		Oakport Street	Tidal Channel	Near 66th Avenue	89.7	SD	Construct metal tubing Type 2 and treat Deck with Methacrylate	5,980.00	\$ 130,000	22	\$ 115,089	\$ 5,024,955	\$ 14,911	\$ 651,036
9	Alameda	City of Oakland	33C0164		Helgenberger Road	Tidal Channel	0.3 Mile North of Coliseum Way	89.1	SD	Treat Deck with Methacrylate	6,945.00		0	\$ -		\$ -	
10	Alameda	City of Oakland	33C0045		Oakport Street	Tidal Channel	0.2 Mile North of Roland Way	87.8		Treat Deck with Methacrylate	3,800.00		0	\$ -		\$ -	
11	Alameda	City of Oakland	33C0166		Helgenberger Road (Ped. Over	Helgenberger Road	.3 Mile West of SR 185			Patch Rebars, Patch conc. Replace Expan. Jt., Seal Deck	2,898.00		0	\$ -		\$ -	
12	Alameda	City of Oakland	33C0153		Olmsted Street	Channel	Between 66th and 69th Avenue	94.0	SD	Treat Deck with Methacrylate	835.00		0	\$ -		\$ -	
13	Alameda	City of Oakland	33C0218		98th Ave	San Leandro Creek	.3 MI W of SR 17	71.2	SD	Seal bridge deck, patch soffit spalls at Bay 7, repair pile extensions	6,400.00	\$ 520,000	81	\$ 460,356	\$ 5,485,311	\$ 59,644	\$ 710,680
14	Alameda	City of Oakland	33C0148		23rd Ave	UP Rail Track	04-ALA-321-0-OAK	66.9	SD	Treat Deck, repair spalls, repair railing, eapiar raveling AC at Abutment.	34,900.00	\$ 745,000	21	\$ 659,549	\$ 6,144,859	\$ 85,452	\$ 796,132
											\$ 6,940,991						