

CITY OF GILROY BRIDGE PREVENTIVE MAINTENANCE PROGRAM

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft2)	Total Particip. Cost	Unit Cost (\$/ft2)	Federal Share	Running Fed Summary	Local Share	Running Local Share		
1		City of Gilroy	37C0271		IOOF Avenue	Miller Slough	0.1 mi. E. of Monterey St	84.5		Deck Seal (Methacrylate)	2,260	\$18,080	\$8	\$16,006	\$16,006	\$2,074	\$2,074		
2		City of Gilroy	37C0320		Lewis Street	Miller Slough	Near Forest St	66.6	SD	Deck Seal (Methacrylate)	2,400	\$19,200	\$8	\$16,998	\$33,004	\$2,202	\$4,276		
3		City of Gilroy	37C0321		Forest Street	Miller Slough	Between IOOF Av and Lewis St	67.3	SD	Deck Seal (Methacrylate)	2,630	\$21,040	\$8	\$18,627	\$51,631	\$2,413	\$6,689		
4		City of Gilroy	37C0339		Murray Avenue	W Br Llagas Cr	0.6 mi. N. of Leavesley Rd	97.6		Deck Seal (Methacrylate)	6,620	\$52,960	\$8	\$46,885	\$98,516	\$6,075	\$12,764		
5		City of Gilroy	37C0352		Farrell Avenue	W Br Llagas Cr	0.2 mi. W. of Monterey Rd	43.4	SD	Deck Seal (Methacrylate)	5,170	\$41,360	\$8	\$36,616	\$135,132	\$4,744	\$17,508		
6		City of Gilroy	37C0363		Church Street	W Br Llagas Cr	0.2 mi. N. of Ronan Ave	97.6		Deck Seal (Methacrylate)	5,280	\$42,240	\$8	\$37,395	\$172,527	\$4,845	\$22,353		
												\$194,880		\$172,527		\$22,353			
												say	\$195,000		\$172,634		\$22,366		
												CM	\$142,909	LS	\$126,517	\$299,151	\$16,392	\$38,758	
												\$337,909		\$299,151		\$38,758			