

FFY 21/22 Bridge Preventative Maintenance Program (PM00040)

Priority (Lowest Number is Top Priority)	Federal/City Project No.	Implementing Agency	Bridge No.	Year Built	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Scour Critical Bridges (113)	Work Description	Deck Area (S.F.)	Total Participating Cost (PE + Const.)	Federal Share PE (88.53%)	Local Share PE (11.47%)	Federal Share CON (88.53%)	Local Share CON (11.47%)	Comments							
1	BRLS-5008(103)/9748	City of Stockton	29C0234	1959	Center Street	Hazelton, BNSF RR, Mormon Slough	10-SJ-117-0-Stkn	91.3	SD	8	Deck Sealing / Joint Seal Repairs	54,799	\$1,615,549.00	\$101,736.00	\$13,181.00	\$1,328,509.00	\$172,123.00	Completed							
2		City of Stockton	29C0233	1959	El Dorado Street	Hazelton, BNSF RR, Mormon Slough	10-SJ-124-0-Stkn	88.8	SD	8	Deck Sealing w/ Methacrylate	54,799													
3	BPMP-5008(157)/PW1603	City of Stockton	29C0157R/L	1966	West Lane	Calaveras River	0.5 Miles North of Fulton Street	92.9	-	5	Scour Countermeasures at Bents 8, 9, 11. Methacrylate, repair AC approach. Repair sidewalk spall. Repair edge spall along expansion joint at abutments	20,656	\$2,172,161.00	\$381,574.00	\$49,437.00	\$1,575,945.00	\$165,205.00	Design/NEPA completed. CEQA IS/MND completed. Acquiring environmental permits.							
4		City of Stockton	29C0243	1959	Pershing Avenue	Calaveras River	North of Telegraph Avenue	99.7	SD	5	Deck sealing w/ Methacrylate. Seal and patch AC approach. Patch header spalls along joint at abutments	20,681													
5		City of Stockton	29C0238	1960	Diamond Street	Mormon Slough	0.1 Miles N. of Charter Way	98.1	SD	5	Deck Sealing with Methacrylate. Concrete Barrier Rail Replacement. Erosion Repairs	4,851													
6		City of Stockton	29C0240	1972	Santa Paula Wy.	Mosher Slough	North of Macduff Avenue	97	-	8	Deck sealing w/ Methacrylate. Concrete spall at metal rail near abutment 1	1,675													
7		City of Stockton	29C0235	1957	Aurora St.	Mormon Slough	0.35 Miles N. of Charter Way	95.3	-	N	Deck Sealing w/ Methacrylate and Lithium Treatment for ASR. Backfill eroded embankment. Bent 3, test for ASR and repair spalled columns	5,283													
8		City of Stockton	29C0399	1971	Turnpike Rd.	Walker Slough	0.25 Miles N. of Downing Ave.	94.7	SD	U	Deck Sealing w/ Methacrylate	4,263													
9		BPMP-5008(177)/PW1704	City of Stockton	29C0407	1997	Carolyn Weston Blvd.	French Camp Slough	0.7 Miles west of Manthey Road	49.2	SD	5	Deck Sealing w/ Methacrylate							22,528	\$1,964,494.00	\$314,330.00	\$40,725.00	\$1,424,837.00	\$184,602.00	Design complete. NEPA/CEQA completed. Need E76 for construction
10			City of Stockton	29C0189	1949	Center Street	Stockton Channel	North of Weber Street	43.0	SD	8	Deck Sealing w/ Methacrylate							10,085						
11	City of Stockton		29C0140	1962	El Dorado Street	Calaveras River	0.5 miles N. of Fulton Street	37.5	SD	8	Deck Sealing with Methacrylate/ Backfill erosion gullies at Abutment 1/ Replace Type A joint seal	17,211													
12	City of Stockton		29C0141	1962	El Dorado Street	Bianchi Road	Bianchi Road	33.9	SD	N	Deck sealing w/ Methacrylate / Replace type A joint at both abutments	6,531													
13	City of Stockton		29C0096	1976	Don Avenue	Mosher Slough	0.1 Miles S. of Waudman Avenue	76.3	SD	5	Deck Sealing w/ Methacrylate	2,279													
14	City of Stockton		29C0401	1992	Feather River	Fourteen Mile Slough	1 Mile N. of March Lane	61.8	SD	8	Deck Sealing w/ Methacrylate	14,564													
15	TBD/PW1801	City of Stockton	29C0093L/R	1968	Airport Way	Duck Creek	1 Mile N. of Industrial Drive	68.0	SD	5	Deck Sealing w/ Methacrylate	5,016	\$1,391,000.00	\$270,920.00	\$35,100.00	\$960,533.00	\$124,447.00	RFA for PE 2021/2022							
16		City of Stockton	29C0400	1971	Manthey Rd.	Walker Slough	0.25 Miles N. of Downing Ave.	66.3	SD	U	Deck sealing w/ Methacrylate	4,263													
17		City of Stockton	29C0242	1952	Pershing Avenue	Smith Canal	Just North of Harding Way	62.7	FO	5	Deck Sealing w/ Methacrylate	6,899													
18		City of Stockton	29C0237	1958	San Joaquin Street	Mormon Slough	0.1 Miles South of Hazelton Avenue	70.4	SD	5	Deck Sealing w/ Methacrylate	6,072													
19	TBD/PW1911	City of Stockton	29C0086	1966	West Lane	Mosher Creek	10-SJ-102-0-Stkn	82.8	-	5	Deck Sealing w/ Methacrylate	2,177	\$1,072,000.00	\$208,789.00	\$27,051.00	\$740,169.00	\$95,991.00	Future RFA for PE							
20		City of Stockton	29C0239	1969	El Dorado Street	Mosher Slough	0.2 Miles N. of Glencannon St.	93.1	SD	8	Deck sealing w/ Methacrylate	3,967													
21		City of Stockton	29C0188	1980	Union Street	Miner Avenue	At Miner Avenue	90.5	-	N	Deck Sealing w/ Methacrylate	4,160													
22		City of Stockton	29C0153	1937	BNSF RR, Worth Street Scotts	Santa Fe UP	0.2 Miles South of Hazelton Avenue	49.0	SD	N	Deck Sealing w/ Methacrylate	4,818													
Total													\$8,215,204.00	\$1,277,349.00	\$165,494	\$6,029,993.00	\$742,368.00								

PE= \$1,442,843
CON= \$6,772,361