

Federal Fiscal Year 2017/2018 Bridge Preventive Maintenance Program for the Town of San Anselmo - BPMP 5159(022)

PM00090

Priority (Lowest Number is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Total Particip. Cost	Unit Cost (\$/ft ²)	Federal Share	Running Fed Summary	Local Share	Running Local Share	Current Status
1	MRN	Town of San Anselmo (SLMO)	27C-0040		Sir Francis Drake Blvd.	San Anselmo Cr.	.13 mi south of intersection of SFDB and Center Blvd. in San Anselmo	66.8		1. Coldplane deck AC on NB lane 2. Repair unsound conc, apply methacrylate and overlay entire deck travel surface with polyester concrete 3. Repair cracks & spalls with epoxy grout 4. Apply methacrylate on the median surface of the deck. 5. Repair joint seals	4,000	\$406,777	\$102	\$360,120	\$360,120	\$46,657	\$46,657	PE Ongoing
2	MRN	Town of San Anselmo (SLMO)	27C-0073		Barber Ave.	San Anselmo Cr.	.04 mi east of intersection with SFDB in San Anselmo	54.3		1. Coldplane deck AC 2. Clean the deck, repair unsound conc, apply methacrylate and overlay the deck with polyester concrete 3. Repair cracks & spalls with epoxy grout 4. Repair joint seals	4,100	\$420,043	\$102	\$371,864	\$731,984	\$48,179	\$94,836	PE Ongoing
3	MRN	Town of San Anselmo (SLMO)	27C-0101		Center Blvd. (@ Lansdale Ave.)	San Anselmo Cr.	At the intersection of Center Blvd. & Lansdale Ave in San Anselmo	20	SD	1. Excavate the fill on top of the bridge 2. Clean the deck, repair unsound conc, place Fiberwrap and backfill (as alternates to items 1 & 2 above, evaluate lining inside surfaces with 6" RC layer & steel plate lining.) 3. Repair joint seals	6,000	\$523,260	\$87	\$463,242	\$1,195,226	\$60,018	\$154,854	PE Ongoing. Request for topo surveys. Will evaluate replacement after surveys.
4	MRN	Town of San Anselmo (SLMO)	27C-0100		Bridge Avenue	San Anselmo Cr.	At the intersection of Center Blvd. & Lansdale Ave in San Anselmo	49.5	SD	1. Coldplane existing deck AC 2. Clean the deck, repair unsound conc, apply methacrylate and overlay the deck with polyester concrete	5,130	\$59,950	n/a	\$53,074	\$1,248,300	\$6,876	\$161,730	Stopped PE work. 6-A submitted to replace Bridge
5	MRN	Town of San Anselmo (SLMO)	27C-0094		Saunders Avenue	San Anselmo Cr.	0.15 miles south of Sir Francis Drake Blvd and 0.15 miles north of Center Blvd in San Anselmo	52.2		1. Coldplane existing deck AC 2. Clean the deck, repair unsound conc, apply methacrylate and overlay the deck with polyester concrete 3. Repair cracks & spalls on girders and other structural members 4. Repair the failed joint seals	3,180	\$363,837	\$114	\$322,105	\$1,570,405	\$41,732	\$203,463	Add to Program for PE

Total PE + CON \$1,773,867
 Total PE dollars requested \$637,426
 Total CON dollars requested \$1,136,441