

**CITY OF CHICO BRIDGE PREVENTATIVE MAINTENANCE PLAN (BPMP)
FEDERAL FISCAL YEAR 2023/2024**

Priority	Agency Location	Bridge Number	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft ²)	Unit Cost (\$/SF Deck)	Federal Share (80%)	Local Share (11.47%)	Total Particip. Cost
1	CHICO	12C0277	VALLOMBROSA AVE	BIG CHICO CREEK	BTW 1ST ST AND MEMORIAL WAY	58.9		RSP, Scour Mitigation	3108.62	\$46	\$ 114,721.68	\$ 16,448.22	\$ 143,402.10
2	CHICO	12C0201	PARK AVE	LITTLE CHICO CREEK	0.1 MI N OF 11TH ST	55.0		RSP, Scour Mitigation	4091.36	\$28	\$ 90,864.95	\$ 13,027.76	\$ 113,581.19
3	CHICO	12C0299	BRUCE RD	S FORK DEAD HORSE SLOUGH	JUST N OF SR 32	85.2		RSP, Scour Mitigation	3148.44	\$27	\$ 67,339.71	\$ 9,654.83	\$ 84,174.64
4	CHICO	12C0274	E 5TH AVE (CHICO)	LINDO CHANNEL	AT E. LINDO AVENUE	89.8		RSP, Scour Mitigation Methacrylate Deck	5121.47	\$31	\$ 126,419.85	\$ 18,125.45	\$ 158,024.81
5	CHICO	12C0205	MAIN STREET	BIG CHICO CREEK	0.15 MI N 2ND ST	65.0		Joint Seal	3348.65	\$11	\$ 29,044.11	\$ 4,164.20	\$ 36,305.14
6	CHICO	12C0273	MANGROVE AVE	LINDO CHANNEL	BTWN E 10TH & COHASSET	77.7		Spall Repair Joint Seal Methacrylate Deck	8650.96	\$19	\$ 130,281.61	\$ 18,679.13	\$ 162,852.01
7	CHICO	12C0363	WALNUT ST	LITTLE CHICO CREEK	BTWN DAYTON RD & 9TH ST	97.0		RSP, Scour Mitigation Methacrylate Deck	3020.35	\$43	\$ 104,442.42	\$ 14,974.43	\$ 130,553.03
8	CHICO	12C0056	MIDWAY ROAD	COMANCHE CREEK	0.1 MI S PARK AVE	58.3		Methacrylate Deck Spall Repair	4546.68	\$14	\$ 50,357.86	\$ 7,220.06	\$ 62,947.33
9	CHICO	12C0064	LONGFELLOW AVE	LINDO CHANNEL	BTWN E 1ST ST & MANZANITA	76.2	FO	Methacrylate Deck	5289.39	\$13	\$ 55,335.35	\$ 7,933.71	\$ 69,169.19
10	CHICO	12C0216R	SKYWAY AVENUE	LITTLE CHICO-BUTTE CR DV CH	0.4 MI NW HUMBUG ROAD	71.0		Methacrylate Deck	4257.13	\$13	\$ 44,524.66	\$ 6,383.72	\$ 55,655.83
11	CHICO	12C0298	FOREST AVE	LITTLE CHICO CREEK	JUST S OF HUMBOLDT RD	94.0		Methacrylate Deck	5877.10	\$13	\$ 61,474.27	\$ 8,813.87	\$ 76,842.83
12	CHICO	12C0275	MANZANITA AVE	LINDO CHANNEL	BTW EAST AVE & HOOKER OAK	83.0		Methacrylate Deck	6170.95	\$13	\$ 64,547.62	\$ 9,254.51	\$ 80,684.52
13	CHICO	12C0338	MILL ST	LITTLE CHICO CREEK	0.1 MI N OF 12TH ST	49.3		Methacrylate Deck	1414.38	\$13	\$ 14,795.23	\$ 2,121.27	\$ 18,494.03
14	CHICO	12C0212	MANZANITA AVE	BIG CHICO CREEK	BTW VALLOMBROSA&CENTENNAL	84.8		Methacrylate Deck	4038.62	\$13	\$ 42,238.34	\$ 6,055.92	\$ 52,797.92
15	CHICO	12C0337	BROADWAY ST	LITTLE CHICO CREEK	JUST S OF 9TH ST	71.5		AC Deck Removal Methacrylate Deck Wingwall and Backwall Repair	1695.32	\$151	\$ 204,598.06	\$ 29,334.25	\$ 255,747.58
16	CHICO	12C0280	PINE ST	LITTLE CHICO CREEK	BTW HUMBOLDT AV & 12TH ST	79.3		Methacrylate Deck	2350.84	\$13	\$ 24,592.79	\$ 3,525.99	\$ 30,740.99
17	CHICO	12C0335	CHESTNUT ST	LITTLE CHICO CREEK	AT W 9TH ST	97.8		Methacrylate Deck	3151.67	\$13	\$ 32,968.84	\$ 4,726.91	\$ 41,211.05

Revised August 2023

PE: 25%
CON: 15%

Grand Total = \$ 1,258,547 \$ 180,444 \$ 1,573,184