Marin County - Dept. of Public Works

Federal Fiscal Year 2023/2024 Bridge Preventive Maintenance Program

Priority (Lowest Number Is Top Priority)	Agency Location	from Inspection Report	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft^2)	Unit Cost ($/$ft^2$)	Federal Share	Local Share	Total Particip. Cost
1	Marin	27C0018	Sir Francis Drake	Lagunitas Creek	1.9 miles East SR 1 at Olema	85.3	SD	Polyester Concrete Overlay	8540.00	42.30	288,994	72,248	361,242
2	Marin	27C0109	Marshal-Petaluma Road	San Antonio Creek	0.27 miles East Chileno Valley Rd	75.7		Patch soffit spalls and deck repairs	671.00	19.70	10,575	2,644	13,219
3	Marin	27C0113	Marshal-Petaluma Road	Salmon Creek	6 miles East of SR 1	93.2		Replace Joint Seals	5018.00	9.40	37,735	9,434	47,169
4	Marin	27C0116	Olema-Bolinas Road	Pine Gulch Creek	1.3 miles South of SR 1	74.0		Methacrylate Deck Treatment	1488.00	49.40	58,806	14,701	73,507
5	Marin	27C0128	Flamingo Road	Coyote Creek	0.17 miles North Marine Ave	87.8		Methacrylate Deck Treatment	3002.00	37.20	89,340	22,335	111,674
6	Marin	27C0132	Mount Shasta Drive	Miller Creek	0.08 miles North Lucas Valley Rd Intersection	95.0		Methcrylate Deck Treament	4544.00	33.10	120,325	30,081	150,406
7	Marin	27C0133	Mt McKinley Road	Miller Creek	Lucas Valley Rd Intersectino	94.4		Methcrylate Deck Treament	3057.00	33.10	80,949	20,237	101,187
8	Marin	27C0155	Bridgegate Drive	Miller Creek	0.1 miles North Lucas Valley Road	88.3		Replace Joint Seals	2908.00	17.30	40,247	10,062	50,308
9	Marin	27C0157	Sir Francis Drake	White's Hill Bridge	0.6 miles North Baywood Canyon Road	86.7		Methcrylate Deck Treament incl. approach slabs	17613.00	26.80	377,623	94,406	472,028
										Grand Total =	**$ 1,104,593**	**$ 276,148**	**$ 1,380,741**