\$477,690

Page 1 of 1

City of Petaluma

Federal Fiscal Year 2023/2024 Bridge Preventive Maintenance Program

	Agency Location			Feature Intersected	Location	Sufficiency SD/FO Rating Status		Deck Area (ft²)		Construction Cost	Contingency (25%)	PE (25%)	CE (15%)	Total Particip. Cost	Federal Share (80%)	Local Share (20%)
1	Petaluma, City of	20C0003	Santori Drive	Adobe Creek	0.2 Mi SE of Casa Grande Ave.	67.8 SD	Methacrylate Deck	2,806	\$57.75	\$98,213	\$24,553	\$24,553	\$14,732	\$162,051	\$129,641	\$32,410
2	Petaluma, City of	20C0045	Washington Street	Petaluma River	Near Downtown Petaluma	92.9 SD	Place 1" Polyester Overlay - Clean & repaint fiberglass column shells	9,334	\$75.47	\$426,916	\$106,729	\$106,729	\$64,037	\$704,412	\$563,530	\$140,882
3	Petaluma, City of	20C0056R	Petaluma Blvd. S	Petaluma River	0.2 Mi S JCT US 101	45.1	Methacrylate Deck	4,175	\$57.75	\$146,110	\$36,528	\$36,528	\$21,917	\$241,082	\$192,865	\$48,216
4	Petaluma, City of	20C0516	Old Rewood Hwy	Willow Brook Creek	0.5 Mi N/O US 101	73.9 SD	Methacrylate Deck & Approach Slabs	14,077	\$74.25	\$633,451	\$158,363	\$158,363	\$95,018	\$1,045,195	\$836,156	\$209,039
5	Petaluma, City of	20C0563	Holly Lane	Washington Creek	W of Madison Street	85.2	Methacrylate Deck	2,842	\$57.75	\$99,456	\$24,864	\$24,864	\$14,918	\$164,103	\$131,282	\$32,821
6	Petaluma, City of	20C0564	Madison Street	Washington Creek	North of Holly Lane	89.5	Methacrylate Deck	1,240	\$57.75	\$43,399	\$10,850	\$10,850	\$6,510	\$71,608	\$57,287	\$14,322

Grand Total = \$ 2,388,451 \$ 1,910,761 \$ 477,690

Subtotal =

\$2,388,451

\$1,910,761