

Priority (Lowest Number Is Top Priority)	County Location	Implementing Agency	Bridge number from Inspection Report	Local Agency Bridge ID	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD Status	Work Description	Deck Area (ft ²)	Total Particip. Cost	Unit Cost (\$/ft ²)	Federal Share	Running Fed Summary	Local Share	Non Particip. Local Cost	Running Local Share
1	Santa Clara	City of Morgan Hill	37C0432	N/A	Butterfield Blvd	Railroad Avenue	S. of Tennant Ave	96.5	SD	Chip out and patch any unsound deck concrete. Blast clean deck surface. Place a minimum of 1" thick polyester concrete overlay on the deck and approach slabs. Remove the failed pourable joint seals and install compression joint seals at both abutments in conjunction with the polyester concrete overlay work.	19,092	\$1,058,637	\$55.45	\$846,909	\$846,909	\$211,727	\$0	\$211,727
2	Santa Clara	City of Morgan Hill	37C0438	N/A	Monterey Rd	Little Llagas Creek	JEO Watsonville Rd	92.8		Replace missing invert pavement in both barrels under the SB lanes of Monterey Rd.	4,180	\$339,743	\$81.28	\$271,794	\$1,118,704	\$67,949	\$0	\$279,676
Total:											\$23,272	\$1,398,380		\$1,118,704		\$279,676	\$0	
														(State)		(Local)		

Notes: Total Participating Cost includes:
 PE - Preliminary Engineering including City Management
 CON - Estimated Construction including 10% Mob, 25% Cont, Construction Engineering.