

Priority (Lowest Number Is Top Priority)	Agency Location	Bridge Number from Inspection Report	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft²)	Unit Cost (\$/ft²)	Federal Share	Local Share	PE Costs	Construction Costs	Total Particip. Cost	Final HBP Comments
1	Tulare County	46C0039	AVE 56	FRIANT-KERN CANAL	0.45 MI WEST OF ROAD 192	79.4	FO	1. Clean the debris out of the joint and install a joint seal	3,513	28	78,400	19,600	24,500	73,500	\$ 98,000	
2	Tulare County	46C0180	ROAD 216	FRIANT-KERN CANAL	0.2 MI NORTH OF AVE 264	91.4		1. Remove AC and dirt from the expansion joint over Pier 2 and replace the Joint seal	2,537	30	60,000	15,000	18,750	56,250	\$ 75,000	
3	Tulare County	46C0236	AVE 328	FRIANT-KERN CANAL	0.3 MI WEST OF SR 245	56.2		1. Remove the AC from Spans 1 and 4 and treat the deck with methacrylate 2. Clean out the joints and place new joint seals	3,984	43	136,000	34,000	42,500	127,500	\$ 170,000	
4	Tulare County	46C0237	AVE 322	FRIANT-KERN CANAL	0.1 MI WEST OF SR 245	70.5		1. Clean out the joint and replace the seal	2,282	33	60,000	15,000	18,750	56,250	\$ 75,000	
5	Tulare County	46C0240	AVE 282 (WIRHT)	FRIANT-KERN CANAL	0.2 MI EAST OF ROAD 206	62.2		1. Remove AC and dirt from the expansion joint over Pier 2. Replace joint seal.	1,962	38	60,000	15,000	18,750	56,250	\$ 75,000	
6	Tulare County	46C0241	AVE 280	FRIANT-KERN CANAL	0.3 MI EAST OF ROAD 204	54.6		1. Clean out the joint opening and place a suitable joint seal.	2,481	30	60,000	15,000	18,750	56,250	\$ 75,000	
7	Tulare County	46C0244	AVE 248	FRIANT-KERN CANAL	0.1 MI EAST OF ROAD 224	51.0		1. Clean out the joint and replace with a suitable joint seal 2. Remove residual AC and treat the deck with methacrylate	1,874	57	84,800	21,200	26,500	79,500	\$ 106,000	
8	Tulare County	46C0247	AVE 228	FRIANT-KERN CANAL	0.35 MI EAST OF ROAD 228	56.7		1. Clean out the joint and place a suitable joint seal	2,537	30	60,000	15,000	18,750	56,250	\$ 75,000	
9	Tulare County	46C0250	AVE 220 (WADDELL)	FRIANT-KERN CANAL	0.25 MI EAST OF ROAD 228	58.1		1. Clean out the joint and place pourable joint seal	2,370	32	60,000	15,000	18,750	56,250	\$ 75,000	
10	Tulare County	46C0251	AVE 216 (CITRUS)	FRIANT-KERN CANAL	0.25 MI EAST OF ROAD 228	51.2		1. Remove the fiber board from the joint opening and place a pourable joint seal 2. Place a 1 inch layer of polyester concrete overlay on the entire deck surface.	2,370	84	160,000	40,000	50,000	150,000	\$ 200,000	
11	Tulare County	46C0253	AVE 208 (5TH AVE)	FRIANT-KERN CANAL	0.25 MI WEST OF ROAD 232	57.7		1. Remove residual AC and treat the deck with methacrylate 2. Replace joint seal at Pier 2	2,370	52	98,400	24,600	30,750	92,250	\$ 123,000	
12	Tulare County	46C0254	AVE 204 (6TH AVE)	FRIANT-KERN CANAL	0.25 MI EAST OF ROAD 228	60.2		1. Clean the expansion joint and install a seal	2,370	32	60,000	15,000	18,750	56,250	\$ 75,000	
13	Tulare County	46C0255	AVE 200 (7TH AVE)	FRIANT-KERN CANAL	0.25 MI WEST OF ROAD 232	60.4		1. Clean debris from joint and install new joint seal.	2,564.63	29	60,000	15,000	18,750	56,250	\$ 75,000	
14	Tulare County	46C0257	AVE 194 (8TH AVE)	FRIANT-KERN CANAL	AT ROAD 234	55.3		1. Install a proper joint seal at Pier 2 2. Treat the deck surface with methacrylate.	2851.631	46	104,800	26,200	32,750	98,250	\$ 131,000	
15	Tulare County	46C0259	AVE 188 (OLIVE)	FRIANT-KERN CANAL	0.1 MI WEST OF ROAD 232	53.6		1. Clean out the open joint at Pier 2 and insall a joint seal	2,370.20	32	60,000	15,000	18,750	56,250	\$ 75,000	
16	Tulare County	46C0260	AVE 184	FRIANT-KERN CANAL	AT DRIVE 232/NEWCOMB ST	58.4		1. Clean out the joint and install a joint seal	2,370.20	32	60,000	15,000	18,750	56,250	\$ 75,000	
17	Tulare County	46C0264	AVE 170 (N GRAND)	FRIANT-KERN CANAL	0.25 MI EAST OF ROAD 224	49.9		1. Clean the AC out of the joint at Pier 2 and install a new seal	3,024.38	25	60,000	15,000	18,750	56,250	\$ 75,000	
18	Tulare County	46C0322	AVE 8	FRIANT-KERN CANAL	AT ROAD 176	73.3		1. Clean joint and install suitable joint seal	2,260.21	33	60,000	15,000	18,750	56,250	\$ 75,000	
19	Tulare County	46C0323	AVE 16	FRIANT-KERN CANAL	0.5 MI WEST OF ROAD 184	79.7		1. Clean out the expansion joint at Pier 2 and install a suitable joint seal	2,260.21	33	60,000	15,000	18,750	56,250	\$ 75,000	
20	Tulare County	46C0324	AVE 24	FRIANT-KERN CANAL	0.05 MI WEST OF ROAD 184	67.8		1. Clean out the expansion joint at Pier 2 and install a suitable joint seal	2,260.21	33	60,000	15,000	18,750	56,250	\$ 75,000	
21	Tulare County	46C0363	ROAD 184	FRIANT-KERN CANAL	0.1 MI SOUTH OF AVENUE 40	58.1		1. Clean out the joint at Pier 2 and install a suitable joint seal	3,349.03	22	60,000	15,000	18,750	56,250	\$ 75,000	
22	Tulare County	46C0364	AVE 40	FRIANT-KERN CANAL	0.05 MI EAST OF ROAD 184	74.9		1. Clean out the joint and install a new seal	2,287.54	33	60,000	15,000	18,750	56,250	\$ 75,000	
23	Tulare County	46C0365	AVE 48	FRIANT-KERN CANAL	0.1 MI EAST OF ROAD 184	73.9		1. Clean out the joint and install a suitable joint seal at Pier 2 2. Remove the existing AC overlay and treat the deck with methacrylate.	2,369.81	55	104,800	26,200	32,750	98,250	\$ 131,000	
Grand Total =											\$ 1,727,200	\$ 431,800	\$ 539,750	\$ 1,619,250	\$ 2,159,000	