

City of Livermore 2022 BPMP Plan													
Priority (Lowest Number is Top Priority)	Agency Location	Bridge Number from Inspection Report	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft2)	Unit Cost (\$/ft2)	Federal Share	Local Share	Total Particip. Cost
1	ALA	33C0070	Stanley Blvd	Arroyo Mocho	0.1 MI West of Murrieta Blvd	86.1	Not SD	1-Remove the Eucalyptus tree & root system rotating N.W. Wingwall	11284	\$ 5	\$ 48,000	\$ 12,000	\$ 60,000
2	ALA	33C0129	South Vasco Road	Arroyo Seco	0.1 MI North of East Avenue	64.9	Not SD	1-Remove asphalt crack sealant, apply methacrylate sealant, restripe bridge deck 2-Repair settled AC approaches by removing AC, and installing new AB and AC.(non-participating cost)	2340	\$ 21	\$ 40,000	\$ 10,000	\$ 50,000
3	ALA	33C0414	Laughlin Road	Altamont Creek	0.1 KM North of Foxtail Drive	95.5	Not SD	1-Apply methacrylate sealant, restripe bridge deck	1629	\$ 25	\$ 32,000	\$ 8,000	\$ 40,000
4	ALA	33C0425	First Street	Union Pacific Railroad	150' South of Scott Street	94	Not SD	1-Apply methacrylate sealant, restripe bridge deck 2-Add joint in center median at BB/EB	15077	\$ 16	\$ 192,000	\$ 48,000	\$ 240,000
5	ALA	33C0395	West Jack London Blvd.	Arroyo Las Positas	0.5 MI East of El Charro Road	89.9	Not SD	1-Apply methacrylate sealant, restripe bridge deck 2-Replace joint seals 3-Paint bridge indentification	4432	\$ 25	\$ 88,000	\$ 22,000	\$ 110,000
6	ALA	33C0195	Arroyo Road	Arroyo Mocho	0.2 MI South of College Avenue	96	Not SD	1-Remove asphalt crack sealant, apply methacrylate sealant, restripe bridge deck 2-Replace joint seals	9898	\$ 9	\$ 72,000	\$ 18,000	\$ 90,000
7	ALA	33C0426	Holmes Street	Arroyo Mocho	500' North of Mocho Street	83	Not SD	1-Remove AC, methacrylate deck, place polyester concrete overlay, feather approach rdwy AC (max. 50' from EB/BB) and restripe 2-Repaint bridge information 3-Seal concrete cracks in Abut with epoxy (non-participating cost)	8221	\$ 67	\$ 440,000	\$ 110,000	\$ 550,000
8	ALA	33C0397	Springtown Blvd	Altamont Creek	1 MI N of I-580	86.1	Not SD	1-Provide cathodic protection for corrosion observed on steel arch near the waterline.	8553	\$ 16	\$ 112,000	\$ 28,000	\$ 140,000
9	ALA	33C0385	South Vasco Road	Union Pacific Railroad	0.9 MI South of I-580	85.9	SD	1-Apply methacrylate sealant, restripe bridge deck 2-Replace joint seals/headers	18811	\$ 13	\$ 200,000	\$ 50,000	\$ 250,000
10	ALA	33C0192	Bluebell Road	Altamont Creek	1.3 MI North of I-580	77.7	Not SD	1-Remove AC, methacrylate deck, place polyester concrete overlay, feather approach rdwy AC (max. 50' from EB/BB) and restripe 2-Paint timber railings (non-participating cost) 3-Repair large concrete spalls on soffits, replace corroded reinf. Steel	2546	\$ 185	\$ 376,000	\$ 94,000	\$ 470,000
11	ALA	33C0194	Charlotte Way	Arroyo Seco	0.3 MI North of East Avenue	84.6	Not SD	1-Apply methacrylate sealant, restripe bridge deck	2687	\$ 11	\$ 24,000	\$ 6,000	\$ 30,000
12	ALA	33C0382	Las Positas Road	Arroyo Seco	0.3 MI East of First Street	95.8	Not SD	1-Remove AC & AB, excavate 3' fill, methacrylate slab, backfill with excavated fill material, place AB and AC, feather approach rdwy AC (max. 50' from EB/BB) and restripe	3947	\$ 149	\$ 472,000	\$ 118,000	\$ 590,000
13	ALA	33C0416	North Mines Road	Union Pacific Railroad	0.5 KM South of State RTE 8	98.8	Not SD	1-Apply methacrylate sealant, restripe bridge deck	19747	\$ 11	\$ 176,000	\$ 44,000	\$ 220,000
14	ALA	33C0424	First Street	Arroyo Seco	600' NW Las Positas Road	95.2	Not SD	1-Remove AC & AB, excavate 1' fill, methacrylate slab, backfill with excavated fill material, place AB and AC, feather approach rdwy AC (max. 50' from EB/BB) and restripe	8893	\$ 92	\$ 656,000	\$ 164,000	\$ 820,000
15	ALA	33C0383	Arroyo Vista Road	Arroyo Seco	500' West of Las Positas Road	96.9	Not SD	1-Remove AC & AB, excavate 1' fill, methacrylate slab, backfill with excavated fill material, place AB and AC, feather approach rdwy AC (max. 50' from EB/BB) and restripe	3782	\$ 95	\$ 288,000	\$ 72,000	\$ 360,000
16	ALA	33C0381	Patterson Pass Road	Arroyo Seco	500' East of Mulqueeny Street	96.5	Not SD	1-Remove AC & AB, excavate 2' fill, methacrylate slab, backfill with excavated fill material, place AB and AC, feather approach rdwy AC (max. 50' from EB/BB) and restripe	3663	\$ 131	\$ 384,000	\$ 96,000	\$ 480,000
17	ALA	33C0380	Charlotte Way	Arroyo Seco	300' West of Lucille Street	96.5	Not SD	1-Remove AC & AB, excavate 2' fill, methacrylate slab, backfill with excavated fill material, place AB and AC, feather approach rdwy AC (max. 50' from EB/BB) and restripe	1792	\$ 162	\$ 232,000	\$ 58,000	\$ 290,000
18	ALA	33C0379	Lucille Street	Arroyo Seco	200' S Charlotte Way	89.4	Not SD	1-Remove AC, methacrylate deck, place polyester concrete overlay, feather approach rdwy AC (max. 50' from EB/BB) and restripe	1332	\$ 128	\$ 136,000	\$ 34,000	\$ 170,000