

Priority (Lowest Number Is Top Priority)	Agency Location	Bridge Number from Inspection Report	Facility Carried	Feature Intersected	Location	Sufficiency Rating	SD/FO Status	Work Description	Deck Area (ft2)	Unit Cost (\$/ft2)	Federal Share	Local Share	Total Particip. Cost
1	City of Palm Desert	56C-0467	Monterey Ave	Whitewater River	0.9 mi N/o Fred Waring Dr	86.5		• Treat Bridge Deck with Methacrylate. This will require AC removal. Repair Soffit Cracks • Replace compresion joint seal. • Remove and Repair Unsound Concrete at Expansion Joints.	36,007.54	12	349,085	87,271	436,356
2	City of Palm Desert	56C-0502	Palm Canyon Drive	Rancho Mirage Channel	4.5 mi SE/o Date Palm Dr	94.6		• Place Polyester Concrete Overlay. This will require AC removal. • Repair Cracks on pile extensions.	5,843.73	59	275,209	68,802	344,011
3	City of Palm Desert	56C-0550	Magnesia Falls Dr	San Pascual Channel	0.7 mi E/o Monterey Ave	95.4		• Treat Bridge Deck with Methacrylate. This will require AC removal. • Replace compresion joint seal.	5,456.66	47	204,360	51,090	255,450
4	City of Palm Desert	56C-0549	Portola Avenue	Whitewater River	0.7 mi N/o Fred Waring Dr.	94.0		• Treat Bridge Deck with Methacrylate. This will require AC removal. • Replace compresion joint seal. • Remove and Repair Unsound Concrete at Expansion Joints.	46,740.34	19	717,791	179,448	897,239
6	City of Palm Desert	56C-0326	Tierra Del Oro	Palm Valley Stormwater Channel	200' W/o Edgehill Drive	80.0		• Treat Bridge Deck with Methacrylate; Remove Unsound Concrete, Replace Compresion Joint Seal, and RSC patch at bridge ends; Remove Unsound Concrete at SW wingwall.	2,590.23	20	42,410	10,603	53,013
Grand Total = \$ 1,588,855 \$ 397,214 \$ 1,986,069													