DRISI

Caltrans Division of Research, Innovation and System Information

Research Notes

Geotechnical/ Structure

Liquefaction-Induced Ground Settlement Procedure

Bridge research to improve guidelines in the evaluation of post-earthquake liquefaction effects to bridge structures for an enhanced seismic performance transportation network.

AUGUST 2021

Project Title:
Liquefaction-Induced Ground Settlement Procedure

Task Number: 3985

Start Date: October 1, 2021

Completion Date: September 30, 2022

Task Manager:
Sharon Yen
Senior Transportation Engineer
sharon.yen@dot.ca.gov

WHAT IS THE NEED?

Practicing engineers require robust procedures to estimate post-liquefaction volumetric settlement, which is a key component of liquefaction effects on bridges, roads, and ports in the State of California. Research on the effects of the recent earthquakes in New Zealand provides a unique opportunity to obtain a comprehensive understanding of how sites with different subsurface conditions perform in major earthquakes with various levels of liquefaction. There is not enough detail information about ground performance to the degree of earthquake that exists in Christchurch and Wellington, New Zealand. The study takes advantage of this opportunity to advance the understanding and practice in liquefaction engineering, to produce a better procedure to estimate liquefaction effects on bridge foundations.

WHAT ARE WE DOING?

The proposed research plan will: (1) examine well-documented case histories of ground performance for three soil conditions at the Port of Wellington: gravel fill, sand fill, and silty soil; (2) characterize the ground conditions and liquefaction-induced volumetric settlement at 13 free-field sites at the port; and (3) combine the Wellington data with other case history data to develop a probabilistic method for estimating volumetric reconsolidation ground settlement, which assesses uncertainty.

Caltrans

DRISI provides solutions and knowledge that improves California's transportation system

ADA Notice: Users with accessibility issues may contact the California Department of Transportation, Division of Research, Innovation and System Information, MS-83 : (916) 654-8899, TTY 711, or Caltrans, DRISI – MS-83, P.O. Box 942873, Sacramento, CA 94273-0001

The study will identify the strengths and limitations of current procedures for evaluating liquefaction-induced volumetric reconsolidation ground settlement, and it will employ the excellent case histories of ground performance at the port to discern the reasons for the different levels of observed ground settlement. The primary focus of the proposed project is to develop a new method for estimating 1D post-liquefaction settlement.

WHAT IS OUR GOAL?

The primary objective of the proposed research project is to develop a new probabilistic method for estimating post-liquefaction volumetric settlement capitalizing on recent data from New Zealand. The project will incorporate liquefaction-induced settlement data from several earthquakes (e.g., 2013 & 2016 Wellington earthquakes and 2010-2011 Christchurch earthquakes) to broaden the existing database from older earthquakes (e.g., 1989 Loma Prieta earthquake) to make the new probabilistic method robust. Investigating liquefaction effects, such as ground settlement, provide invaluable information that will serve as benchmarks to our understanding of soil liquefaction characteristics. Insights from the study can improve current empirical liquefaction effects assessment procedures.

WHAT IS THE BENEFIT?

Simplified liquefaction triggering procedures and post-liquefaction settlement procedures provide useful insights, but they cannot explain the different levels of ground and facilities damage during three major New Zealand earthquakes affecting the Port of Wellington (Mw6.5 2013 Cook Strait, Mw6.6 2013 Lake Grassmere, and Mw7.8 2016 Kaikoura events). This sequence of earthquakes, each event with its different effects on the major port facilities in Wellington, warrants further study.

Performance-based earthquake engineering (PBEE) requires analytical tools that can discern varying levels of seismic performance. These well-recorded earthquakes, the comprehensive subsurface investigations already performed, and the well-documented performance of the ground at the port provide an exceptional opportunity to evaluate the capabilities of current procedures and to support development of an improved procedure for evaluating ground performance at sites involving liquefaction by combining the Wellington data with those from other important earthquakes, such as those in the 2010-2011 Canterbury earthquake sequence.

The newly available case histories of ground performance, including those in Wellington and Christchurch, provide an unparalleled opportunity to develop robust probabilistic-based simplified procedures that can capture the different ground settlements measured at the port during these events.

This research project will provide a new probabilistic 1D post-liquefaction volumetric settlement procedure for use by Caltrans engineers and consultants. Learning from observations after design level earthquakes is invaluable to advancing understanding in earthquake engineering.

WHAT IS THE PROGRESS TO DATE?

This project is being initiated as a task order through the Caltrans PEER-Bridge Program. It is targeted to being on October 01, 2021 and continue for 12 months.

The contents of this document reflect the views of the authors, who are responsible for the facts and accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the California Department of Transportation, the State of California, or the Federal Highway Administration. This document does not constitute a standard, specification, or regulation. No part of this publication should be construed as an endorsement for a commercial product, manufacturer, contractor, or consultant. Any trade names or photos of commercial products appearing in this document are for clarity only.

© Copyright 2021 California Department of Transportation
ALL RIGHTS RESERVED