

Pavement

MAY 2026

Project Title: Partnered Pavement Research Center (PPRC) 23: Performance Related Specifications

Task Number: 4394

Start Date: November 27, 2023

Completion Date: June 30, 2026

Task Manager:

Jamieson Scott
Associate Environmental Planner
jamieson.scott@dot.ca.gov

DRISI Division Chief:

Prakash Sah, PE
Prakash.Sah@dot.ca.gov

Towards Implementation of Recycled Fibers from Novel and Existing Source Materials in Concrete

Identifying and evaluating recycled fiber materials for concrete pavements.

WHAT IS THE NEED?

Fiber-Reinforced Concrete (FRC) can extend pavement service life and reduce the need for crack and joint repairs. However, specifications for FRC remain limited, and recycled fibers – often matching or surpassing virgin fibers in performance – all still underused. California needs validated design parameters, supply-chain strategies, and life-cycle cost and environmental data to integrate recycled fibers into concrete paving practices.

WHAT ARE WE DOING?

Phase II of this task builds on initial work (2022–2023) and focuses on:

- Source material sampling, characterization, and fiber production to identify viable recycled fiber feedstocks in California.
- Optimization of fiber size and load through trial batching, industry collaboration, and performance testing.
- Durability evaluation using freeze-thaw and other standardized tests on selected recycled Fiber-Reinforced Concrete (rFRC).
- Documenting Phase II research findings and refine associated guidelines based on results.
- Test track construction and testing with Heavy Vehicle Simulator loading to assess fiber contributions to fatigue life and joint load transfer.
- Mechanistic-empirical modeling to incorporate fiber benefits into PavementME design frameworks.



DRISI provides solutions and knowledge that improves California's transportation system.

- Final research report and implementation proposal for inclusion in Caltrans' Rigid Design Catalog.

WHAT IS OUR GOAL?

The main goal of this task is to validate recycled fibers as effective FRC additives, quantify their environmental and economic benefits, and develop design guidelines and specification language for the California Department of Transportation (Caltrans) to adopt rFRC in concrete pavements.

WHAT IS THE BENEFIT?

Implementing recycled fibers will enhance pavement resilience, reduce reliance on virgin materials, and lower life-cycle costs and carbon emissions. Caltrans gains sustainable infrastructure solutions, cost savings, and leadership in innovative concrete practices.

WHAT IS THE PROGRESS TO DATE?

- Reviewed collected fiber samples and met with suppliers to obtain additional fibers.
- Developed a fiber-reinforced concrete batching and testing plan, completed fiber size and load selection through trial batches and meetings with industry, and finalizing the technical report for submittal to Caltrans.
- Completed freeze-thaw testing.
- Submitted Phase 2 report, which was approved by Caltrans. Met with the Technical Advisory Panel and approved initiation of Phase 3. Report is undergoing editorial review.
- Worked on test factorial and fiber sampling.
- Repaired and calibrated the MTS load frame in preparation for fatigue testing of FRC.
- Updated the Scope of Work.
- Completed a literature review of existing pavement design procedures with FRC.

The contents of this document reflect the views of the authors, who are responsible for the facts and accuracy of the data presented herein. The contents do not necessarily reflect the official views or policies of the California Department of Transportation, the State of California, or the Federal Highway Administration. This document does not constitute a standard, specification, or regulation. No part of this publication should be construed as an endorsement for a commercial product, manufacturer, contractor, or consultant. Any trade names or photos of commercial products appearing in this document are for clarity only.