

CHAPTER 3B. PAVEMENT AND CURB MARKINGS

Section 3B.01 Yellow Center Line Pavement Markings

Standard:

- 01 **Center line pavement markings, when used, shall be the pavement markings used to delineate the separation of traffic lanes that have opposite directions of travel on a roadway and shall be yellow.**

Option:

- 02 Center line pavement markings may be placed at a location that is not the geometric center of the roadway.
- 03 On roadways without continuous center line pavement markings, short sections may be marked with center line pavement markings to control the position of traffic at specific locations, such as around curves, over hills, on approaches to grade crossings, at grade crossings, and at bridges.

Standard:

- 04 **The center line markings on two-lane, two-way roadways shall be one of the following as shown in Figure 3B-1:**

- A. **Two-direction passing zone markings consisting of a normal width broken yellow line where crossing the center line markings for passing with care is permitted for traffic traveling in either direction;**
- B. **One-direction no-passing zone markings consisting of a double yellow line, one of which is a normal width broken yellow line and the other is a normal width solid yellow line, where crossing the center line markings for passing with care is permitted for the traffic traveling adjacent to the broken line, but is prohibited for traffic traveling adjacent to the solid line; or**
- C. **Two-direction no-passing zone markings consisting of two normal width solid yellow lines where crossing the center line markings for passing is prohibited for traffic traveling in either direction.**

- 05 **A single solid yellow line shall not be used as a center line marking on a two-way roadway.**

- 06 **Except where a reversible lane (see Section 3B.04) or a two-way left-turn lane (see Section 3B.05) is present, the center line markings on undivided two-way roadways with four or more lanes for moving motor vehicle traffic always available shall be the two-direction no-passing zone markings consisting of normal width double solid yellow lines as shown in Figure 3B-2.**

Guidance:

- 07 *Section 3B.11 contains information for application of pavement markings through intersections or interchanges.*
- 08 *On two-way roadways with three through lanes for moving motor vehicle traffic, two lanes should be designated for traffic in one direction by using one-direction or two-direction no-passing zone markings as shown in Figure 3B-3.*

Support:

- 09 [Refer to FHWA's List of Known Errors for error in labeling Paragraph 7. Refer to Section 1A.04 for more details.](#)

Section 3B.02 Warrants for Yellow Center Lines

Standard:

- 01 **Center line markings shall be placed on all paved undivided two-way urban arterials and collectors that have a traveled way of 20 feet or more in width and an ADT of 6,000 vehicles per day or greater. Center line markings shall also be placed on all paved undivided two-way streets or highways that have three or more lanes for moving motor vehicle traffic.**

Guidance:

- 02 *Center line markings should be placed on paved urban arterials and collectors that have a traveled way of 20 feet or more in width and an ADT of 4,000 vehicles per day or greater. Center line markings should also be placed on all rural arterials and collectors that have a traveled way of 18 feet or more in width and an ADT of 3,000 vehicles per day or greater. Center line markings should also be placed on other traveled ways where an engineering study indicates such a need.*
- 03 *Engineering judgment should be used in determining whether to place center line markings on traveled ways that are less than 16 feet wide because of the potential for traffic encroaching on the pavement edges, traffic being affected by parked vehicles, and traffic encroaching into the opposing traffic lane.*

Option:

- 04 Center line markings may be placed on other paved two-way traveled ways that are 16 feet or more in width.

05 If a traffic count is not available, the ADTs described in this Section may be estimates that are based on engineering judgment.

Standard:

06 **Centerline patterns shall be selected from those shown in Figures 3A-101(CA) and 3A-104(CA).**

07 **Raised retroreflective pavement markers shall be used to supplement the centerline markings on State highways. If used in snow areas, they shall be recessed.**

Option:

08 Raised retroreflective pavement markers may be used to supplement the centerline markings on highways and conventional roads.

Support:

09 On horizontal curves with radii less than 3280 feet and without street lighting, Detail 22 instead of Detail 21 can be helpful in improving the delineation for centerline markings, as it includes retroreflective raised pavement markers. Detail 22 can be applied in advance of the approach to the curve per Table 2C-3 and continued throughout the length of the curve.

10 Refer to CVC § 21460 for Double Lines.

11 Refer to CVC § 21460.5 for Two-Way Left-Turn Lanes.

Standard:

12 **A left edge line shall consist of a solid yellow line of 4 to 6 inches wide for local streets and roads and 6 inches wide on the State Highway System, yellow reflective pavement markers, yellow-red retroreflective markers, or a combination of line and markers as shown in Figure 3A-105(CA).**

Option:

13 Two normal solid yellow lines may be used as a left edge line on a divided roadway for more emphasis when motorists tend to use the shoulder for a through lane or where encroachments onto the shoulder occasionally occur.

Support:

14 Left edge line patterns for median islands are shown in Figure 3A-107(CA).

Standard:

15 **When a passing lane is provided, a two-direction no passing marking (refer to Figure 3A-104(CA)) shall be used when the Average Daily Traffic (ADT) exceeds 3,000. Refer to Figure 3B-104(CA).**

Option:

16 Passing in both directions may be provided by alternating the direction of the middle lane at about 1 mile intervals.

17 A one-direction no passing marking (refer to Figure 3A-103(CA)) with one or more YIELD TO UPHILL TRAFFIC (R55(CA)) signs may be used when the ADT is 3,000 or less.

Section 3B.03 No-Passing Zone Pavement Markings

Standard:

01 **No-passing zones shall be marked by either the one-direction no-passing zone pavement markings or the two-direction no-passing zone pavement markings described in Section 3B.01 and shown in Figures 3B-1 and 3B-3.**

02 **No-passing zone markings shall be used on:**

- A. Two-way roadways at lane-reduction transitions (see Section 3B.12),**
- B. Approaches to obstructions that must be passed on the right (see Section 3B.13),**
- C. Approaches to grade crossings (see Section 8C.02), and**
- D. Approaches to crosswalks.**

03 **On two-way, two-lane or three-lane roadways where center line markings are installed, no-passing zones shall be established at vertical and horizontal curves and other locations where an engineering study indicates that passing must be prohibited because of inadequate sight distances or other special conditions.**

04 **On roadways with center line markings, no-passing zone markings shall be used at horizontal or vertical curves where the passing sight distance is less than the minimum shown in Table 3B-1 for the 85th-percentile speed or the speed limit.**

Support:

05 The passing sight distance on a vertical curve is the distance at which an object 3.5 feet above the pavement surface can be seen from a point 3.5 feet above the pavement (see Figure 3B-4). Similarly, the passing sight distance on a horizontal curve is the distance measured along the center line (or right-hand lane line of a three-lane roadway) between two points 3.5 feet above the pavement on a line tangent to the embankment or other obstruction that cuts off the view

on the inside of the curve (see Figure 3B-4).

- 06 The upstream end of a no-passing zone at point “a” in Figure 3B-4 is that point where the sight distance first becomes less than that specified in Table 3B-1. The downstream end of the no-passing zone at point “b” in Figure 3B-4 is that point at which the sight distance again becomes greater than the minimum specified.

Guidance:

- 07 ~~Where the distance between successive no-passing zones is less than 400 feet, no-passing zone markings should connect the zones.~~

Standard:

- 07a **If the gap between successive no-passing zones is less than the sight distance for the prevailing speed shown in Table 3B-1, or 400 feet, whichever is greater, the no-passing zone shall be continuous.**

Support:

- 08 No-passing zone signs (see Sections 2B.36, 2B.37, and 2C.53) are sometimes used to emphasize the existence and extent of a no-passing zone.

Standard:

- 09 **On three-lane roadways where the direction of travel in the center lane transitions from one direction to the other, a no-passing buffer zone, consisting of a flush median island (see Section 3J.03) at least 50 feet in length, shall be provided in the center lane as shown in Figure 3B-5. A lane-reduction transition (see Section 3B.12) shall be provided approaching each end of the buffer zone.**

Support:

- 10 Refer to CVC §§ 21750 through 21759 for overtaking and passing.

- 11 Refer to CVC § 21460 for Double Lines.

- 12 CVC § 21752 restricts passing (driving on the left side of a two-way roadway) when approaching within 100 feet of or when traversing any intersection or railroad grade crossing. CVC § 21752 also restricts passing (driving on the left side of a two-way roadway) when the view is obstructed upon approaching within 100 feet of any bridge, viaduct, or tunnel. The patterns and policy for intersection markings are shown in Figure 3A-109(CA).

Standard:

- 13 **No-passing zone patterns shall be selected from those shown in Figures 3A-103(CA) and 3A-104(CA).**

Guidance:

- 14 *The no-passing zone markings at intersections, when used, should be between 100 feet and 300 feet in length at the approach to an intersection and placed in a pattern as shown in Figure 3A-109(CA).*

Section 3B.04 Yellow Pavement Markings for Reversible Lanes

Standard:

- 01 **If reversible lanes are used, the lane line pavement markings on each side of reversible lanes shall consist of a normal width broken double yellow line to delineate the edge of a lane in which the direction of travel is reversed from time to time, such that each of these markings serve as the center line markings of the roadway during some period (see Figure 3B-6).**

- 02 **Signs (see Section 2B.34), lane-use control signals (see Chapter 4T), or both shall be used to supplement reversible lane pavement markings.**

Support:

- 03 Section 3E.02 contains additional applications of pavement markings for counter-flow preferential lanes that also operate as reversible lanes.

Section 3B.05 Pavement Markings for Two-Way Left-Turn Lanes

Standard:

- 01 **If a two-way left-turn lane that is never operated as a reversible lane is used, the lane line pavement markings on each side of the two-way left-turn lane shall consist of a normal width broken yellow line and a normal width solid yellow line to delineate the edges of a lane that can be used by traffic in either direction as part of a left-turn maneuver. These markings shall be placed with the broken line toward the two-way left-turn lane and the solid line toward the adjacent traffic lane as shown in Figure 3B-7.**

Guidance:

- 02 *White two-way left-turn lane-use arrows should be used at or just downstream from the beginning of a two-way left-*

turn lane.

Option:

- 03 Additional two-way left-turn lane-use arrow markings may be used at other locations along a two-way left-turn lane where engineering judgment determines that such additional markings are needed to emphasize the proper use of the lane.

Standard:

- 04 **A single-direction lane-use arrow shall not be used in a lane bordered on both sides by yellow two-way left-turn lane longitudinal markings.**

Guidance:

- 05 *Signs should be used in conjunction with the two-way left-turn markings (see Section 2B.32).*
06 *Two-way left-turn lane markings should not extend to intersections (see definition in Section 1C.02).*

Option:

- 07 Two-way left-turn lanes may be transitioned to mandatory left-turn lanes as shown in Figure 3B-7 or painted median islands where they approach an intersection.

Support:

- 08 Section 8A.06 contains guidance information for discontinuing a two-way left-turn lane in the immediate vicinity of a highway-rail or highway-LRT grade crossing.

Standard:

- 09 **On State highways, reversible lanes shall be separated by physical barriers or delineators.**

Support:

- 10 A two-way left-turn lane is a lane reserved in the center of a highway for exclusive use of left or U-turning vehicles. Refer to CVC § 21460.5. It is normally used where there are many points of access.

Standard:

- 11 **The two-way left-turn lane markings shall be selected from those shown in Figures 3B-7 and 3A-108(CA).**

Option:

- 12 Optional treatments at signalized, major, and minor intersections, as shown in Figure 3B-7(CA), may be used.
13 Two-way opposing pavement arrows may be used as shown in Figure 3B-7(CA). The arrows may be supplemented by a Two-Way Left Turn Lane (R3-9a or R3-9b) sign at new installations and problem locations.

Guidance:

- 14 *A gap in the markings should be made at all intersections.*

Support:

- 15 For left turn channelization, refer to Figure 3B-101(CA) and Caltrans' Highway Design Manual, Section 405.2. Refer to Section 1A.11 for information regarding this publication.

- 16 Channelized left-turn lanes in combination with continuous raised-curb medians are used instead of two-way left-turn lanes (TWLTL) if one or more of the following conditions exist:

- A. Average daily traffic volumes exceed 20,000 vehicles per day
- B. For remediation where there is a demonstrated crash problem,
- C. Wherever a need is demonstrated through engineering study.

- 17 Refer to CVC § 21460.5 for Two-Way Left-Turn Lanes.

- 18 For details of two-way left-turn lanes, refer to Figure 3B-7(CA). For left turn channelization, refer to Figure 3B-101(CA) and Caltrans' Highway Design Manual, Section 405.2. Refer to Section 1A.05 for information regarding this publication.

Section 3B.06 White Lane Line Pavement Markings

Standard:

- 01 **When used, lane line pavement markings delineating the separation of traffic lanes that have the same direction of travel shall be white.**

- 02 **Lane line markings shall be used on all freeways and Interstate highways.**

Guidance:

- 03 *Lane line markings should be used:*

- A. *On all roadways that are intended to operate with two or more adjacent traffic lanes in the same direction of travel, except as otherwise required for reversible lanes.*
- B. *At congested locations where the roadway will accommodate more traffic lanes with lane line markings than*

without the markings.

Support:

- 04 Examples of lane line markings are shown in Figures 3B-2, 3B-3, ~~and 3B-7~~ through 3B-13, ~~and 3B-7(CA)~~ through 3B-10(CA).

Standard:

- 05 **Except as provided in Paragraph 1 of Section 3B.07, where crossing the lane line markings with care is not discouraged or prohibited, the lane line markings shall consist of a normal width broken white line.**
- 06 **Where crossing the lane line markings is discouraged, the lane line markings shall consist of a normal width solid white line.**

Guidance:

- 07 *A solid white lane line marking should be used on approaches to:*
- A. *Intersections to separate a through lane from a mandatory turn lane.*
 - B. *Intersections to separate contiguous mandatory turn lanes from each other.*
 - C. *Toll collection points to separate toll lanes, payment methods, channelized movements, or obstructions.*

Option:

- 08 Solid white lane line markings may be used:
- A. On approaches to intersections to separate contiguous through lanes.
 - B. To separate through traffic lanes from auxiliary lanes, such as an added uphill truck lane.
 - C. On approaches to crosswalks across multi-lane roadways.
- 09 Wide solid lane line markings may be used for greater emphasis.
- 10 A curved transition may be used where an edge line, channelizing line, or dotted extension line changes direction.

Support:

- 11 Examples of locations where a curved transition can have value include freeway exit and entrance ramps, and turn lanes.

Standard:

- 12 **Where crossing the lane line markings is prohibited, the lane line markings shall consist of a double solid white line (see Figure 3B-8).**
- 13 **Lane line patterns shall be selected from those shown in Figure 3A-102(CA). Detail 9 or 10 (40 mph or less) or Detail 12, 12A, or 13 (45 mph or more) shall be used on freeways, expressways, freeway ramps, freeway to freeway connectors and collector roads, except when used in snow areas, the raised pavement markers, if used, shall be recessed; otherwise, use Detail 8 or 11.**
- 14 **When a climbing lane is provided on an upgrade and truck lane control signs are used (refer to Section 2B.38), an 8-inch solid white line shall be used in place of the standard lane line stripe.**

Section 3B.07 White Lane Line Markings for Non-Continuing Lanes

Standard:

- 01 **A normal width dotted white line marking shall be used as the lane line to separate a through lane that continues beyond the interchange or intersection from an adjacent deceleration or acceleration lane.**
- 02 **For exit ramps with a parallel deceleration lane, a normal width dotted white lane line extension shall be installed from the upstream end of the taper to the theoretical gore or to the upstream end of a solid white lane line, if used, that extends upstream from the theoretical gore as shown in Drawings A and C in Figure 3B-9.**
- 03 **For an exit ramp with a tapered deceleration lane, a normal width dotted white line extension shall be installed from the theoretical gore through the taper area such that it meets the edge line at the upstream end of the taper as shown in Drawing B in Figure 3B-9.**
- 04 **For entrance ramps with a parallel acceleration lane, a normal width dotted white lane line shall be installed from the theoretical gore or from the downstream end of a solid white lane line, if used, that extends downstream from the theoretical gore, to a point at least one-half the distance from the theoretical gore to the downstream end of the acceleration taper, as shown in Drawing A in Figure 3B-10 and 3B-10(CA) Sheet 2 of 2.**

Option:

- 05 For entrance ramps with a parallel acceleration lane, a normal width dotted white line extension may be installed from the downstream end of the dotted white lane line to the downstream end of the acceleration taper, as shown in Drawing A in Figure 3B-10 and 3B-10(CA) Sheet 2 of 2.

- 06 For entrance ramps with a tapered acceleration lane, a normal width dotted white line extension may be installed from the downstream end of the channelizing line adjacent to the through lane to the downstream end of the acceleration taper, as shown in Drawings B and C in Figure 3B-10 and 3B-10(CA) Sheet 1 of 2.

Standard:

- 06a **White chevron markings (refer to Section 3B.25) shall be placed in the neutral area of exit ramp gores.**
- 07 **A wide dotted white lane line shall be used:**
- A. **As a lane drop marking in advance of lane drops at exit ramps to distinguish a lane drop from a normal exit ramp (see Drawings A, B, and C in Figure 3B-11),**
 - B. **In advance of freeway route splits with dedicated lanes (see Drawing D in Figure 3B-11),**
 - C. **In advance of freeway route splits with an option lane (see Drawing E in Figure 3B-11),**
 - D. **To separate a through lane that continues beyond an interchange from an adjacent continuous auxiliary lane between an entrance ramp and an exit ramp (see Drawing F in Figure 3B-11 and Figure 3B-11(CA) Sheet 1 of 2),**
 - E. **As a lane drop marking in advance of lane drops at intersections to distinguish a lane drop from an intersection through lane (see Drawing A in Figure 3B-12), and**
 - F. **To separate a through lane that continues beyond an intersection from an adjacent auxiliary lane between two intersections (see Drawing B in Figure 3B-12).**

Guidance:

- 08 *Lane drop markings used in advance of lane drops at freeway and expressway exit ramps should begin at least ½ mile in advance of the theoretical gore. If the dropped lane is an auxiliary lane 1/2 mile or less in length, the lane drop line should extend throughout the entire length.*
- 09 *On the approach to a multi-lane exit ramp having an optional exit lane that also carries through traffic, lane line markings should be used as illustrated in Drawing B in Figure 3B-11.*
- 10 *Lane drop markings used in advance of lane drops at intersections should begin a distance in advance of the intersection that is determined by engineering judgment as suitable to enable drivers who do not desire to make the mandatory turn to move out of the lane being dropped prior to reaching the queue of vehicles that are waiting to make the turn. The lane drop markings should begin no closer to the intersection than the most upstream regulatory or warning sign associated with the lane drop.*
- 11 *The dotted white lane lines that are used for lane drop markings and that are used as a lane line separating through lanes from auxiliary lanes should consist of line segments that are 3 feet in length separated by 9-foot gaps.*

Standard:

- 11a **The lane drop line pattern shall be as shown in Figure 3A-111(CA).**
- Support:
- 11b Refer to Figures 3A-111(CA), 3B-9(CA), 3B-10(CA), 3B-14(CA) and 3B-104(CA) for further details of markings and signing.
- Option:
- 11c A 8-inch wide single solid white line preceded by an 8-inch wide dotted white line may be placed in advance of an intersection where the outside lane is dropped at the intersection, and as a result, creates a mandatory turn lane.

Standard:

- 11d **If used, diagonal lines shall be the same color as the edge line.**
- Support:
- 12 Sections 3B.21 and 3B.23 contain information regarding other markings that are associated with lane drops, such as ONLY word pavement markings and lane-use arrows.
- 13 Section 3B.12 contains information about the lane line markings that are to be used for transition areas where the number of through lanes is reduced at a location that is not at an interchange or intersection.
- Option:
- 14 In the case of a lane drop at an exit ramp or intersection, a solid white line may replace a portion, but not all of the length, of the wide dotted white lane line.

Standard:

- 15 **Left-turn or right-turn lanes shall be separated from the through lanes by a single solid 8-inch-wide white line as shown in Figure 3A-112(CA) except as provided in paragraph 16.**
- Option:
- 16 Left-turn or right-turn lanes may be separated from the through lanes by multiple solid 8-inch-wide white lines or two longitudinal

solid 8-inch-wide lines with diagonal lines used for crosshatch markings.

Section 3B.08 Channelizing Lines

Support:

01 Channelizing lines are used to form neutral areas where traffic traveling in the same general direction is permitted on both sides including entrance and exit ramps, access and egress points to and from managed lanes, toll-plaza bypasses, and left-turn lanes separated from through lanes. Channelizing lines are also sometimes used to alter travel paths for speed management or other purposes.

02 Chapter 3J contains information for the application of channelizing lines used in conjunction with islands.

Standard:

03 **Except as provided in Section 3E.04 and Paragraph 6 of Section 3J.05, a channelizing line shall be a solid wide or double solid white line.**

Support:

04 Examples of channelizing line applications are shown in Figures 3B-9, 3B-10, 3B-10(CA), 3B-11, Drawing C in Figure 3B-15, Figures 3J-1 through 3J-5, and Drawing B in Figure 3J-6.

Standard:

05 **For all exit ramps and for entrance ramps with parallel acceleration lanes, channelizing lines shall be placed on both sides of the neutral area (see Figures 3B-9 and 3B-11, 3B-9(CA), 3B-10(CA) Sheet 2 of 2, and Drawing A in Figure 3B-10).**

06 **For entrance ramps with tapered acceleration lanes, channelizing lines shall be placed along both sides of the neutral area to a point at least one-half of the distance to the theoretical gore (see Drawing C in Figure 3B-10 and Figure 3B-10(CA) Sheet 1 of 2).**

07 **Channelizing lines shall be placed on both sides of the neutral area for bifurcations created from open-road tolling lanes that bypass a conventional toll plaza.**

08 **Where neutral areas are formed at access and egress points to and from a managed-lane facility, channelizing lines shall be placed on both sides of the neutral area (see Figures 2G-8, 2G-10, 2G-13, 2G-16, 2G-22, 2G-23, 2G-27, and 2G-28).**

Option:

09 For entrance ramps with tapered acceleration lanes, the channelizing lines may extend to the theoretical gore as shown in Drawing B in Figure 3B-10 and 3B-10(CA) Sheet 1 of 2.

Standard:

10 **Other pavement markings in the neutral area shall be white.**

Support:

11 Pavement markings within the neutral area include chevron markings (see Section 3B.25), retroreflective raised pavement markers (see Section 3B.16), and internally illuminated raised pavement markers (see Section 3B.16).

Section 3B.09 Edge Line Pavement Markings

Standard:

01 **If used, edge line pavement markings shall delineate the right or left edges of a roadway.**

02 **Except as provided in Section 3E.04, right edge line pavement markings, if used, shall consist of a normal width solid white line to delineate the right-hand edge of the roadway.**

03 **If used on the roadways of divided highways or one-way streets, or on any ramp in the direction of travel, left edge line pavement markings shall consist of a normal width solid yellow line to delineate the left-hand edge of a roadway or to indicate driving or passing restrictions left of these markings, except as provided in Section 3E.04.**

Support:

04 Edge line markings provide visual references to guide road users during adverse weather and visibility conditions.

Option:

05 Wide solid edge line markings may be used for greater emphasis. Support:

06 Increasing edge line width from 4 inches to at least 6 inches can be a beneficial countermeasure on all facility types in both urban and rural areas.

Guidance:

07 *Edge line markings should not be continued through intersections, except for the following situations:*

A. *Dotted edge line extensions (see Section 3B.11), or*

B. *Through that part of an intersection with no intersection approach (such as the far side of a T- intersection).*

Support:

08 Section 3B.11 contains information on the use and application of edge lines through intersections, interchanges, and driveways.

Standard:

09 **A right edge line shall consist of a solid white line of 4 to 6 inches for local streets and roads, and 6 inches on the State Highway System.**

Guidance:

10 *The edge line should be placed 2 inches in from the edge of the traveled way, approximately 12 feet from the lane line or centerline on highway mainlines, ramps, and connectors. Refer to Figure 3A-106(CA).*

11 *Generally, the solid edge line should be dropped at the beginning of intersection flares.*

Option:

12 *In heavy fog areas, or locations where additional guidance would be beneficial, a dotted 4-inch-wide white right-edge line may be continued across an intersection.*

Support:

13 Edge line is not used at turnouts. Refer to Figure 3B-105(CA).

Standard:

14 **Exit and entrance ramps, including freeway connectors, shall be marked with a yellow edge line supplemented with yellow-red reflective pavement markers on the left and a white edge line on the right. Refer to Figure 3A-105(CA).**

15 **Exit ramps shall be further supplemented with enhanced reflective pavement marker spacings on the right and left edge lines. Enhanced blank-red pavement marker spacings shall be used at a closely spaced pattern on white right edge lines, and enhanced yellow-red reflective pavement marker spacing shall be used at a closely spaced pattern on yellow left edge lines. Refer to Figure 3A-114(CA)**

Guidance:

16 *If used, the enhanced spacing retroreflective pavement markers should be placed at a minimum of 120 feet from the ramp terminus. The spacing should be 12 feet, typical for 240 feet, and 6 feet, typical for an additional 120 feet. Refer to Figure 3A-114(CA).*

Standard:

17 **When the blank-red retroreflective pavement markers are placed along the white right Edge line, the side that is visible to traffic proceeding in the wrong direction shall be red, and the side visible to approaching traffic shall be blank.**

Section 3B.10 Warrants for Use of Edge Lines

Standard:

01 **Edge line markings shall be placed on paved streets or highways with the following characteristics:**

A. Freeways,

B. Expressways, and

C. Rural arterials with a traveled way of 20 feet or more in width and an ADT of 6,000 vehicles per day or greater.

Guidance:

02 *Edge line markings should be placed on paved streets or highways with the following characteristics:*

A. *Rural arterials and collectors with a traveled way of 20 feet or more in width and an ADT of 3,000 vehicles per day or greater.*

B. *On other paved streets and highways where an engineering study indicates a need for edge line markings.*

03 *Edge line markings should not be placed where an engineering study or engineering judgment indicates that providing them is likely to decrease safety for all road users.*

Option:

04 Edge line markings may be placed on streets and highways with or without center line markings.

05 Edge line markings may be excluded, based on engineering judgment, for reasons such as if the traveled way edges are delineated by curbs, parking, or other markings.

06 If a bicycle lane is marked on the outside portion of the traveled way, the edge line that would mark the outside edge of the bicycle lane may be omitted.

07 Edge line markings may be used where edge delineation is desirable to minimize unnecessary driving on paved shoulders or on refuge areas that have lesser structural pavement strength than the adjacent roadway.

Standard:

08 **Edge lines shall be used on all State highways, except urban-type streets with curbs and parking provisions.**

Option:

09 The Two-Way Traffic (W6-3) sign may be used in conjunction with edge lines at locations where road users could perceive that they are on a one-way roadway when, in fact, they are on a two-lane, two-way highway. Refer to Section 2C.51 for the W6-3 sign.

Section 3B.11 Application of Pavement Markings Through Intersections or Interchanges

Standard:

01 **Pavement markings extended into or continued through an intersection or interchange area shall be the same color as the line markings they extend (see Figure 3B-13).**

Guidance:

02 *Pavement markings extended into or continued through an intersection or interchange area should be at least the same width as the line markings they extend.*

03 *Where highway design or reduced visibility conditions make it desirable to provide control or to guide vehicles through an intersection or interchange, such as at offset, skewed, complex, or multi-leg intersections, on curved roadways, where multiple turn lanes are used, or where offset left-turn lanes might cause driver confusion, dotted lane line extension markings consisting of 2-foot line segments and 2-foot to 6-foot gaps should be used to extend longitudinal line markings through an intersection or interchange area.*

04 *Where greater restriction is preferred, solid lane lines or channelizing lines should be extended into or continued through intersections.*

Standard:

05 **Extensions of center lines through intersections shall be dotted lines.**

Guidance:

06 *Where a double line is extended through an intersection, a single line of equal width to one of the lines of the double line should be used.*

Standard:

07 **Solid lines shall not be used to extend edge lines into or through intersections except through that part of an intersection with no intersecting approach (such as at the far side of a T-intersection).**

Guidance:

08 *Edge line markings should be discontinued across intersecting approaches at intersections or interchanges.*

09 *Driveways that do not meet the definition of an intersection (see Section 1C.02) should have edge line markings maintained across the intersecting approach of the driveway.*

Option:

10 Dotted edge line extensions may be placed through intersections.

Support:

11 Section 3B.31 contains information about edge lines through diverging diamond interchanges with a transposed alignment crossroad.

12 Section 3D.03 provides information for edge lines through roundabouts.

13 Section 5B.02 contains information on edge line extensions for driving automation system considerations.

14 Section 8C.05 contains information about the extension of edge lines through grade crossing areas.

15 Section 9E.03 contains information for the extensions of bicycle lanes through intersections.

Support:

16 Refer to Figure 3A-112(CA), Detail 40 and 40A for lane line extensions.

Section 3B.12 Lane-Reduction Transitions

Support:

01 A lane-reduction is where the number of through lanes is reduced at a location that is not at an interchange or intersection because of narrowing of the roadway or because of a section of on-street parking in what would otherwise be a through lane.

02 Section 3B.07 contains information on pavement markings for lane drops and splits.

03 Section 2C.47 contains information for warning signing used for lane reductions.

Standard:

04 **Lane-reduction transitions (see Figure 3B-14 3B-14(CA)) shall include the following elements:**

- A. **A no-passing zone (see Section 3B.03) to prohibit passing in the direction of the convergence and through the transition area except where not applicable such as one-way streets, expressways, and freeways; and**
- B. **An edge line (see Section 3B.09) in the direction of the convergence and through the transition area, except as provided in Paragraph 6 of this Section.**

Guidance:

05 *Except as provided in Paragraph 6 of this Section, the edge line marking should be installed from the location of the Lane Ends warning sign to beyond the beginning of the narrower roadway.*

Option:

06 On roadways with operating speeds less than 25 mph where curbs clearly define the roadway edge in the lane-reduction transition, or where a through lane becomes a parking lane, the edge line may be omitted as determined by engineering judgment.

Guidance:

07 *Lane-reduction transitions should include the following elements:*

- A. *Delineators installed adjacent to the lane or lanes reduced for the full length of the transition and should be so placed and spaced (see Section 3G.04) to show the reduction except as provided in Paragraph 13 of this Section and except as provided in Paragraph 2 of Section 3G.03 for freeways and expressways,*
- B. *Lane-reduction arrow markings (see Drawing F in Figure 3B-21) on the roadway with a speed limit of 45 mph or more, and*
- C. *A termination of the broken white lane line at a point that is 1/4 of the advance placement distance (see Section 2C.04) between the Lane Ends sign (see Section 2C.47) and the point where the transition taper begins.*

Support:

07a Refer to FHWA's List of Known Errors for error in Paragraph 07, Item B text. Refer to Section 1A.04 for more details.

Guidance:

08 *For roadways having a speed limit of 45 mph or greater, the transition taper length for a lane-reduction transition should be computed by the formula $L = WS$, where L equals the taper length in feet, W equals the width of the offset distance in feet, and S equals the 85th-percentile speed or the speed limit in mph, whichever is higher. For roadways where the speed limit is less than 45 mph, the formula $L = WS^2/60$ should be used to compute the taper length.*

09 *The minimum lane reduction transition taper length should be 100 feet in urban areas and 200 feet in rural areas.*

10 *Where observed speeds exceed speed limits, longer tapers should be used.*

Option:

11 The minimum taper length may be less than 100 feet on roadways where the operating speed is less than 25 mph.

12 On new construction, where no speed limit has been established, the design speed may be used in the transition taper length formula.

13 On low-speed urban roadways where curbs clearly define the roadway edge in the lane-reduction transition, or where a through lane becomes a parking lane, delineators may be omitted as determined by engineering judgment.

14 Where a lane-reduction transition occurs on a roadway with a speed limit of less than 45 mph, lane-reduction arrow markings may be used.

15 Lane-reduction arrow markings may be used in long acceleration lanes based on engineering judgment.

16 A dotted white line may be used between the point where the broken white lane line is terminated to the point where the transition taper begins.

Support:

17 Typical lane reduction transitions (four lane to two lane) and transitions from two lanes to four lanes are shown in Figure 3B-14(CA).

Section 3B.13 Approach Markings for Obstructions

Standard:

01 **Pavement markings shall be used to guide traffic away from fixed obstructions within a paved roadway.**

Approach markings for bridge supports, refuge islands, median islands, toll plaza islands, and raised channelization islands shall consist of a tapered line or lines extending from the center line or the lane line to a

point 1 to 2 feet to the right-hand side, or to both sides, of the approach end of the obstruction (see Figure 3B-15).

Guidance:

02 *For roadways having a speed limit of 45 mph or greater, the taper length of the tapered line markings should be computed by the formula $L = WS$, where L equals the taper length in feet, W equals the width of the offset distance in feet, and S equals the 85th-percentile speed or the speed limit, whichever is higher. For roadways where the speed limit is less than 45 mph, the formula $L = WS^2/60$ should be used to compute the taper length.*

03 *The minimum taper length should be 100 feet in urban areas and 200 feet in rural areas.*

Option:

04 *The minimum taper length may be less than 100 feet on roadways where the operating speed is less than 25 mph.*

Standard:

05 **If traffic is required to pass only to the right of the obstruction, the markings shall consist of a two-direction no-passing zone marking at least twice the length of the diagonal portion as determined by the appropriate taper formula (see Drawing A in Figure 3B-15).**

Option:

06 *If traffic is required to pass only to the right of the obstruction, yellow diagonal markings (see Section 3B.25) may be placed in the flush median islands (see Section 3J.03) between the no-passing zone markings as shown in Drawings A and B in Figure 3B-15.*

Standard:

07 **If traffic can pass either to the right or left of the obstruction, the markings shall consist of two channelizing lines diverging from the lane line, one to each side of the obstruction. In advance of the point of divergence, a wide solid white line or normal width double solid white line shall be extended in place of the broken lane line for a distance equal to the length of the diverging lines (see Drawing C in Figure 3B-15).**

Option:

08 *If traffic can pass either to the right or left of the obstruction, additional white chevron markings (see Section 3B.25) may be placed in the flush neutral area between the channelizing lines as shown in Drawing C in Figure 3B-15. Other markings, such as white delineators, white channelizing devices, white raised pavement markers, and white crosswalk markings may also be placed in the flush neutral area.*

Section 3B.14 Raised Pavement Markers – General

Standard:

01 **The color of raised pavement markers under both daylight and nighttime conditions shall conform to the color of the marking for which they serve as a positioning guide, or for which they supplement or substitute.**

Option:

02 *The side of a raised pavement marker that is visible to traffic proceeding in the wrong direction may be red (see Section 3A.03).*

03 *Retroreflective or internally illuminated raised pavement markers may be used in the roadway immediately adjacent to curbed approach ends of raised medians and curbs of islands, or on top of such curbs (see Section 3J.06).*

Standard:

04 **When used, internally illuminated raised pavement markers shall be steadily illuminated and shall not be flashed.**

Support:

05 *Flashing raised pavement markers are considered to be In-Roadway Lights (see Chapter 4U).*

05a *Refer to FHWA's List of Known Errors for error in Paragraph 5 text. Refer to Section 1A.04 for more details.*

Guidance:

06 *The spacing of raised pavement markers used to supplement or substitute for other types of longitudinal markings should correspond with the pattern of broken lines for which the markers supplement or substitute.*

Standard:

07 ~~**The value of N cited in Sections 3B.15 through 3B.17 for the spacing of raised pavement markers shall equal the length of one line segment plus one gap of the broken lines used on the highway.**~~

07a **The widths and patterns of raised pavement markers shall conform to the details shown in Figures 3A-101(CA) through 3A-114(CA). Refer to Section 3A.04.**

Option:

- 08 For additional emphasis, retroreflective raised pavement markers may be spaced closer than described in Sections 3B.15 through 3B.17, as determined by engineering judgment or engineering study.

Support:

- 09 Section 9A.03 contains information for the application of raised pavement markers to bicycle facilities.

Support:

- 10 Raised pavement markers are not normally placed where snowplows would damage the markers and require an unusual amount of replacement, unless recessed.

Guidance:

- 11 *When used in these areas, they should be recessed, as shown in Caltrans' Standard Plan A20-D. Refer to Section 1A.05 for information regarding this publication.*

Advance Markers

Option:

- 12 Advance Markers at exit ramps may be used to help motorists locate exit ramps in heavy fog areas.

Support:

- 13 The Advance Markers consist of a 3-2-1 countdown pattern of one-way clear reflective pavement markers. The pattern consists of three markers placed on the right shoulder 2100 feet in advance of the neutral area (gore), two markers at 1400 feet, and one marker at 700 feet. The markers are placed on a line perpendicular to the lane line at 1-foot spacing, beginning 2 inches off the edge of the traveled way.

Section 3B.15 Raised Pavement Markers as Vehicle Positioning Guides with Other Longitudinal Markings

Option:

- 01 Retroreflective or internally illuminated raised pavement markers may be used as positioning guides with longitudinal line markings without necessarily conveying information to the road user about passing or lane-use restrictions. In such applications, markers may be positioned in line with or immediately adjacent to a single line marking, or positioned between the two lines of a double center line or double lane line marking.

Guidance:

- 02 ~~Except as otherwise provided in Paragraphs 3 and 4 of this Section, the spacing for such applications should be 2N (see Section 3B.14).~~

Option:

- 03 Where it is desired to alert the road user to changes in the travel path, such as on sharp curves or on transitions that reduce the number of lanes or that shift traffic laterally, the spacing ~~may be reduced to N or less~~ shown in Details 16, 17, 19, 20, 22 or 23 may be used.

- 04 ~~On freeways and expressways, the spacing may be increased to 3N for relatively straight and level roadway segments where engineering judgment indicates that such spacing will provide adequate delineation under wet night conditions.~~

Standard:

- 05 **The widths and patterns of raised pavement markers shall conform to the details shown in Figures 3A-101(CA) through 3A-114(CA). Refer to Section 3A.04.**

Section 3B.16 Raised Pavement Markers Supplementing Other Markings

Guidance:

- 01 *The use of retroreflective or internally illuminated raised pavement markers for supplementing longitudinal line markings should comply with the following:*

A. Lateral Positioning

1. *When supplementing double line markings, pairs of raised pavement markers placed laterally in line with or immediately outside of the two lines should be used.*
2. *When supplementing wide line markings, pairs of raised pavement markers placed laterally adjacent to each other should be used.*

B. Longitudinal Spacing

1. ~~When supplementing solid line markings, raised pavement markers at a spacing no greater than N (see~~

~~Section 3B.14) should be used, except that when supplementing channelizing lines or edge line markings, a spacing of no greater than $N/2$ should be used.~~

- ~~2. When supplementing broken line markings, a spacing no greater than $3N$ should be used. However, when supplementing broken line markings identifying reversible lanes, a spacing of no greater than N should be used.~~
3. When supplementing dotted lane line markings, a spacing appropriate for the application should be used.
4. When supplementing longitudinal line extension markings through at-grade intersections, one raised pavement marker for each short line segment should be used.
- ~~5. When supplementing line extensions through freeway interchanges, a spacing of no greater than N should be used.~~

02 Raised pavement markers should not supplement right-hand edge lines unless an engineering study or engineering judgment indicates the benefits of enhanced delineation of a curve or other location would outweigh possible impacts on bicyclists using the shoulder, and the spacing of raised pavement markers on the right-hand edge does not simulate a broken line during wet night conditions.

02a One-way blank-red retroreflective raised pavement markers should supplement wrong-way arrows, limit lines/stop lines, yield lines, or crosswalk markings used at freeway exit ramps

Option:

03 Raised pavement markers also may be used to supplement other markings such as channelizing islands, gore areas, approaches to obstructions, or wrong-way arrows.

04 To improve the visibility of horizontal curves, center lines may be supplemented with retroreflective or internally illuminated raised pavement markers for the entire curved section as well as for a distance in advance of the curve that approximates 5 seconds of travel time.

Standard:

05 The widths and patterns of raised pavement markers shall conform to the details shown in Figures 3A-101(CA) through 3A-114(CA). Refer to Section 3A.04.

06 When the one-way blank-red retroreflective raised pavement markers are placed along the type V arrow, limit lines, yield lines, or crosswalk markings, the side that is visible to traffic proceeding in the wrong direction shall be red and the side visible to approach traffic shall be blank.

Section 3B.17 Raised Pavement Markers Substituting for Pavement Markings

Option:

01 Retroreflective or internally illuminated raised pavement markers, or non-retroreflective raised pavement markers supplemented by retroreflective or internally illuminated markers, may be substituted for markings of other types.

Guidance:

02 *If used, the pattern of the raised pavement markers should simulate the pattern of the markings for which they substitute.*

Standard:

03 Non-retroreflective raised pavement markers shall not be used alone, without supplemental retroreflective or internally illuminated markers, as a substitute for other types of pavement markings.

Support:

04 Section 6J.02 contains information for flexible temporary pavement markers used during surface treatment paving operations.

04a Refer to FHWA's List of Known Errors for error in Paragraph 4 text. Refer to Section 1A.04 for more details.

Standard:

05 If raised pavement markers are used to substitute for broken line markings, a group of three to five markers ~~equally spaced at a distance no greater than $N/8$ (see Section 3B.14) shall be used. If N is other than 40 feet, the markers shall be equally spaced over the line segment length (at $\frac{1}{2}$ points for three markers, at $\frac{1}{3}$ points for four markers, and at $\frac{1}{4}$ points for five markers).~~ At least one retroreflective or internally illuminated marker per group shall be used or a retroreflective or internally illuminated marker shall be installed midway in each gap between successive groups of non- retroreflective markers.

06 ~~When raised pavement markers substitute for solid line markings, the markers shall be equally spaced at no greater than $N/4$, with retroreflective or internally illuminated units at a spacing no greater than $N/2$.~~

Guidance:

- 07 *Raised pavement markers should not substitute for right-hand edge line markings unless an engineering study or engineering judgment indicates the benefits of enhanced delineation of a curve or other location would outweigh possible impacts on bicyclists using the shoulder, and the spacing of raised pavement markers on the right-hand edge line does not simulate a broken line during wet night conditions.*

Standard:

- 08 ~~When raised pavement markers substitute for dotted lines, they shall be spaced at no greater than N/4, with not less than one raised pavement marker per dotted line segment. At least one raised marker every N shall be retroreflective or internally illuminated.~~

Option:

- 09 When substituting for wide lines, raised pavement markers may be placed laterally adjacent to each other to simulate the width of the line.

Support:

- 10 Section 5B.02 contains information on raised pavement marker considerations for driving automation systems.

Section 3B.18 Curb Markings for Parking Regulations

Guidance:

- 01 *Except as provided in Paragraph 4 of this Section, since yellow and white curb markings are frequently used for curb delineation and visibility, parking regulations should be established through the installation of standard signs (see Sections 2B.53 and 2B.54).*
- 02 *Where curbs are marked to convey parking regulations in areas where curb markings are frequently obscured by snow and ice accumulation, signs should be used with the curb markings except as provided in Paragraph 4 of this Section.*
- 03 *Except as provided in Paragraph 4 of this Section, when curb markings are used without signs to convey parking regulations, a legible word marking regarding the regulation (such as “No Parking” or “No Standing”) should be placed on the curb.*

Option:

- 04 Curb markings without word markings or signs may be used to convey a general prohibition by statute of parking within a specified distance of a STOP sign, YIELD sign, driveway, fire hydrant, or crosswalk.
- 05 Local highway agencies may prescribe special colors for curb markings to supplement standard signs for parking regulation.

Support:

- 06 Refer to Sections 2C.70 through 2C.73 for marking noses of raised medians and curbs of islands with object markers.
- 07 Refer to Section 2B.52 for Parking Regulations.
- 08 In California, curb markings are not used for delineating traffic. They are mainly used for parking regulations.

Standard:

- 09 **The color of curb markings shall conform to CVC § 21458 quoted below:**
- (a) Whenever local authorities enact local parking regulations and indicate them by the use of paint upon curbs, the following colors only shall be used, and the colors indicate as follows:**
 - (1) Red indicates no stopping, standing, or parking, whether the vehicle is attended or unattended, except that a bus may stop in a red zone marked or signposted as a bus loading zone.**
 - (2) Yellow indicates stopping only for the purpose of loading or unloading passengers or freight for the time as may be specified by local ordinance.**
 - (3) White indicates stopping for either of the following purposes:**
 - (A) Loading or unloading of passengers for the time as may be specified by local ordinance.**
 - (B) Depositing mail in an adjacent mailbox.**
 - (4) Green indicates time limit parking specified by local ordinance.**
 - (5) Blue indicates parking limited exclusively to the vehicles of disabled persons and disabled veterans.**
 - (b) Regulations adopted pursuant to subdivision (a) shall be effective on days and during hours or times as prescribed by local ordinances.**
- 10 **Parking regulations shall be covered by ordinance or order of the authority having jurisdiction over the street or highway.**

Option:

- 11 Curb markings may supplement standard signs.
- 12 Prohibitions or restrictions enacted by local authorities under CVC §§ Sections 22506, 22507, and 22500 may be indicated by marking curbs as prescribed by CVC § 21458.

Policy on Parking Restrictions

Support:

- 13 Loading Zones - Local authorities are authorized by Section 21112 of the CVC to license and regulate the location of stands on streets and highways for use of taxicabs and other public carriers for hire. Where such stands are located on State highways, and highway maintenance is not delegated to the local authority, the approval of Caltrans is required. The District Directors have been delegated the authority to approve local ordinances establishing such stands.

Section 3B.19 Stop and Yield Lines

Option:

- 01 Stop lines may be used to indicate the point behind which vehicles are required to stop in compliance with a STOP (R1-1) sign, a ~~Stop Here for Pedestrians (R1-5b) sign, a Stop Here for School Crossing (R1-5c) sign, a Stop Here for Trail Crossing (R1-5d) sign,~~ or some other traffic control device that requires vehicles to stop, except YIELD signs that are not associated with passive grade crossings.

Standard:

- 02 **Stop lines shall consist of solid white lines extending across approach lanes to indicate the point at which the stop is intended or required to be made.**
- 03 **Except as provided in Section 8C.03, stop lines shall not be used at locations where drivers are required to yield in compliance with a YIELD (R1-2) sign, a Yield Here to Pedestrians (R1-5) sign, a Yield Here to School Crossings (R1-5a) sign, a Yield Here to Trail Crossings (R1-5d) sign, or at locations on uncontrolled approaches where drivers or bicyclists are required by State law to yield to pedestrians.**

Guidance:

- 04 *Stop lines should be used to indicate the point behind which vehicles are required to stop in compliance with a traffic control signal (see Section 4D.08).*
- 05 *Stop lines should be 12 to 24 inches wide.*

Option:

- 06 Stop lines may be omitted at ramp control signals.

Support:

- 07 Section 4J.02 contains information regarding the use and application of stop lines in conjunction with a pedestrian hybrid beacon.

Standard:

- 08 **If used, a yield line pavement marking shall not be installed without a Yield (R1-2) sign, a Yield Here to Pedestrians (R1-5) sign, a Yield Here to School Crossings (R1-5a) sign, a Yield Here to Trail Crossings (R1-5d) sign, or some other traffic control device that requires vehicles to yield (see Figure 3B-16).**
- 09 **Yield lines shall not be used at locations where drivers are required to stop in compliance with a STOP (R1-1) sign, a ~~Stop Here for Pedestrians (R1-5b) sign, a Stop Here for School Crossing (R1-5c) sign, a Stop Here for Trail Crossing (R1-5d) sign,~~ a traffic control signal, or some other traffic control device.**
- 10 **Yield lines shall consist of a row of solid white isosceles triangles pointing toward approaching vehicles extending across approach lanes to indicate the point at which the yield is intended or required to be made.**

Option:

- 11 If a yield line marking is used on a bicycle facility, a Bicycles Yield to Pedestrians (R9-6) sign (see Section 9B-12) may be used.

Guidance:

- 12 *The individual triangles comprising the yield line should have a base of 12 to 24 inches wide and a height equal to 1.5 times the base. The space between the triangles should be 3 to 12 inches.*
- 13 *If used, stop and yield lines should be placed a minimum of 4 feet in advance of the nearest crosswalk line at controlled intersections, except for yield lines at roundabouts as provided for in Section 3D.04 and at midblock crosswalks. In the absence of a marked crosswalk, the stop line or yield line should be placed at the desired stopping or yielding point, but should not be placed more than 30 feet or less than 4 feet from the nearest edge of the intersecting*

traveled way.

Standard:

- 14 **If yield (~~stop~~) lines are used at a crosswalk that crosses an uncontrolled multi-lane approach, Yield Here to (~~Stop Here for~~) Pedestrians (R1-5 series) signs (see Section 2B.19) shall be used.**

Guidance:

- 15 *If yield (~~stop~~) lines are used at a crosswalk that crosses an uncontrolled multi-lane approach, the yield (~~stop~~) line should be placed 20 to 50 feet in advance of the nearest crosswalk line (see Drawing B in Figure 3B-16).*
- 16 *If yield ~~or stop~~ lines are used in advance of a crosswalk that crosses an uncontrolled multi-lane approach, parking should be prohibited in the area between the yield ~~or stop~~ line and the crosswalk.*

Support:

- 17 Section 9B.12 contains information for providing signing applicable to bicyclists also subject to a yielding requirement at a crosswalk that crosses an uncontrolled approach.

Guidance:

- 18 *Yield (~~stop~~) lines and Yield Here to (~~Stop Here for~~) Pedestrians signs should not be used in advance of crosswalks that cross an approach to or departure from a circular intersection.*

Support:

- 19 Section 8C.03 contains information regarding the use of stop lines and yield lines at grade crossings. Option:
- 20 Stop and yield lines may be staggered longitudinally on a lane-by-lane basis (see Drawing D in Figure 3B-13).

Support:

- 21 Staggered stop lines and staggered yield lines can improve the driver's view of pedestrians, provide better sight distance for turning vehicles, and increase the turning radius for left-turning vehicles.
- 22 *As defined in CVC § 377, a "limit line" is a solid white line not less than 12 inch nor more than 24 inch wide, extending across a roadway or any portion thereof to indicate the point at which traffic is required to stop in compliance with legal requirements.*

Standard:

- 23 **For all purposes, limit line(s) as defined per CVC § 377 shall mean stop line(s). See Paragraph 5.**

Guidance:

- 24 *If a sidewalk exists, the limit line should be placed in advance of an unmarked crosswalk area.*

Option:

- 25 *A limit line may be placed in advance of a crosswalk where vehicles are required to stop, in compliance with a STOP (R1-1) sign, traffic control signal or some other traffic control device.*

Support:

- 26 *If a marked crosswalk is in place, it would normally function as a limit line.*
- 27 *Typical limit line markings are shown in Figure 3B-102(CA).*

Section 3B.20 Word, Symbol, and Arrow Pavement Markings – General

Support:

- 01 Word, symbol, and arrow markings on the pavement are used for the purpose of regulating, warning, or guiding traffic. These pavement markings can be helpful to road users in some locations by supplementing signs and providing additional emphasis for important regulatory, warning, or guidance messages, because the markings do not require diversion of the road user's attention from the roadway surface. Symbol messages are preferable to word messages. Examples of standard word and arrow pavement markings are shown in Figures 3B-17 and 3B-21, respectively.

- 01a *Normally, pavement word and symbol markings supplement standard signing.*

Option:

- 02 Word, symbol, and arrow pavement markings may be used as determined by engineering judgment to supplement signs and/or to provide additional emphasis for regulatory, warning, or guidance messages provided by other devices.

Support:

- 03 Section 8C.04 contains information for arrow pavement markings in the vicinity of grade crossings.

Standard:

- 04 **Word, symbol, and arrow markings shall be white, except as otherwise provided in this Section.**
- 05 **Pavement marking letters, numerals, symbols, and arrows shall be installed in accordance with the design details in the Pavement Markings chapter of the "Standard Highway Signs" publication (see Section 1A.05).**

Support:

05a Refer to Caltrans' Standard Plans for pavement marking letters, numerals, and symbols. Refer to Section 1A.05 for information regarding this publication

Guidance:

06 *Word, symbol, and/or arrow markings that are grouped together to formulate one interrelated message should not exceed three lines of information.*

07 *Except for the two opposing white arrows of a two-way left-turn lane marking (see Figure 3B-7) and the pavement word marking messages described in Items B and D of Paragraph 2 of Section 3B.26, the longitudinal space between word, symbol, and/or arrow markings that are used together to formulate one interrelated message should be at least four times the height of the characters for low-speed roads, but not more than ten times the height of the characters under any conditions.*

08 ~~Except for the SCHOOL word marking~~ (see Section 7C.02), pavement word, symbol, and arrow markings should be no more than one lane in width.

09 *Pavement word, symbol, and arrow markings should be proportionally scaled to fit within the width of the facility upon which they are applied.*

Option:

10 On narrow, low-speed shared-use paths, the pavement words, symbols, and arrows may be smaller than suggested, but to the relative scale.

11 On roadways where the operating speed is less than 25 mph, word, symbol, and arrow markings may be proportionally reduced by 25 percent.

Section 3B.21 Word Pavement Markings

Guidance:

01 *Letters and numerals should be 6 feet or more in height, except as provided in Section 9E.01 for the BIKE LANE word pavement marking and in Section 9E.15 for a bicycle detector symbol and WAIT HERE FOR GREEN word pavement marking.*

02 *If a pavement marking word message consists of more than one line of information, it should read in the direction of travel. The first word of the message should be nearest to the road user.*

Standard:

03 **The word STOP shall not be placed on the pavement in advance of a stop line, unless every vehicle is required to stop at all times.**

Guidance:

03a A STOP pavement legend should be placed on all but minor approaches to State highways not controlled by signals.

Option:

03b Pavement markings with appropriate figures may be used to supplement speed limit signs. Refer to Section 2B.21.

Guidance:

04 *Where through lanes approaching an intersection become mandatory turn lanes, ONLY word pavement markings (see Figure 3B-17) should be used in addition to signs (see Sections 2B.27 and 2B.28) and the required lane-use arrow markings (see Section 3B.23).*

Option:

05 The ONLY word marking may be used to supplement the lane-use arrow markings in lanes that are designated for the exclusive use of a single movement such as turn bays.

06 The ONLY word marking may be used to supplement a preferential lane word or symbol marking (see Section 3E.03).

07 On roadways where the operating speed is less than 25 mph, word markings may be proportionally reduced by 25 percent.

Standard:

08 **The ONLY word marking shall not be used in a lane that is shared by more than one movement.**

Option:

09 Electric vehicle charging stations in off-street locations may be marked with a white, twelve-inch high EV CHARGING ONLY pavement legend (Refer to Figure 3B-106(CA)) to supplement Electric Vehicle Charging Station signs in sections 2B.52 and 2I.03.

Standard:

- 10 Each electric vehicle charging station designated for Van Accessible, Standard Accessible, and Ambulatory electric vehicle charging stations shall be marked with a white, twelve-inch high EV CHARGING ONLY pavement legend (Refer to Figure 3B-106(CA) to supplement signs, per CBC, Chapter 11B, Section 812.9, and Figure 11B-812.9).

Support:

- 11 The authority for local agencies to regulate accessible parking, including designated EV charging stations, is provided by CVC § 22511. The provisions apply to parking areas open to public travel, such as rest stops. Refer to Section 1B.01.

Section 3B.22 Symbol Pavement Markings

Support:

- 01 Section 3E.03 contains information on the diamond-shaped symbol for high-occupancy vehicle (HOV) lanes.
02 Chapter 9E contains information on symbol markings that can be used for bicycle lanes.

Option:

- 03 Pavement markings simulating Interstate, U.S., State, and County route signs (see Figure 2D-4) with appropriate route numbers, but elongated for proper proportioning when viewed as a marking, may be used to guide road users to their destinations (see Figure 3B-18).

Guidance:

- 04 *If route sign markings are provided to guide road users, those route sign markings should be provided in option lanes if markings are provided in any lanes.*
05 *If two route sign markings are provided in an option lane, they should be placed in sequence and not divided around an optional lane arrow.*

Support:

- 06 Section 3A.03 provides information on route sign colors.
07 Section 9E.14 contains information on route markers for designated bicycle routes that can be used on shared-use paths.

Guidance:

- 08 ~~The International Symbol of Accessibility parking space marking (see Figure 3B-19) should be placed in each parking space designated for use by persons with disabilities.~~

Standard:

- 08a The International Symbol of Accessibility (ISA) parking space marking shall be placed in each parking space within the highway right-of-way (refer to Figure 3B.19).

Guidance:

- 08b *The ISA parking space marking (Figure 3B-19) should be placed in each parking space within the highway right-of-way designated for use by persons with disabilities.*

Option:

Standard:

- 09 A blue background with a white border ~~may~~ shall supplement the wheelchair symbol as shown in Figure 3B-19.

- 09a If used, new construction of accessible parking spaces within the highway right-of-way and loading and unloading areas shall include pavement marking details shown on Figure 3B-19, or as shown on Caltrans' Standard Plan A90A. The loading and unloading area shall be marked by a border and hatched lines. The border shall be painted blue, and the hatched lines shall be painted a suitable contrasting color to the parking space (blue or white paint is preferred).

- 09b If used, new construction of accessible parking within the highway right-of-way shall include a blue painted curb, as shown on Caltrans' Standard Plan A90B. If parking within the highway right-of-way designated and designed for persons with disabilities includes a loading and unloading area, it shall be marked by a border and hatched lines. The border shall be painted blue, and the hatched lines shall be painted a suitable contrasting color to the parking space (blue or white paint is preferred).

- 09c Loading and unloading areas shall include the words "NO PARKING" within the blue border and shall be painted in white letters no less than 12 inches high (Refer to detail in Figure 3B-19). Refer to California Code of Regulations Title 24, Section 1129B.4.

Support:

- 09d Provisions apply to parking areas open to public travel, such as rest stops. Refer to Section 1B.01.

10 A yield-ahead triangle symbol or YIELD AHEAD word pavement marking may be used on approaches to intersections where the approaching traffic will encounter a YIELD sign at the intersection.

Standard:

11 **The yield-ahead triangle symbol or YIELD AHEAD word pavement marking shall not be used unless a YIELD sign (see Section 2B.05) is in place at the intersection. The yield-ahead triangle symbol marking shall be as shown in Figure 3B-20.**

Option:

12 A pedestrian symbol pavement marking may be used on portions of facilities that are reserved exclusively for pedestrian use, such as where a shared-use path transitions to become separate facilities for different types of users.

Section 3B.23 Lane-Use Arrows

Support:

01 Lane-use arrow markings (see Figure 3B-21) are used to indicate the mandatory or permissible movements in certain lanes (see Figure 3B-22) and in two-way left-turn lanes (see Figure 3B-7).

02 Section 8C.04 contains information about the placement of lane-use arrow markings in the vicinity of grade crossings.

Guidance:

03 *Lane-use arrow markings should be used in lanes and turn bays designated for the exclusive use of a turning movement, except where engineering judgment determines that physical conditions or other markings (such as a dotted extension of the lane line through the taper into the turn bay) clearly discourage unintentional use of a turn bay by through vehicles. Lane-use arrow markings should also be used in lanes from which movements are allowed that are contrary to the normal rules of the road (see Drawing B in Figure 3B-13).*

04 *When used in turn lanes, at least two arrows should be used, one at or near the upstream end of the full-width turn lane and one at an appropriate distance upstream from the stop line or intersection (see Drawing A in Figure 3B-12).*

05 *Where opposing offset channelized left-turn lanes exist, lane-use arrow markings should be placed near the downstream terminus of the offset left-turn lanes to reduce wrong-way movements (see Figure 2B-20).*

Option:

06 An additional arrow or arrows may be used in a turn lane. When arrows are used for a short turn lane, the second (downstream) arrow may be omitted based on engineering judgment.

Support:

07 An arrow at the downstream end of a turn lane can help to prevent wrong-way movements.

Standard:

08 **Where through lanes approaching an intersection become mandatory turn lanes, turn lane-use arrow markings (see Drawing A in Figure 3B-12 and Figure 3B-21) shall be used and shall be accompanied by standard signs (see Section 2B.28).**

Arrows:

Standard:

08a **Where a turning movement is mandatory, an arrow marking accompanied by a regulatory sign shall be used. However, when an additional clearly marked lane is provided for the approach to the turning movement, the sign is not required. Refer to CVC § 22101.**

Support:

08b Examples of entrance/exit ramp terminal signs and pavement markings are shown in Figure 3B-21(CA).

Guidance:

08c *The Type V arrows and warning signs, as shown in Figure 3B-103(CA), should be used at locations where road users could perceive that they are on a one-way roadway when, in fact, they are on a two-lane, two-way highway. The following are some typical situations:*

- A. *Construction sites where a two-lane highway is being converted to a freeway or an expressway.*
- B. *Two-lane, two-way highways where the ultimate freeway or expressway right-of-way has been purchased and grading for the full width has been completed.*
- C. *Two-lane, two-way highways following long sections of multi-lane freeway or expressway.*

Exit Ramp Arrows:

Standard:

- 08d A minimum of two pavement arrows shall be placed on each freeway exit ramp lane.
- 08e A Type V arrow shall be the first arrow, on the ramp, in the direction of travel when exiting the freeway.
- 08f Where a mandatory movement is required, a Type I, II, III, IV, VII, or VIII arrow shall be placed with its point approximately 20 feet preceding the limit line, crosswalk, or "STOP" pavement legend. Where no mandatory movement is required, a Type V arrow shall be used at this location.
- 08g All other additional arrows, when used, shall be a minimum of 24 feet in length.
- 08h All arrows shall be placed in the center of the lane and spaced approximately 100 feet to 300 feet apart.

Guidance:

- 08i *The actual position and spacing should be determined in the field to provide the optimum visibility for traffic that may attempt to enter the exit ramp in the wrong direction.*

Support:

- 08j Refer to Figure 3B-21(CA).

Entrance Ramp Arrows:

Standard:

- 08k A minimum of one Type I arrow, not less than 18 feet in length, shall be positioned in the center of each freeway entrance ramp lane so that it is clearly in view of a right-way road user.

Guidance:

- 08l *The distance between arrows, when more than one per lane is needed, should be 100 feet to 300 feet. The Type V arrow should not be used on entrance ramps.*

Support:

- 08m Refer to Figure 3B-21(CA).
- 08n Additional information on the signing of ramp terminals is shown in Section 2E.59.

Turn Lane Arrows:

Standard:

- 08o One directional arrow, a minimum of 8 feet in length, shall be placed in the center of each turning lane near the point of entrance.

Option:

- 08p High approach speeds may justify the use of a longer arrow. Two or more arrows may be placed in long turning lanes.

Support:

- 08q Refer to Figures 3B-7(CA) and 3B-101(CA).
- 08r Refer to Section 2B.48 and 2E.59 for Wrong-Way Traffic Control at Interchange Ramps.

Guidance:

- 09 *Where through lanes approaching an intersection become mandatory turn lanes, ONLY word markings (see Figure 3B-17) should be used in addition to signs (see Sections 2B.27 and 2B.28) and the required turn lane-use arrow markings. These signs and markings should be placed well in advance of the turn and should be repeated as necessary to provide the through motorist advance notification to vacate the lane prior to reaching a point where roadway geometrics or a queue of waiting vehicles forces the motorist to make an unintended turn.*

Option:

- 10 On freeways or expressways where a through lane becomes a mandatory exit lane, lane-use arrow markings may be used on the approach to the exit in the dropped lane and in an adjacent optional through-or-exit lane if one exists.

Section 3B.24 Wrong-Way Arrows

Guidance:

- 01 *Where crossroad channelization or ramp geometrics do not make wrong-way movements difficult, the appropriate lane-use arrow should be placed in each lane of an exit ramp near the crossroad terminal where it will be clearly visible to a potential wrong-way road user (see Figure 2B-15).*

Option:

- 02 The wrong-way arrow markings shown in Drawing G in Figure 3B-21 may be placed near the downstream terminus of a ramp as shown in Figure 2B-15 and in Drawing A in Figure 2B-16, or at other locations where lane-use arrows are not appropriate, to indicate the correct direction of traffic flow and to discourage drivers from traveling in the wrong

direction.

Section 3B.25 Chevron and Diagonal Markings

Support:

- 01 Chevron or diagonal markings are used to discourage travel on certain paved areas, such as shoulders, neutral areas, and flush median islands.

Support:

- 01a For chevron markings in exit gore areas, refer to Section 3B.11.

Option:

- 02 Chevron and diagonal markings may be used:
- A. On approaches to obstructions in the roadway (see Sheet 2 of Figure 3B-15),
 - B. For channelized travel paths on approaches to intersections,
 - C. In buffer spaces between preferential lanes and general-purpose lanes (see Drawing A in Figure 3E- 2),
 - D. In the neutral area gores (see Figures 3B-9 through 3B-11),
 - E. In the neutral area of bifurcations created from open-road tolling lanes that bypass a conventional toll plaza,
 - F. In the neutral areas at access and egress points to and from a managed-lane facility (see Figures 2G-8, 2G-10, 2G-22, and 2G-23), and
 - G. In the neutral areas of islands.
- 03 Chevron markings may be supplemented with white retroreflective or internally illuminated raised pavement markers (see Section 3B.16) for enhanced nighttime visibility.

Support:

- 04 Section 5B.02 contains information on chevron markings for driving automation system considerations.

Standard:

- 05 **Chevron markings shall be white, with the point of each chevron facing toward approaching traffic, as shown in Figures 3B-9 through 3B-11, and Drawing C in Figure 3B-15.**

Option:

- 06 Diagonal markings for opposing directions of traffic may be used:
- A. On approaches to obstructions in the roadway (see Drawings A and B in Figure 3B-15),
 - B. In flush median islands between double solid yellow center line markings (see Figure 3B-5), and
 - C. In buffer spaces between preferential lanes and general-purpose lanes (see Drawing D in Figure 3E- 4).
- 07 Diagonal markings may be used on paved shoulders or in no-parking zones, or other locations for special emphasis.

Standard:

- 08 **When diagonal markings are used between opposing directions of traffic or on the left shoulder of a one-way or divided roadway, they shall be yellow and slant away from traffic in the adjacent travel lanes, as shown in Figures 3B-2 and 3B-5, and Drawings A and B in Figure 3B-15.**
- 09 **When diagonal markings are used on the right shoulder or in no-parking zones (see Figure 3B- 23), they shall be white and slant away from traffic in the adjacent travel lane.**

Guidance:

- 10 *Except as provided in Paragraph 11 of this Section, chevrons and diagonal markings should be at least 12 inches wide for roadways having a speed limit of 45 mph or greater, and at least 8 inches wide for roadways having a speed limit of less than 45 mph. The longitudinal spacing of the chevrons or diagonal lines should be determined by engineering judgment considering factors such as speeds and desired visual impacts. The chevrons and diagonal lines should form an angle of approximately 30 to 45 degrees with the longitudinal lines that they intersect.*

Option:

- 11 Diagonal markings used in no-parking zones or on roadways with operating speeds of less than 25 mph may be 4 inches wide (see Figure 3B-23).

Guidance:

- 12 *Diagonal and chevron markings should be used, when in the opinion of an engineer, it is necessary to add emphasis or to discourage vehicular travel upon a paint-formed roadway feature such as an unusually wide shoulder area, a pedestrian refuge island, or a traffic divisional or channelization island.*
- 13 *Diagonal lines, when used, should be installed between an edge line and a traffic island, or between pairs of double yellow lines.*
- 14 *Chevron markings, when used, should be installed between channelizing lines for traffic flows in the same direction.*

Support:

- 15 The applicable channelizing lines for chevron markings are shown in Figure 3A-110(CA), Details 36, 36A, and 36B, and pairs of lines shown in Figure 3A-112(CA), Details 38 and 38A.
- 16 The diagonal lines or chevron markings are normally 12 inches wide.

Standard:

- 17 **Diagonal lines and chevrons shall be the same color as the line or lines to which they connect and shall point at a 45-degree forward angle.**
- 18 **Diagonal lines or chevrons, if used, shall be the same color as the edge line.**

Option:

- 19 The spacing between these lines may vary from 1 foot in a pedestrian crosswalk to 200 feet for vehicular traffic.

Section 3B.26 Do Not Block Intersection Markings

Support:

- 00 Refer to CVC § 22526 for entering an intersection, a rail crossing, or a marked crosswalk.

Option:

- 01 Do Not Block Intersection markings may be used to mark the edges of an intersection area that is in close proximity to a signalized intersection, railroad crossing, or other nearby traffic control that might cause vehicles to stop within the intersection and impede other traffic entering the intersection. If authorized by law, Do Not Block Intersection markings with appropriate signs may also be used at other locations.

Standard:

- 02 **If used, Do Not Block Intersection markings (see Figure 3B-24) shall consist of one of the following alternatives:**
- A. Wide solid white lines that outline the intersection area that vehicles must not block;**
 - B. Wide solid white lines that outline the intersection area that vehicles must not block and a white word message such as DO NOT BLOCK or KEEP CLEAR;**
 - C. Wide solid white lines that outline the intersection area that vehicles must not block and white cross-hatching within the intersection area; or**
 - D. A white word message, such as DO NOT BLOCK or KEEP CLEAR, within the intersection area that vehicles must not block.**
- 03 **Do Not Block Intersection markings shall be accompanied by one or more DO NOT BLOCK INTERSECTION (DRIVEWAY) (CROSSING) (R10-7) signs (see Section 2B.59), one or more DO NOT STOP ON TRACKS (R8-8) signs (see Section 8B.07), or one or more similar signs.**

Section 3B.27 Parking Space Markings

Standard:

- 01 **On-street parking space markings shall be white.**

Support:

- 02 Examples of on-street parking space markings are shown in Figure 3B-23.

Option:

- 03 Blue lines may supplement white parking space markings of each parking space designated for use only by persons with disabilities (see Figure 3B-23).

Support:

- 04 Additional parking space markings for the purpose of designating spaces for use only by persons with disabilities are discussed in Section 3B.22 and illustrated in Figure 3B-19.

Support:

- 05 Refer to CVC §§ 22500 through 22522 for parking space markings.
- 06 Refer to Section 2B.45 for Parking Signs.

Policy on Parking Restrictions

Option:

- 07 Local authorities may, by ordinance, provide for the establishment of parking meter zones and cause streets and highways to be marked with white lines designating parking spaces. Refer to CVC § 22508.

Support:

- 08 No ordinance or resolution of local authorities shall apply to any state highway until the proposed ordinance or resolution has been presented to, and approved in writing by, the Department of Transportation. Refer to CVC § 21960(c).
- 09 The desirable dimensions of parking meter stalls are 8 feet by 24 feet with a minimum length of 20 feet.

Guidance:

- 10 *At signalized intersections, parking should be prohibited for a minimum of 30 feet on the near side and one stall length on the far side. Refer to Figure 3B-23(CA).*

Standard:

- 11 **Stopping, standing, or parking of a vehicle within 20 feet of the vehicle's approach side of any unmarked or marked crosswalk, or 15 feet of any crosswalk where a curb extension is present, is prohibited. Refer to CVC § 22500.**

Section 3B.28 Speed Reduction Markings

Support:

- 01 Speed reduction markings (see Figure 3B-25) are transverse markings that are placed on the roadway within a lane (along both edges of the lane) in a pattern of progressively reduced spacing to give drivers the impression that their speed is increasing.
- 02 Speed reduction markings have been shown to enhance safety around curves and locations with a history of run-off-the-road crashes when applied in combination with horizontal alignment warning signs (see Section 2C.05).

Option:

- 03 Speed reduction markings may be placed in advance of an unexpectedly severe horizontal or vertical curve or other roadway feature where drivers need to decelerate prior to reaching the feature and where the desired reduction in speeds has not been achieved by the installation of warning signs and/or other traffic control devices.

Guidance:

- 04 *If used, speed reduction markings should be reserved for unexpected curves or other usages based on engineering judgment. Speed reduction markings should not be used on long tangent sections of roadway or in areas frequented mainly by local or familiar drivers, such as school zones. If used, speed reduction markings should supplement the appropriate warning signs and other traffic control devices and should not substitute for these devices.*

Standard:

- 05 **Speed reduction markings shall be a series of white transverse lines on both sides of the lane that are perpendicular to the center line, edge line, or lane line.**

Guidance:

- 06 *The longitudinal spacing between the markings should be progressively reduced from the upstream to the downstream end of the marked portion of the lane.*
- 07 *Speed reduction markings should not be greater than 12 inches in width, and should not extend more than 18 inches into the lane.*

Standard:

- 08 **Speed reduction markings shall be used only in lanes that have a longitudinal line (center line, edge line, or lane line) on both sides of the lane.**

Section 3B.29 Speed Hump and Speed Table Markings

Support:

- 00 According to CVC § 440, speed humps or bumps are not official traffic control devices.

Standard:

- 01 **If speed hump markings are used, they shall be a series of white markings placed on a speed hump to identify its location. If markings are used for a speed hump that does not also function as a crosswalk or speed table, the markings shall comply with Option A, B, or C shown in Figure 3B-26. If markings are used for a speed hump that also functions as a crosswalk or speed table, the markings shall comply with Option A or B shown in Figure 3B-27.**

Option:

- 02 Where used, center line markings, lane line markings, and edge lines may be discontinued on the profile of the speed hump.

Standard:

- 03 **Where a speed hump or a speed table specifically incorporates a crossing movement for pedestrians, bicyclists, or equestrians, and functions as a raised crosswalk, crosswalk markings (see Chapter 3C) shall be provided.**

Section 3B.30 Advance Speed Hump and Speed Table Markings

Option:

- 01 Advance speed hump markings (see Figure 3B-28) may be used in advance of speed humps or other engineered vertical roadway deflections such as dips where added visibility is desired or where such deflection is not expected.
- 02 Advance word pavement markings such as BUMP or HUMP (see Section 3B.20) may be used on the approach to a speed hump either alone or in conjunction with advance speed hump markings. Appropriate advance warning signs may be used in compliance with Section 2C.27.

02a. Raised retroreflective pavement markers may be used to supplement advance speed hump markings (Refer to Figure 3B-28).

Support:

02b Provisions for raised pavement markers supplementing other markings are contained in Section 3B.14 and 3B.16.

Standard:

- 03 **If advance speed hump or speed table markings are used, they shall be a series of eight white 12-inch transverse lines that become longer and are spaced closer together as the vehicle approaches the speed hump or other deflection. If advance markings are used, they shall comply with the detailed design shown in Figure 3B-28.**

Guidance:

04 *If used, advance speed hump markings should be installed in each approach lane.*

Section 3B.31 Markings for a Diamond Interchange with a Transposed Alignment Crossroad

Support:

01 Markings used in a diverging diamond interchange with a transposed alignment crossroad can be advantageous for minimizing wrong-way movements. The potential for wrong-way movements is greatest at the crossover intersections where the alignment becomes transposed.

01a Diverging diamond interchanges, also known as double-crossover diamond interchanges, include directional crossovers on either side of the interchange that transpose the crossroad, which results in vehicles traveling on the left-hand side of the street or highway between the crossover intersections.

Standard:

- 02 **On the transposed alignment, each direction shall be considered a one-way roadway whereas the edge line convention shall be in accordance with Section 3B.09. Both yellow and white edge lines shall be used.**
- 03 **A lane-use arrow (see Section 3B.23) shall be used in each approach lane at the crossover intersection.**

Support:

04 Section 3C.11 contains information on crosswalks and pedestrian movements for diverging diamond interchanges with a transposed alignment crossroad.

Standard:

- 05 **Flush median islands (see Section 3J.03) shall not be used to divide the inverted flow of traffic.**

Guidance:

06 *Edge line and lane line extensions (see Section 3B.11) should be provided through the crossing points.*

Support:

07 Figure 3B-29 illustrates an example of pavement markings for a diverging diamond interchange with a transposed alignment crossroad.

Section 3B.101(CA) Turnouts

Guidance:

01 *Paved turnouts should be marked with an 8-inch-wide single solid white line between the through lane and the turnout. The line should not extend through the entry and exit areas. Refer to Figure 3B-105(CA) and Caltrans' Highway Design Manual, Section 204.5 (4). Refer to Section 1A.05 for information regarding this publication.*

02 *The right edge line should be dropped throughout the length of the turnout.*

Option:

03 *Turnout length may be increased 100 feet on downgrades over 3%.*

Figure 3B-1. Yellow Center Lines for Two-Lane, Two-Way Applications




Figure 3B-2. Yellow Center Lines for Four-or-More Lane, Two-Way Applications




Figure 3B-3. Yellow Center Lines for Three-Lane, Two-Way Applications





Figure 3B-4. Method of Locating and Determining the Limits of No-Passing Zones at Curves

A – No-passing zone at VERTICAL CURVE



B – No-passing zone at HORIZONTAL CURVE




Figure 3B-5. Application of Three-Lane, Two-Way Markings for Changing the Direction of the Center Lane




Figure 3B-6. Example of Yellow Pavement Markings for Reversible Lanes




Figure 3B-7. Examples of Two-Way Left-Turn Lane Marking Applications





Figure 3B-7(CA). Example of Two-Way Left-Turn Lane Marking Applications



Notes:

1. See Figure 3A-108(CA) for Two-Way Left-Turn Lane line markings.
2. Two-Way Pavement Arrows, and the R3-9a (overhead) and R3-9b (post-mounted) signs are optional. See Section 2B.32.

Figure 3B-8. Example of a Double Solid White Line Used to Prohibit Lane Changing






Figure 3B-9. Examples of Dotted Line and Channelizing Line Applications for Exit Ramp Markings (Sheet 1 of 2)




* Refer to FHWA's List of Known Errors for error. Refer to Section 1A.04 for more details.

Figure 3B-9. Examples of Dotted Line and Channelizing Line Applications for Exit Ramp Markings (Sheet 2 of 2)

C – Parallel deceleration lane at a multi-lane exit ramp having an optional exit lane that also carries the through route



Tapered Deceleration Lane



1. Place a Solid White Line and One-Way Clear Retroreflective Markers on 24 ft centers. See Detail 36 on Figure 3A-110(CA).

2. Place a Solid Yellow Left Edge Line and One-Way Yellow Retroreflective Pavement Markers on 24 ft centers. See Detail 25A on Figure 3A-105(CA).
3. A flared Right Edge Line 150 ft in advance of an exit ramp, is recommended where climatic conditions, such as areas that experience heavy fog, may require additional guidance. In areas that normally do not experience these conditions, a continuous edge line may be used. See also Section 3B.14, Advance Markers - Exit Ramps.
4. Place delineators 2 ft to 6 ft outside edge of paved shoulder, approximately 200 ft apart with a minimum of 3 delineators per tangent. For additional details on delineator locations and spacing on curves, see Figures 3G-1 and 3G-102(CA).
5. See Figure 3A-114(CA) for Ramp Terminal Markings and Section 2B.48.
6. See Section 3B.25 Chevron and Diagonal Markings.

Figure 3B-10. Examples of Dotted Line and Channelizing Line Applications for Entrance Ramp Markings (Sheet 1 of 2)




Figure 3B-10. Examples of Dotted Line and Channelizing Line Applications for Entrance Ramp Markings (Sheet 2 of 2)






Figure 3B-10(CA). Examples of Dotted Line and Channelizing Line Applications for Entrance Ramp Markings (Sheet 1 of 2)



Notes:

1. Place an 8 in. Solid White Line and One-Way Clear Retroreflective Markers on 24 ft centers. See Detail 36A on Figure 3A-110(CA).
2. Place a Solid Yellow Left Edge Line and One-Way Yellow Retroreflective Pavement Markers on 24 ft centers. See Detail 25A on Figure 3A-105(CA).
3. Place delineators 2 ft to 6 ft outside the edge of paved shoulder, approximately 200 ft apart with a minimum of 3 delineators per tangent. For additional details on delineator locations and spacing on curves, see Figures 3G-1 and 3G-102(CA).
4. When the entrance ramp lane becomes an added freeway lane, it shall be marked as a standard lane line. If the additional lane terminates at an exit ramp within 1/2 mi.

Figure 3B-10(CA). Examples of Dotted Line and Channelizing Line Applications for Entrance Ramp Markings (Sheet 2 of 2)




Notes:

1. An 8 in. Solid White Channelizing Line should be continued for approximately one-tenth the length of the acceleration lane beyond the tangent point. See Detail 38A on Figure 3A-112(CA).
2. A Dashed White Lane Line (Detail 8 or 11) is normally used for the remaining length of the lane. However, in those locations where the lane may give the appearance of an added lane and to discourage its use by through traffic, an 8 in. Dashed White Channelizing Line (Detail 37) may be considered. See Figures 3A-102(CA) and 3A-111(CA).
3. See Figure 3B-14(CA) for transition area signing and marking details, when the acceleration lane is longer than 1 mi.

Figure 3B-11. Examples of Applications of Freeway and Expressway Lane-Drop Markings (Sheet 1 of 6)

A – Lane drop at a single lane exit ramp



B – Lane drop at a multi-lane exit ramp having an optional exit lane that also carries the through route




Figure 3B-11. Examples of Applications of Freeway and Expressway Lane-Drop Markings (Sheet 3 of 6)




Figure 3B-11. Examples of Applications of Freeway and Expressway Lane-Drop Markings (Sheet 4 of 6)




Figure 3B-11. Examples of Applications of Freeway and Expressway Lane-Drop Markings (Sheet 5 of 6)




Figure 3B-11. Examples of Applications of Freeway and Expressway Lane-Drop Markings (Sheet 6 of 6)






Figure 3B-11(CA). Examples of Applications of Freeway and Expressway Lane-Drop Markings (Sheet 1 of 2)

Auxiliary (Weaving) Lane, such as at Cloverleaf Interchange

A. AUXILIARY (WEAVING) LANE (600 FT TO 1/2 MI.)



B. AUXILIARY (WEAVING) LANE (LONGER THAN 1/2 MI.)



NOT TO SCALE

LEGEND


➔ Direction of Travel

Notes:


1. Auxiliary (Weaving) Lanes less than 600 ft are normally marked as Exit Ramps (see Sheets 1 and 2) and Entrance Ramps (Refer to Figure 3B-10(CA)).
2. An 8 in. Solid White Channelizing Line should be continued for approximately one-tenth the length of the acceleration lane beyond the tangent point. See Detail 38A.
3. A Dashed White Lane Line (Detail 8 or 11) is normally used for the remaining length of the lane. However, in those locations where the lane may give the appearance of an added lane and to discourage its use by through traffic, an 8 in. Dashed White Channelizing Line (Detail 37) may be considered. See Details on Figures 3A-102(CA) and 3A-111(CA).
4. Refer to Section 3B.25 Chevron and Diagonal Markings.

Figure 3B-11(CA). Examples of Applications of Freeway and Expressway Lane-Drop Markings (Sheet 2 of 2)


CASE 1: Mainline Lane Drop to a One Lane Exit



CASE 2: Mainline Lane Drop to a Two Lane Exit (Optional Lane)



CASE 3: Mainline Lane Drop to a Two Lane Exit



NOT TO SCALE

LEGEND

➔ Direction of Travel - - - Lane Drop Pattern

Note: Refer to Part 2 for signs.

**Figure 3B-12. Examples of Applications of Conventional Road Lane-Drop Markings
(Sheet 1 of 2)**




Figure 3B-12. Examples of Applications of Conventional Road Lane-Drop Markings
(Sheet 2 of 2)

B – Auxiliary lane between intersections

Note: See Section 3B.20 for the spacing of pavement markings grouped together to formulate one message.





Figure 3B-13. Examples of Line Extensions through Intersections (Sheet 1 of 2)

A – Typical pavement markings with offset lane lines continued through the intersection



B – Typical pavement markings with line extensions into intersection for double turns





Figure 3B-13. Examples of Line Extensions through Intersections (Sheet 2 of 2)

C – Typical dotted line markings to extend lane line markings into the intersection



D – Typical dotted line markings to extend center line and lane line markings into the intersection






Figure 3B-14. Examples of Applications of Lane-Reduction Transition Markings

A – Lane reduction




B – Lane reduction with lateral shift to the left



* Refer to FHWA's List of Known Errors for errors. Refer to Section 1A.04 for more details.


**Figure 3B-14(CA). Examples of Applications of Lane-Reduction Transition Markings
(Sheet 1 of 3)**



Notes:


1. A W9-1 sign should be used in conjunction with the W4-2 sign.
2. The R4-1 sign should not be used on a freeway or expressway, etc., where two or more lanes remain after a lane is dropped. See Section 2B.36.
3. Lane Reduction Arrows are placed in groups of three. They are optional on highways where speeds are 40 mph or less. Where speeds are 45 mph or more or a W9-1 sign is used, an additional group of arrows may be placed in advance of the W9-1 sign. See also Note 4.
4. Delineators should be spaced approximately 200 ft apart. There should be a minimum of 3 delineators throughout the entire length of a lane reduction transition. See Section 3G.04.
5. A left lane drop should be avoided on undivided roadways because of the difficulty in placing signs to warn motorists in the left lane.

**Figure 3B-14(CA). Examples of Applications of Lane-Reduction Transition Markings
(Sheet 2 of 3)**



Note: The examples in this figure show a median and a merge right condition. When there is no median, Figure 3B-14(CA) (Sheet 1 of 3) should be used because of the difficulty in placing signs to warn the motorist in the left lane.

**Figure 3B-14(CA). Examples of Applications of Lane-Reduction Transition Markings
(Sheet 3 of 3)**



Notes:

1. See Figure 3B-101(CA) for taper and storage lengths. See Detail 37B for lane drop markings. The minimum length of solid channelizing line is 50 ft.
2. The RIGHT LANE TURNS RIGHT AHEAD (W73A(CA)) sign should be placed in conjunction with the RIGHT LANE MUST TURN RIGHT (R3-7) sign and the appropriate lane line and markings. A THRU TRAFFIC MERGE LEFT (W74(CA)) sign may be placed in advance of the W73A(CA) sign. However, adequate sight distance or proximity to a freeway ramp, cross road, etc., may dictate the need and location of additional signs and the length of the turn lane.

Figure 3B-15. Examples of Applications of Markings for Obstructions in the Roadway
(Sheet 1 of 2)





Figure 3B-15. Examples of Applications of Markings for Obstructions in the Roadway
(Sheet 2 of 2)

C – Traffic passing in the same direction on both sides of an obstruction



For speeds of 45 mph or more: $L = WS$
For speeds of less than 45 mph: $L = WS^2/60$
 S = 85th-percentile speed or the speed limit
in mph, whichever is higher
 W = Offset distance in feet

Minimum length of: $L = 100$ feet in urban areas
 $L = 200$ feet in rural areas

Length "L" should be extended as required by
sight distance conditions

Figure 3B-16. Examples of Yield Line Applications




Figure 3B-17. Example of Elongated Letters for Word Pavement Markings



Figure 3B-18. Examples of Elongated Route Shields and Markers Applied as Pavement Markings

**A – Interstate Shield
on dark or
light pavement**



**B – U.S. Route Shield
on dark pavement**



**C – U.S. Route Shield
on light pavement**



~~**D – State Route Marker
on dark pavement**~~



~~**E – State Route Marker
on light pavement**~~



Note: See the “Standard Highway Signs” publication for sizes and details

Figure 3B-18(CA). Examples of California Elongated Route Shields and Markers Applied as Pavement Markings

**D - State Route Shield
on dark or light pavement**




Figure 3B-19. International Symbol of Accessibility Parking Space Marking



Notes:

1. See the "Standard Highway Signs" publication for sizes and details
2. The blue-colored background with white border is optional


Figure 3B-19(CA). International Symbol of Accessibility Parking Space Marking and Related Markings (Sheet 1 of 2)



Notes:

1. The words "NO PARKING" shall be painted in the loading and unloading area in white letters no less than 12 in. high on a contrasting background and located so that it is visible to traffic enforcement officials. Use the FHWA Series Fonts as the official font for all pavement Legends. Adjust the spacing between individual letter pairs (kerning) and adjust the spacing across a whole word or block of text (tracking) to ensure proper visibility, legibility, and continuity of the stencil pieces during the field marking process.
2. Loading and unloading area border shall be marked in blue paint. The hatched lines shall be painted a suitable contrasting color to the parking space. Blue or white paint is preferred.

Figure 3B-19(CA). International Symbol of Accessibility Parking Space Marking and Related Markings (Sheet 2 of 2)



Notes:

1. The words "NO PARKING", shall be painted in white letters no less than 12 in. high on a contrasting background and located so that it is visible to traffic enforcement officials. See Standard Plan A24E for square unit area for painting the legend "NO PARKING".
2. Accessible on-street parking spaces shall not be smaller in length or width than that specified by the local jurisdiction for other parking spaces, but not less than 20 ft in length and not less than 8 ft in width.
3. The hatched lines shall be painted a suitable contrasting color to the parking space. Blue or white paint is preferred.
4. Actual dimensions and curb geometry may differ from that shown. See Standard Plan A90B for additional details.
5. Accessible on-street parking shall comply with CA MUTCD standards, applicable provisions of CVC 22500 through 22526, and California Building Code (CBC), Chapter 11.

Figure 3B-20. Yield Ahead Triangle Symbols




Figure 3B-21. Examples of Standard Arrows for Pavement Markings






Figure 3B-21(CA). Examples of Standard Arrows for Pavement Markings (Sheet 1 of 9)



[illegible]

TYPE V ARROW



7.25 ft

13 ft

1 ft Grid

1 ft

9 ft

15 ft

1 ft Grid

1 ft


Figure 1 shows a U-shaped structure on a 1 ft grid. The structure has a total width of 7.75 ft and a total height of 10 ft. The top horizontal segment is 7.75 ft wide. The vertical segments are 2.5 ft high. The bottom horizontal segment is 1 ft wide. The structure is composed of a U-shaped wall and a central vertical segment.

LEGEND


January 18, 2026

Figure 3B-21(CA). Examples of Standard Arrows for Pavement Markings (Sheet 3 of 9)

A - Optional Lane Use Curved-stem (CS) Arrows



B - Mandatory Lane Use Curved-stem (CS) Arrows




★ Ovals (symbolizing central island) with the arrows should only be used for left lane and single lane approaches to the roundabout

NOT TO SCALE

Note: The design details for various arrows are also shown in Department of Transportation's Standard Plans.

Figure 3B-21(CA). Examples of Standard Arrows for Pavement Markings (Sheet 4 of 9)



NOT TO SCALE


LEGEND

➡ Direction of Travel

Notes:

1. Place Solid Yellow Left Edge Line and One-Way Yellow Retroreflective Pavement Markers on 24 ft centers as shown. Refer to Detail 25A on Figure 3A-105(CA).
2. Place Limit Line as shown. See also Note 7 and refer to Section 3B.19.
3. Place "STOP" legend as shown. Refer to Section 3B.19.
4. Place Solid White Right Edge Line, flared end optional, as shown. Refer to Detail 27B on Figure 3A-106(CA).
5. Place Type V Arrows, in pairs, as shown. Refer to Section 3B.23.
6. Place Type I Arrow as shown. Refer to Section 3B.23.
7. A "YIELD" (R1-2) sign, Yield Line and "YIELD" pavement legend may be used in lieu of the "STOP" (R1-1) sign, Limit Line, and "STOP" pavement legend on low volume roads.

Figure 3B-21(CA). Examples of Standard Arrows for Pavement Markings (Sheet 5 of 9)



NOT TO SCALE


LEGEND

➔ Direction of Travel

Notes:

1. Place Solid Yellow Left Edge Line and One-Way Yellow Retroreflective Pavement Markers on 24 ft centers as shown. Refer to Detail 25A on Figure 3A-105(CA).
2. Place Limit Line as shown. Refer to Section 3B.19.
3. Place "STOP" legend as shown. Refer to Section 3B.19.
4. Place Solid White Right Edge Line, flared end optional, as shown. Refer to Detail 27B on Figure 3A-106(CA).
5. Place Type V Arrows, in pairs, as shown. See Section 3B.23.
6. Place Type I Arrow as shown. See Section 3B.23.
7. A "YIELD" (R1-2) sign, Yield Line and "YIELD" pavement legend may be used in lieu of the "STOP" (R1-1) sign, Limit Line and "STOP" pavement legend on low volume roads.


Figure 3B-21(CA). Examples of Standard Arrows for Pavement Markings (Sheet 6 of 9)



Notes:

1. Place Solid Yellow Left Edge Line and One-Way Yellow Retroreflective Pavement Markers on 24 ft centers as shown. Refer to Detail 25A on Figure 3A-105(CA).
2. Place Limit Line as shown. Refer to Section 3B.19.
3. Place "STOP" legend as shown. Refer to Section 3B.19.
4. Place Solid White Right Edge Line, flared end optional, as shown. Refer to Detail 27B on Figure 3A-106(CA).
5. Place Type V Arrows as shown. Refer to Section 3B.23.
6. Place Type III (L) Arrows, in pairs, as shown when distance permits. Refer to Section 3B.23.
7. Place Type III (R) Arrows, in pairs, as shown when distance permits. Refer to Section 3B.23.
8. Intersection Lane Control (R61(CA) series) signs should be placed on both sides of the exit ramp, at the beginning of the Solid White Line. An additional set should also be placed in advance where distance permits, to alert the motorist of lane use controls ahead. Refer to Figure 2B-4(CA) for appropriate R61(CA) sign selection.


Figure 3B-21(CA). Examples of Standard Arrows for Pavement Markings (Sheet 7 of 9)



Notes:

1. Place Solid Yellow Left Edge Line and One-Way Yellow Retroreflective Pavement Markers on 24 ft centers as shown. Refer to Detail 25A on Figure 3A-105(CA).
2. Place Limit Line as shown. Refer to Section 3B.19.
3. Place "STOP" legend as shown. Refer to Section 3B.19.
4. Place Solid White Right Edge Line, flared end optional, as shown. Refer to Detail 27B on Figure 3A-106(CA).
5. Place Type V Arrow as shown. Refer to Section 3B.23.
6. Place Type III (L) Arrows, in pairs, as shown where distance permits. Refer to Section 3B.23.
7. Place Type II (L) Arrow, as shown where distance permits. Refer to Section 3B.23.
8. Intersection Lane Control (R61(CA) series) signs should be placed on both sides of the exit ramp, at the beginning of the Solid White Line. An additional set should also be placed in advance where distance permits, to alert the motorist of lane use controls ahead. Refer to Figure 2B-4(CA) for appropriate R61(CA) sign selection.
9. A "YIELD" (R1-2) sign, Yield Line and "YIELD" pavement legend may be used in lieu of the "STOP" (R1-1) sign, Limit Line, and "STOP" pavement legend on low volume roads.
10. Place Type II (B) Arrow, as shown. Refer to Section 3B.23.
11. Lane Line Extensions through the intersection may be used, as shown. Refer to Detail 40 on Figure 3A-112(CA).
12. Place Type I (24 ft) Arrows as shown. Refer to Section 3B.23.


Figure 3B-21(CA). Examples of Standard Arrows for Pavement Markings (Sheet 8 of 9)



Notes:

1. Place Solid Yellow Left Edge Line and One-Way Yellow Retroreflective Pavement Markers on 24 ft centers as shown. Refer to Detail 25A on Figure 3A-105(CA).
2. Place Limit Line as shown. Refer to Section 3B.19.
3. Place "STOP" legend as shown. Refer to Section 3B.19.
4. Place Solid White Right Edge Line, flared end optional, as shown. Refer to Detail 27B on Figure 3A-106(CA).
5. Place Type V Arrows as shown. Refer to Section 3B.23.
6. Place Type III (L) Arrows, in pairs, as shown where distance permits. Refer to Section 3B.23.
7. Place Type II (B) Arrow, as shown where distance permits. Refer to Section 3B.23.
8. Place Type II (L) Arrow, as shown. Refer to Section 3B.23.
9. Place Type I (24 ft) Arrow as shown. Refer to Section 3B.23.
10. Lane Line Extensions through the intersection may be used, as shown. Refer to Detail 40 on Figure 3A-112(CA).
11. Intersection Lane Control (R61(CA) series) signs should be placed on both sides of the exit ramp, at the beginning of the Solid White Line. An additional set should also be placed in advance where distance permits, to alert the motorist of lane use controls ahead. Refer to Figure 2B-4(CA) for appropriate R61(CA) sign selection.
12. The Added Lane Symbol (W4-3) sign should be used in lieu of the Merge Symbol (W4-1) sign, when an extra lane is provided of more than 1/2 mile in length.

Figure 3B-21(CA). Examples of Standard Arrows for Pavement Markings (Sheet 9 of 9)



Notes:

1. Place Solid Yellow Left Edge Line and One-Way Yellow Retroreflective Pavement Markers on 24 ft centers as shown. Refer to Detail 25A on Figure 3A-105(CA).
2. Place Limit Line as shown. Refer to Section 3B.19.
3. Place "STOP" legend as shown. Refer to Section 3B.19.
4. Place Solid White Right Edge Line, flared end optional, as shown. Refer to Detail 27B on Figure 3A-106(CA).
5. Place Type V Arrows as shown. Refer to Section 3B.23.
6. Place Type III (L) Arrows, in pairs, as shown where distance permits. Refer to Section 3B.23.
7. Place Type III (R) Arrows, in pairs, as shown where distance permits. Refer to Section 3B.23.
8. Intersection Lane Control (R61(CA) series) signs should be placed on both sides of the exit ramp, at the beginning of the Solid White Line. An additional set should also be placed in advance where distance permits, to alert the motorist of lane use controls ahead. Refer to Figure 2B-4(CA) for appropriate R61(CA) sign selection.
9. Place Type II (B) Arrows, in pairs, as shown where distance permits. Refer to Section 3B.23.
10. Lane Line Extensions through the intersection may be used, as shown. Refer to Detail 40 on Figure 3A-112(CA).
11. Place Type I (24 ft) Arrows as shown. Refer to Section 3B.23.

Chapter 3B – Pavement and Curb Markings (Figures)

Part 3 Markings

Figure 3B-23. Examples of Parking Space Markings




Figure 3B-24. Do Not Block Intersection Markings




Figure 3B-25. Example of the Application of Speed Reduction Markings




Figure 3B-26. Pavement Markings for Speed Humps without Crosswalks




Figure 3B-27. Pavement Markings for Speed Tables or Speed Humps with Crosswalks




Figure 3B-28. Advance Warning Markings for Speed Humps or Speed Tables




Figure 3B-29. Example of Pavement Markings for a Diamond Interchange with a Transposed Alignment Crossroad






Figure 3B-101(CA). Examples of Left-Turn Channelization Markings

4-Lane Roadway



2-Lane Roadway



NOT TO SCALE


$$\text{Approach Taper} = \frac{WS^2}{60} \text{ for speeds of 40 mph or less and } WS \text{ for speeds of 45 mph or more}$$

Where S = Off Peak 85th Percentile Speed in mph
W = Width of Lateral Traffic Shift in feet

Notes:

1. Bay taper length = 60 ft or 90 ft for Business, Residential, and Urban Areas, and 120 ft for high speed Rural Areas.
2. Refer to Striping Details 21 through 23 or 28 through 30.
3. On two lane roads, use Striping Details 21 through 23 for one half (1/2) of the passing sight distance for the prevailing speed.
4. Refer to Striping Detail 38, use a minimum storage length of 50 ft.
5. Refer to Highway Design Manual, Section 405.2 for design details.
6. Based on engineering judgement, intersection of the Approach and Bay Tapers may be located within the width of the left-turn lane.


Figure 3B-102(CA). Examples of Intersection Markings



Notes:


1. The Limit Line is optional; refer to Section 3B.19. The Limit Line on wide side roads on long radius corners may be bent at a $45^\circ \pm$ angle for traffic making a right turn.
2. When a Stop Ahead (W3-1) or STOP AHEAD (W3-1a) sign is used, a STOP AHEAD pavement marking may be placed to supplement the sign according to Section 3B.21.

Figure 3B-103(CA). Treatment for Divided Highway Illusion



Note: Use a Double Yellow Line (Two Direction - No Passing) to discourage wrong way movements at critical locations, such as entering roads or approaches to transitions.


Figure 3B-104(CA). Passing Lanes



Notes:


1. For taper lengths, sign and delineator placement at different speeds, see Figure 3B-12(CA) (Sheet 1 of 3).
2. The R4-1 sign should not be used on a freeway or expressway, etc., where two or more lanes remain after a lane is dropped. See Section 2B.36.
3. To discourage vehicular travel off the traveled way, the Right Edge Line should be continued until there is at least 4 ft between the beginning of the edge line taper and the edge of the traveled way.
4. Delineators should be spaced approximately 200 ft apart. There should be a minimum of 3 delineators throughout the entire length of a lane reduction transition. See Section 3G.04.
5. Lane Reduction Arrows may be placed when a passing lane is 1 mi or more in length.

Figure 3B-105(CA). Examples of Signing and Marking Turnouts



Note: Refer to Detail 27B on Figure 3A-106(CA).

Figure 3B-106(CA). Electric Vehicle Charging Station Pavement Legend Detail



NOT TO SCALE

Note: Use the FHWA Series Fonts as the official font for all pavement Legends. Adjust the spacing between individual letter pairs (kerning) and adjust the spacing across a whole word or block of text (tracking) to ensure proper visibility, legibility, and continuity of the stencil pieces during the field marking process.

Table 3B-1. Minimum Passing Sight Distances for No-Passing Zone Markings

85th-Percentile or Speed Limit	Minimum Passing Sight Distance
25 mph	450 feet
30 mph	500 feet
35 mph	550 feet
40 mph	600 feet
45 mph	700 feet
50 mph	800 feet
55 mph	900 feet
60 mph	1,000 feet
65 mph	1,100 feet
70 mph	1,200 feet