# District 10 Mobility Performance Report

2017 Second Quarter

DEPARTMENT OF TRANSPORTATION

August 15, 2017 : Jaime Q. Quesada

## **District 10 Mobility Performance Report**

## 2017 Second Quarter

## **EXECUTIVE SUMMARY**

## Overview

Caltrans District 10 contains eight counties located within the Central Valley (San Joaquin / Stanislaus / Merced) and the Sierra Nevada (Amador / Calaveras / Tuolumne / Mariposa / Alpine). Over the years detection in Alpine and Calaveras Counties has been sparse, so the District 10 Mobility Performance Report (MPR) no longer includes these two counties in the quarterly or annual analysis.

The MPR quarterly analysis compares information in the current quarter to that of the previous quarter and the quarter one year prior. The following are the performance measures reported in the MPR:

- Vehicle Miles Traveled (VMT)
- Vehicle Hours of Delay (VHD)
- Lost Lane Miles (LLM)
- Detector Health (DH)

This information is based on data collected every day of the quarter, twenty—four hours a day, by automated vehicle detector stations deployed on urban-area freeways where congestion is regularly experienced. The MPR presents congestion information at two speed thresholds: delay from vehicles traveling below 35 miles per hour (mph), and delay from vehicles traveling below 60 mph. The delay at the 35 mph threshold represents severe congestion while delay at 60 mph

represents all congestion, both light and heavy. These thresholds are set by Caltrans and are based upon engineering experience and District input.

#### **FINDINGS**

In the second quarter, total delay equaled 73 thousand vehicle hours of delay (VHD) at the 35 mph speed threshold (45.3% decrease over one year ago; 11.3% decrease over last quarter), and 320 thousand VHD at the 60 mph threshold (35.3% decrease over one year ago; 7.8% increase over last quarter). The average weekday delay experienced in this quarter was approximately 1,105 VHD at 35 mph (40.6% decrease over one year ago; 8.4% decrease over last quarter), and 4,170 VHD at 60 mph (25.5% decrease over one year ago; 32.4% decrease over last quarter). The decreases in VHD can be attributed to completion of the I5 widening which included HOV lanes, SR 99 South Stockton Widening, and SR 99 Manteca Widening projects.

# Top Ten Bottlenecks for 2017 Quarter 2

FWY	COUNTY	LOCATION	SHIFT	ABS. PM	CAPM	# DAYS ACTVE	AVG. EXTENT (MILES)	TOTAL DELAY (VEH-HRS)	TOTAL DURATION (MINS)
1205-VV	SJ	E of Hansen Rd	AM	3.310	2.380	54	4.9	120872	8410
SR99-S	STA	Kansas Ave	PM	227_834	R16.799	45	1.5	9665	4000
SR99-S	SJ	N/O Jack Tone Rd	PM	238.974	3.189	49	0.4	4146	6265
SR99-S	SJ	S/O Austin Rd OC	PM	240_425	4.640	52	0.2	3974	7360
SR99-S	SJ	S/O Rte 120	PM	241.202	5.417	45	0.6	3798	5065
SR219-W	STA	E/O SR 99	PM	0.092	0.168	24	2.3	1158	1720
15-N	SJ	N/O French Camp Rd	PM	468_140	R22.648	34	0.2	502	1975
SR219-W	STA	E/O SR 99	AM	0.092	0.168	13	2.3	408	445
SR99-N	SJ	N/O E.Hammer Lane OC	AM	258_860	23.050	23	0.6	398	1780
15-S	SJ	N/O French Camp Rd OC	AM	468.057	R22.565	10	0.4	301	385

The following District 10 projects are currently being constructed or are scheduled for construction effective August 2017. These current and future (planned) projects will further relieve congestion in District 10:

## **MERCED COUNTY**

MER 99 MISSION AVENUE INTERCHANGE / FREEWAY; EA 10-36311

Convert from 4 lane expressway to 6 lane freeway on an 8 lane right of way Approve Construction Contract Date – 04/07/2008 End Project – 04/02/2018

## MER 99 NB LIVINGSTON MEDIAN WIDENING; EA 10-0Q121

Lane widening from 2 to 3 lanes Approve Construction Contract Date – 08/01/2021 End Project – 10/02/2023

## MER 99 SB LIVINGSTON MEDIAN WIDENING; EA 10-0Q122

Lane widening from 2 to 3 lanes Approve Construction Contract Date – 01/19/2019 End Project – 10/01/2021

## MER 152 – LOS BANOS BYPASS SEGMENT I; EA 10-41911

Convert 4 lane expressway to 6 lane freeway Approve Construction Contract Date – 05/15/2018 End Project – 10/01/2020

## SAN JOAQUIN COUNTY

# SJ 4 RAMP METERING IMPROVEMENTS; EA 10-1F180

Install ramp meters along SR 4 between the I-5 and SR 99 Connectors Currently in PRS/PDS; PA&ED Scheduled for mid-2016 End Project – Estimated to be mid 2020

## SJ 99 – SOUTH STOCKTON WIDENING; EA 10-3A100

Widen existing freeway from 4 to 6 lanes Approve Construction Contract Date – 12/3/2012 End Project – 12/5/2017

## SJ 120 RAMP METERING IMPROVEMENTS; EA 10-1F040

Install ramp meters along SR 4 between the I-5 and SR 99 Connectors Currently in PRS/PDS; PA&ED Scheduled for mid-2016 End Project – Estimated to be mid 2020

## I-205 SMART CORRIDOR PHASE 2; EA 10-1C330

Install ramp meters and ITS elements along I205 from MacArthur to Grant Line Road Currently in PA&ED End Project -11/01/2021

## STANISLAUS COUNTY

## STA 99 – PELANDALE INTERCHANGE; EA 10-47210

Modify Existing Interchange Approve Construction Contract Date – 4/15/2014 End Project – 12/1/2017

## STA 99 – KIERNAN INTERCHANGE; EA 10-0L330

Reconstruct Interchange Approve Construction Contract Date – 2/1/2013 End Project – 11/30/2017

## STA 99 / SJ 99 RAMP METERING & MAINLINE IMPROVEMENTS; EA 10-1C300

Improve Mainline and Ramp Operations; Standardize Structure Clearance; Add Auxiliary Lane Currently in PA&ED

End Project – Estimated to be mid 2020


The above capacity increasing, ramp metering, interchange improvement, and interchange construction projects are located on the routes, in the cities, and in the counties that experience the most congestion in District 10. It is expected that the projects will help increase the Vehicle Miles Traveled while reducing congestion and delay as the population and demand in District 10 grows over the next 10 years.

The next section of this report summarizes the District 10 2017 Q2 Quarterly Mobility Statistics.


## 2017 Q2 Quarterly Mobility Statistics - District 10

Data may change in coming months due to on-going data reconciliation process





## Data may change in coming months due to on-going data reconciliation process



Data may char	nge in comi	ng months due to	on-going	data reconciliation :	process
---------------	-------------	------------------	----------	-----------------------	---------

Congestion by Route											
		Vehicle Hours of Delay at 35 mph		Difference 2017 Q2-2016 Q2		Difference 2017 Q2-2017 Q1		Rank			
Route	County	2016 Q2	2017 Q1	2017 Q2	Absolute	Percentage	Absolute	Percentage	2016 Q2	2017 Q1	2017 Q2
1205	San Joaquin	285,784	119,552	188,203	-97,581	-34.1%	68,651	57.4%	1	1	1
SR99	San Joaquin	47,605	68,896	37,376	-10,229	-21.5%	-31,520	45.8%	2	2	2
SR99	Stanislaus	13,575	2,946	18,271	4,696	34.6%	15,325	520.1%	4	5	3
I580	San Joaquin	16,416	42,247	6,839	-9,576	-58.3%	-35,408	-83.8%	3	3	4
I5	San Joaquin	2,745	960	3,417	672	24.5%	2,457	255.8%	7	7	5
SR219	Stanislaus	0	3,522	2,797	2,797		-725	-20.6%		4	6
SR132	San Joaquin	0	476	2,582	2,582	2582200.0%	2,106	442.4%	12	8	7
SR4	San Joaquin	9,798	320	1,017	-8,781	-89.6%	697	217.7%	5	9	8
SR99	Merced	7,099	1,552	710	-6,389	-90.0%	-842	-54.2%	6	6	9
SR120	San Joaquin	0	203	502	502		299	147.7%		10	10
15	Merced	5	0	0	-5	-100.0%	0		11		
I5	Stanislaus	973	11	0	-973	-100.0%	-11	-100.0%	8	12	
SR104	Amador	0	0	0	0		0				
SR108	Tuolumne	0	0	0	0		0				
SR12	San Joaquin	0	0	0	0		0				
SR120	Tuolumne	0	0	0	0		0				
SR152	Merced	835	10	0	-835	-100.0%	-10	-100.0%	9	13	
SR49	Mariposa	205	25	0	-205	-100.0%	-25	-100.0%	10	11	
TOTALS		385,039	240,720	261,714	-123,326	-32.0%	20,994	8.7%		-	

SR 219 Stanislaus: No delay detected in 2016 Q2 SR 132 San Joaquin: No delay detected in 2016 Q2 SR 120 San Joaquin: No delay detected in 2016 Q2 I5 Merced: No delay detected in 2017 Q1 and 2017 Q2

I5 Stanislaus: No delay detected in 2017 Q2

SR 104 Amador: No delay detected in 2016 Q2, 2017 Q1, and 2017 Q2 SR 108 Tuolumne: No delay detected in 2016 Q2, 2017 Q1, and 2017 Q2 SR 12 San Joaquin: No delay detected in 2016 Q2, 2017 Q1, and 2017 Q2 SR 120 Tuolumne: No delay detected in 2016 Q2, 2017 Q1, and 2017 Q2

SR 152 Merced: No delay detected in 2017 Q2 SR 49 Mariposa: No delay detected in 2017 Q2